

BOQ FOR INTERIOR WORK FOR SBI AT RBO-07 SULTANPUR.					
All rates of items are excluding G.S.T. The Contractor should quote the rates exclusive of G.S.T.					
S.N	DESCRIPTION OF ITEM	Unit	Quantity	Unit Rate	Amount
1	COMPUTER CLERICAL COUNTER WITH 01 MM MICA ON TOP				
	Manufacturing, supplying and fixing of computer counter made to shape as per approved design / drawing / size (5 ft. approx. W x 2.5 ft. H x 2.5 ft. D) and made of 19 mm BWR grade ISI board and double moulding at front side of top & have lamination on top with 1mm thickness of approved brand, round moulding on front of counter both sides post-formed and other places 01mm laminate of make ISI branch Sunmica, Century, green or equivalent finish as per the layout joint free at front and top potation and as per the standard design , Each counter shall be provided with 3 drawers in telescopic channel and matching mica. All internal faces shall be painted with white enamel paint including inside of drawers readymade MS CPU stand complete to the satisfaction of Architect/Bank's Engineer.(This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.) .	RMT	0.00		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
2	FULL HEIGHT BLOCKED PARTITIONS				
	Providing & fixing in position metal stud dry wall partition with the following specifications: a) Framing shall consist of existing aluminium partation or Aluminum/wooden/existing aluminium s Section 50 mm*50mm(Wall thickness 2 mm) @ 2'0" C/C Both ways Horizontally and Vertically, quality of workmanship top class tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. b) 06 mm BWR grade ISI ply fixed on both sides with 25 mm dry wall screws. c) 01mm laminate of make ISI branch Sunmica Century, green or equivalent finish as per the layout joint free at front and top potation on both sides (dark for bands, light for body) up to false ceiling level. d) 05 mm thick clear float glass with etching design as directed between 1200 X2000 mm level in specified areas fixed with 85 X 15 mm beech wood jamb and 12 X 12 mm beech wood beading at edge provide wooden polished beading 03 inch X 06mm min. e) All beech wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment complete to the satisfaction of Architect/ Bank's Engineer. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.) .	SQ.MTR	163.00		INR 0.00
	Make				
	Aluminium Section - Jindal, Indal, Balco				
	Plywood & MDF - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
3	PARTLY GLAZED WOODEN FULL HEIGHT PARTITIONS 05 MM GLASS (up to 8Ft High)				

	<p>Providing & fixing in position metal stud dry wall partition with the following specifications:</p> <p>a) Framing shall consist of existing aluminium partation or Aluminum/wooden/existing aluminium s Section 50 mm*50mm(Wall thickness 2 mm) @ 2'0" C/C Both ways Horizontally and Vertically, quality of workmanship top class tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings.</p> <p>b) 06 mm BWR grade ISI ply fixed on both sides with 25 mm dry wall screws.</p> <p>c) 01mm laminate of make ISI branch Sunmica Century, green or equivalent finish as per the layout joint free at front and top potation on both sides (dark for bands, light for body) up to false ceiling level.</p> <p>d) 05 mm thick clear float glass with etching design as directed between 1200 X2000 mm level in specified areas fixed with 85 X 15 mm beech wood jamb and 12 X 12 mm beech wood beading at edge provide wooden polished beading 03 inch X 06mm min.</p> <p>e) All beech wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment complete to the satisfaction of Architect/ Bank's Engineer. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	SQ.MTR	10.00		INR 0.00
	Make				
	Aluminium Section - Jindal, Indal, Balco				
	Plywood & MDF - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Plain Glass - Saint Gobain, Modi & Equivalent				
4	PARTLY GLAZED WOODEN LOW HT PARTIONS 12MM Glass				
	<p>Providing & fixing in position metal stud dry wall partition with the following specifications:</p> <p>a) Framing shall consist of existing aluminium partation or aluminium partition or Aluminum/wooden Section 50 mm*50mm (Wall thickness 2 mm) @ 2'0" C/C Both ways Horizontally and Vertically, quality of workmanship top class tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings.</p> <p>b) 06 mm BWR grade ISI ply fixed on both sides with 25 mm dry wall screws.</p> <p>c) 01mm laminate of make ISI branch Sunmica Century, green or equivalent laminate on both sides (dark for bands, light for body) up to false ceiling level.</p> <p>d) 12 mm thick clear float glass with etching design as directed between 900 X1200 mm level in specified areas fixed with 85 X 15 mm beech wood jamb and 12 X 12 mm beech wood beading at edge provide wooden polished beading 03 inch X 06mm min..</p> <p>e) All beech wood members to have melamine polish finish. Length X height up to 1350 mm will be measured for payment</p> <p>Note: Surface measurement for one face & visible areas below false ceiling will be made for payment. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	SQ.MTR	60		INR 0.00
	Make				
	Aluminium Section - Jindal, Indal, Balco				
	Plywood & MDF - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Plain Glass - Saint Gobain, Modi & Equivalent				
5	RM Table with 01mm mica and 12mm glass (Size 1800 X 900 X 750 mm)				

	<p>Providing, making & placing in position executive table with the following specifications:</p> <p>a) Table top made in 19 mm BWR grade board post-formed on two edges, all other members with 18/19 mm BWR grade board double moulding at front side of top with 01mm laminate of make ISI branch Sunmica Century, green or equivalent laminate, all edges to have 20 X 6 mm beech wood lipping.</p> <p>b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc.</p> <p>c) One ready made mobile CPU pedestal.</p> <p>d) One MS key board tray with channels to be provided e) One foot rest</p> <p>f) Side table post-formed with shutters to be made with 19mm BWR grade board with pf laminate or top and other members with 18/19 mm BWR grade board & 01 mm laminate with necessary hardware viz: cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech wood beading and 20 X 6 mm beech wood lipping etc.</p> <p>g) All the exposed surfaces to have 1.0 mm laminate of approved shade and brand. 12mm thick Toughened glass for the modesty panel with specified itching with Blue colour. All unexposed surfaces to have two coats of enamel paint with putty. All wooden members to have melamine polish.</p> <p>complete to the satisfaction of Architect / Bank's Engineer.</p> <p>Note: Rate shall be inclusive of cost of cutting hole complete. (COLOUR OF CORIAN: WHITE, if applicable) (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	NOS	1		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
6	Manager's table with 01mm mica and 12mm glass (Size 1500 X 900 X 750 mm)				
	<p>Providing, making & placing in position executive table with the following specifications:</p> <p>a) Table top made in 19 mm BWR grade board post-formed on two edges, all other members with 18/19 mm BWR grade board double moulding at front side of top with 01mm laminate of make ISI branch Sunmica Century, green or equivalent laminate, all edges to have 20 X 6 mm beech wood lipping.</p> <p>b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc.</p> <p>c) One ready made mobile CPU pedestal.</p> <p>d) One MS key board tray with channels to be provided e) One foot rest</p> <p>f) Side table post-formed with shutters to be made with 19mm BWR grade board with pf laminate or top and other members with 18/19 mm BWR grade board & 01 mm laminate with necessary hardware viz: cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech wood beading and 20 X 6 mm beech wood lipping etc.</p> <p>g) All the exposed surfaces to have 1.0 mm laminate of approved shade and brand. 12mm thick Toughened glass for the modesty panel with specified itching with Blue colour. All unexposed surfaces to have two coats of enamel paint with putty. All wooden members to have melamine polish. complete to the satisfaction of Architect / Bank's Engineer.</p> <p>Note: Rate shall be inclusive of cost of cutting hole complete. (COLOUR OF CORIAN: WHITE, if applicable). (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	NOS	5		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				

7	WORK STATION TABLE (Size :- 5'-0" x 5'-0" x 2'-0") ht. 2'-6" :- Providing and fixing of WORK STATION 2'-0" wide top and length 4'-6" made up of 19mm board pasted on 1.0 mm thk. laminate. The Top of table will be finish with 1.00 thk laminate.all hardware fittings fixtures etc. The drawers to be made out of 19mm thk board with 1.0 mm laminate finish in the front ,sides to be made out of 12mm plywood and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint. All exposed edges to have wooden lipping stained to match the desk and melamine finished.Design and detail of the table shall be as per Bank design. (As per Site, Designing of Table and specification may be Changed). The works to include a keyboard try and CPU trolley to be modular, All as per the design and instructions Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	12		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
8	WORK STATION TABLE (Size :- 4'-6" x 2'-0") ht. 2'-6" :- Providing and fixing of WORK STATION 2'-0" wide top and length 4'-6" made up of 19mm board pasted on 1.0 mm thk. laminate. The Top of table will be finish with 1.00 thk laminate.all hardware fittings fixtures etc. The drawers to be made out of 19mm thk board with 1.0 mm laminate finish in the front ,sides to be made out of 12mm plywood and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint. All exposed edges to have wooden lipping stained to match the desk and melamine finished.Design and detail of the table shall be as per Bank design. (As per Site, Designing of Table and specification may be Changed). The works to include a keyboard try and CPU trolley to be modular, All as per the design and instructions Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	6		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
8	Meeting Table of Size Dia :- 3'-0"	No.	1		INR 0.00
	Supplying and fixing Table Top to be made with 25mm thick Plywood 180 degree (full round to oval shape as per drawing) post formed edges on two sides of appoved post forming laminate shade and colour. 19mm thick BWR plywood frame work in vertical's, horizontal's and footrest. All exposed surfaces, Table top, and front apron finished with 1mm thick laminate and skirting finished with combination of 1mm thick laminate . Internal surfaces finished with 1.0mm thick laminate colour of approved brand. Plywood edges to be finished with edge band of approved colour. The top should be provided with necessary cutouts and closers for the wirings. The pedestals shall be provided with necessary bottom support and 90 degree lug-support for the structure as required making the frame intact and free from any type of play/movement. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per drawings and instructions of the Architect/Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).				
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
9	Conference Table of size 20 feet X 5 feet in oval shape.				

	Supplying and fixing Table Top to be made with 25mm thick Plywood 180 degree (full round to oval shape as per drawing) post formed edges on two sides of approved post forming laminate shade and colour. 19mm thick BWR plywood frame work in vertical's, horizontal's and footrest. All exposed surfaces, Table top, and front apron finished with 1mm thick laminate and skirting finished with combination of 1mm thick laminate. Internal surfaces finished with 1.0mm thick laminate colour of approved brand. Plywood edges to be finished with edge band of approved colour. The top should be provided with necessary cutouts and closers for the wirings. The pedestals shall be provided with necessary bottom support and 90 degree lug-support for the structure as required making the frame intact and free from any type of play/movement. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per drawings and instructions of the Architect/Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	Nos	1		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
10	CUPBOARDS / STORAGE UNITS OF 2.5 FT. (0.75 mtrs) HT.				
	Providing, making and placing in position low height storage units up to 750 mm height or height as directed and 450 mm deep made with 18/19 mm mm BWR grade board front sides and middle shelf and back side with 12 mm mm BWR grade ISI ply covered with 01mm laminate of make ISI branch Sunmica Century, green or equivalent laminate (dark for bands and light for body) at all exposed surfaces. The top shall have 19 mm mm grade board board 'post-formed' edge with lamination,Inner/unexposed surfaces to be painted with two or more coats of enamel paint with putty finish including melamine polish finish for all Wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	RMT	30		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
11	CUPBOARDS / STORAGE UNITS OF 5 FT. (1.53 mtrs) HT.				
	Manufacturing, supplying and fixing of box type cupboards / storage units of required, sizes and as shown in the drawing and of 1' 5" depth and made out of 19 mm thick Plywood all-round and 8 mm Plywood of approved make at the back. The 19mm Plywood shelves / compartments shall be provided at 15" c/c horizontally and 3' 0" c/c vertically. The unit shall have hinged type shutters on the front made out of 19 mm Plywood with approved quality concealed hinges, locks tower bolts, knobs all as per approved quality. All external surfaces to be laminated with 01mm laminate of make ISI branch Sunmica Century, green or equivalent laminate and all internal surfaces to be laminated with approved shade & make. Front edges of shelves and all exposed edges of plywood to be leaped with teak wood finished with polish. Footing to be made of 2.5" x 1.5" wood frame covering all four sides of bottom surface and covered with 6 mm Plywood of approved make and 01 mm thick laminate of same shade . complete to the satisfaction of Arcs of the Architect/Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	RMT	25		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
12	CUPBOARDS / STORAGE UNITS OF 8 FT. (2.44mtrs) HT.				

	Manufacturing, supplying and fixing of box type cupboards / storage units of required, sizes and as shown in the drawing and of 1' 5" depth and made out of 19 mm thick Plywood all-round and 8 mm Plywood of approved make at the back. The 19mm Plywood shelves / compartments shall be provided at 15" c/c horizontally and 3' 0" c/c vertically. The unit shall have hinged type shutters on the front made out of 19 mm Plywood with approved quality concealed hinges, locks tower bolts, knobs all as per approved quality. All external surfaces to be laminated with 01mm laminate of make ISI branch Sunmica Century, green or equivalent laminate and all internal surfaces to be laminated with approved shade & make. Front edges of shelves and all exposed edges of plywood to be leaped with teak wood finished with polish. Footing to be made of 2.5" x 1.5" wood frame covering all four sides of bottom surface and covered with 6 mm Plywood of approved make and 01 mm thick laminate of same shade . complete to the satisfaction of Arcs of the Architect/Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).. All wooden members to have melamine polish. complete to the satisfaction of Architect / Bank's Engineer.	RMT	10		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
13	WOODEN CLADDING/WALL PANELLING (Frame work /08mm ply)				
	Providing, and fixing of wall/column paneling made with 08mm ISI grade board with 01mm laminate of make ISI branch Sunmica Century, green or equivalent thick lamination over Gypsteel / Boral makes 51mm x 35mm metal studs/ Tube section of min 2"*1.5" as detailed in (Full height partition) above. The rate should be inclusive of providing texture painting in between and providing steam beach cornice between paneling and texture paint. The necessary provision in paneling (3"x1.5" box in manager cabin from false ceiling to table) for running of Electrical conduit has to be made. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	200.00		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Aluminium Section - Jindal, Indal, Balco				
14	ACP WALL PANELLING (FAÇADE OF MAIN ENTRANCE)				
	Providing & Fixing in position Aluminum Composite Panel (ACP) with framing of Aluminum Tube section of min 1.5"*1" and 20 gauges 2'-0"c/c both ways. ACP to be in 2' width panels or distributed equally panels to be fixed to the frame with 3M or equivalent adhesive with Mirror screws joints to be finished with Silicon base sealant ACP thickness shall be minimum 3 mm. Aluminium foil thickness to be minimum 0.25 on both side . Alubond , Eurobond , Fujibond , Alcobond ,or equivalent ISI approved brands to be used. Bright Silver Shade/colored to fix the indoor AC UNITS both the AC units to be installed near the machine area at the highest Position with bulkit.complete to the satisfaction of Architect/Bank's Engineer. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	15		INR 0.00
	Make:-				
	ACH Sheet :- Alucobond/Eurobond/Alstrong/Alstone				
	Aluminium Section - Jindal, Indal, Balco				
15	Dining Table OF SIZE (8'x3')				

	Supplying and fixing Table Top to be made with 25mm thick Plywood 180 degree (full round) post formed edges on two sides of appoved post forming laminate shade and colour. 19mm thick BWR plywood frame work in vertical's, horizontal's and footrest. All exposed surfaces, Table top, and front apron finished with 1mm thick laminate and skirting finished with combination of 1mm thick laminate . Internal surfaces finished with 1.0mm thick laminate colour of approved brand. Plywood edges to be finished with edge band of approved colour. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per drawings and instructions of the Architect. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	Nos	1		INR 0.00
	Make:-				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Godrej, Hafele, Dorset, Ozone				
	FALSE CEILING				
16	ARMSTRONG TILE CEILING				
	Providing and fixing False Ceiling with Mineral Fibre Accoustic Ceiling Tiles of Armstrong with with narrow reveal (NR/E), having noise reduction properties laid on exposed grid system with 15mm side SilhoutteXL 6mmtype black inside 'T'section flanges of white colour, main runners spaced at 1200mm centers securely fixed to the structure soffit with approved hangers at 1200mm max. centers, 1200mm flush fitting crossed tees interlocked between main runners at 600mm centers to form 1200x600 modules. 1200mm cross tees shall be crimped in 600x600mm module formed by fixing 600mm long flush fitting cross tees centrally between the 1200 cross tees, ceiling tiles of visual pattern tiles 8581M/Dunne premier miro look of size 600x600x12mm placed in the grid et c. complete to the satisfaction of Architect/Bank's Engineer. Note: Rate shall include making necessary cutouts or openings for light fixtures etc. complete. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	130.00		INR 0.00
	Make				
	600 x 600 Tiles - Armstrong /Gyproc/knauff , Grid - Armstrong/ Boaral/ Diamond				
17	GYPSUM BOARD CEILING				
	Providing and fixing 12.5mm thick Gypsum Ceiling Board False Ceiling in horizontal, vertical surfaces moulded corners & offsets as per architectural drawing which shall include providing and fixing roll formed G.I. perimeter channels of sizes27x.5mm thick having one flange of 30mm along the perimeter of the ceiling fixed to the brick wall or partition with help of rawl plug or screw including ending of G.I.intermediate channels of size 45x9mm thick with two flanges of 15mm thick each from the soffit @1200mm c/c with steel /G.I.hanger of width 25mm & 0.5mm thickness fixed to soffit with G.I.cleat & steel expansion fasteners of 0.5mm thickness having knurled wedge of 51.5mm, two flanges of 26mm each with tips of 10.5 mm fixed to the intermediate channel with the help of converting clips in a direction perpendicular to the intermediate channel of 350mm c/c 12.5mm taper edge gypsum plaster board confirming to I.S.: 2095,1982 shall be screwed at 230mm c/c with screw fixing done mechanically with suitable attachment of the tapered & squared edges of the boards as recommended by the manufacturer finished with two or more coats of oil bound distemper over acoat of primer. Item includes extra frame work for necessary hatch doors/ opening upto 600mmx600mm or as per requirement with 19mm commercial board wherever required including necessary brass hinges, screws & finish smooth as directed The rate shall include the cost of extra frames for A.C openings light fixtures,speakers & coves etc.complete to the satisfaction of Architect/ Bank's Engineer. Note: Only horizontal base area shall be measurement for payments. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	240		INR 0.00
	Make				
	Gypsum Board- Saint Gobain, Boral, Sakrani				

	GI Channel - Gyp steel/IGL/Diamond/Ultra				
	Paint - Berger/ Asian/ Nerolac				
18	Door with Fixed Glazing				
	Providing and fixing 12 mm thick, toughened glass, etched Door, inclusive of Providing and fixing 12mm thick toughened, fixed, side glazing panels with etching same as Door and with frameless fittings of DORMA make or equivalent, with following parts, viz: SM1040 forover/side panel, SM 1041 connector for side/upper panel, SM 1020 upper patch, SM 1010 bottom patch, SM 1049 E floor lock, SM 1052 strike plate BTS 84 or equivalent, floor spring including Providing and fixing of DORMA make handles TG 9159 EQ-S or equivalent as per approved design, grinding & polishing smooth of glass edge with cutting & making good the floor wherever required etc complete to the satisfaction of Architect/ Bank's Engineer. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).				
	Make				
	Patch Fitting - Ozone / Godrej / Dorset.				
	Plain Glass - Saint Gobain, Modi & Equivalent				
a	Toughened Glass Door all accessories as required only.	SQ.MTR	23		INR 0.00
b	Fixed Glazing	SQ.MTR	15		INR 0.00
19	Providing and fixing 12mm thick clear Glass in front of public counters, cash counters & elsewhere held together with SS clamps & SS studs as per approved sample including providing and fixing steam beach beadings (18x18mm), steam beach moulding (62x31mm) along with polish & melamine spray finish etc. complete. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	0		INR 0.00
	Make				
	Plain Glass - Saint Gobain, Modi & Equivalent				
20	Vertical Blinds -Providing & fixing MARVEL/Vista make as approved by Bank's Engineer/Architect with runner, thread and other accessories. Note: Payment will be made on the basis of brickwork opening.(Make : Vista) (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	45		INR 0.00
	Make				
	Vertical Blinds - Vista/ MAC/ DACK				
21	PIN-UP BOARDS Providing and fixing pinup boards. It consist ½” soft boards of good density to be mounted over ½” ply. The soft board will be covered with a plain fabric approved blue color (approx Rs.150 /Rmts.) from front and edges. Suitable laminated border (as directed by architect) will be fixed on all four sides and. Note : Only soft boards provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	15		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
22	Providing and fixing Frosted Film Over Glass as per drawing or instruction of Bank/Architect (approved Make). (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	50		INR 0.00
	Make				
	3M / S-Plus				
23	Providing and fixing Lacquered Glass at wall paneling(Mainly) in blue color.(coated Rate should be exclusive of mica). (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQ.MTR	20		INR 0.00
	Make				

	Plain Glass - Saint Gobain, Modi & Equivalent				
24	Pantry Storage (Shutters under Platform)				
	<p>Providing and fixing Storage under Platform made of 18mm thk. FIRESAFE IS: 5509 plywood sheet finish with 1mm thick high glossed laminate sheet on outer face and 1mm thick white laminate sheets on inner face of the shutter; edge to be covered with aluminum profile section as per selection, shutters to have soft close hinges (Hettich/Dorma/Hafele) with teak wood frame below platform. Item to be inclusive of 19mm thick interal horizontal laminated shelves, joining cleats, accessories, ss hardware, soft close drawer with ss basket, aluminum profile handles etc. complete. In side of storage to be finished with 1mm thick laminate etc. complete to the satisfaction of Architect/Bank's Engineer.</p> <p>(Measurement will be counted from front shutter's height & width, no extra measurement and payment will be given for ss basket & shelves).</p> <p>(Base price of laminate to be used to be Rs. 50/ sq.ft.). (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	RMT	5.00		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
25	Pantry Storage (Overhead Unit)				
	<p>Providing and fixing Over Head Storage made of FIRESAFE IS: 5509 plywood sheet inside laminate finish with required 19mm thick aluminium profile shutters with back painted glass, required soft closing hinges (hettich/ haffle/ dorma) & glass shelves. Item to be inclusive of all accessories, storage shelves, lift up sutters, design grooves, moulded edges, aluminum profile, soft close hinges etc. complete. Inner side of the storage to have 1mm thick laminate finish etc. complete to the satisfaction of Architect/ Bank's Engineer.</p> <p>(Base price of laminate to be used to be Rs. 50/ sq.ft.). (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	RMT	5		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
	MISCELLANEOUS WORKS				
26	<p>Providing and fixing GODREJ NIGHT LATCH in Doors of Cash Counters, Cash Deptt. & System. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	NOS	0		INR 0.00
	Make				
	Lockes :- Godrej, Hafele, Dorset, Ozone				
27	<p>Providing 90cm diameter 90cm high seif supported writing ledge with 4 nos.6"X 6" pigeion holes in center made of 18 mm commercial board and 0.8 mm mica, wood beading, polishing etc. Complete. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	NOS	0		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
28	<p>Poster frames wall Hung</p> <p>2 Sheets of 900 mm X 600 mm clear acrylic (poster to be sandwiched in between). Outer sheet in 5mm thick and beveled crystal edge polished for 19 mm at 8-10 degrees on all sides in the front. Rear sheet is 5 mm thick flat. Rate inclusive of S1 grade aluminum/steel studs. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).</p>	NOS	4		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				

	Laminate - Century/Merino/Greenlam/Aica				
29	Providing and fixing M.S. truss for cashroom storage; grills door of required pattern in MS frames of door / windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer & MS, required embedding using mortar etc. all complete.(to be fixed inner side of the entrance). (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	kg	0		INR 0.00
30	Semi Glazed Door (3'-0"x7'-0") :- Providing and fixing made in 35mm thick Flush door with 1mm lamination form both sides and 8mm plain glass with Etching / Acid texture border fixed with Steam beach molding duly melamine polished. 35mmX 12mm steam beach Lipping to be provided to all the edges of the door . Rate also to include the cost of Door Frame made Steam beach wood fixed in partition or wall.. Door Frame should be fixed properly to the Partitions, All Hardware should be of Brass / SS Brush finish with ISI mark. Hardware includes Concealed Door closer, Cylindrical Lock, Door stopper and other standard needs. All as per the design and instructions Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQM	12		INR 0.00
	Make				
	Plain Glass - Saint Gobain, Modi				
	Lockes with SS Handles - Hafele, Godrej, Hettich				
	Door Closer - Godrej, Hafele, Dorset, Ozone				
	Hinges - Hafele/Hafele/Godrej				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
31	Solid Flush door: Providing and fixing 30 mm thick flush door with 10 mm thick teakwood lipping on all sides finished in 1 mm thick laminate on both sides of approved shade 'UGM' Frosty White/ Bleached Teak of make Archidlam/ equivalent shade in approved make with all necessary hardware including SS door handle, SS stopper, lock, door closer, SS heavy duty butt hinges etc. of make Dorma/ Hettich/ Hafele all complete as per directions of Architect/ Bank. Item to include 2 coat of Fire retardant paint Viper of navair/ approved equivalent. ♦necessary wood frame of 2nd class teak wood (size 75 X75) to be provided all around for fixing of shutters. The frame to be fixed with partition or wall with holdfast / GI fastner. The wooden frame is to be finished with enamel paint (smooth finished base, free from all defects); shade as per approved by architect. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	Sqm	14.00		0.00
	Make				
	Lockes with SS Handles - Hafele, Godrej, Hettich				
	Door Closer - Godrej, Hafele, Dorset, Ozone				
	Hinges - Hafele/Hafele/Godrej				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
31	Providing and fixing glazed Aluminium Door of required size made up of 83.5mm wide vertical members, 85-90mm wide top and bottom members and 83.5mm wide middle member. Members to be of aluminium with power coating and of black shade. Thickness of the section of the aluminum sheet forming the members to be not less than 1.5mm. Item includes proving 8mm thick clear float glass of Modifloat/ Saint Gobain/ Asahi make in the aluminum door along with all accessories as may be required. Item also includes providing Godrej/ Dorma/ Haffle make 100kg weight floor spring with 0.3 million cycles rating along with pivot of same make on top and Godrej make heavy duty lock in the aluminum door. Item includes providing wool pile/ weather strip on the un-pivoted vertical member of the door and a customized door handle of approved colour to fit on the aluminium sections etc. complete. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQM	0.0		INR 0.00
32	Providing and fixing readymade M.S. steel keyboard in Cash Counters, Cash Deptt. & System. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	25		INR 0.00

	Make				
	Steel keyboard- Ebco or & Equivalent				
33	Providing and fixing self locking lock of "Godrej" multilatch in drawers or equivalent. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	50		INR 0.00
	Make				
	Lockes :- Godrej, Hafele, Dorset, Ozone				
34	Providing and fixing self-locking cylindrical lock of "Godrej" or equivalent for doors. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	10		INR 0.00
	Make				
	Lockes :- Godrej, Hafele, Dorset, Ozone				
35	Providing and fixing door closer Godrej/Amar/Everite for doors. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	10		INR 0.00
	Make				
	Door Closer :- Godrej, Hafele, Dorset, Ozone				
36	Providing and laying imported Rubber Door Mats of approved shade. Size : 2400X1200mm as per the selection of Architect/ Bank's Engineer. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	NOS	1		INR 0.00
37	MAIN ELECTRICAL PANEL STORAGE:- Providing and fixing of Main panel storage of 19mm thick Commercial ply shutter of approved make finished with laminate on outer surface 1.0 Thk. 12.5 mm thick cement based bison board finish on all internal surface with stainless steel louver of (SS 304 grade). Louvre perforation and necessary hardware complete as per details. All as per the design and instructions Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.) Note: Only front elevation area to be measured for payment.	SQM	10		INR 0.00
	Make				
	Plywood - Century /Green ply/Archid				
	Laminate - Century/Merino/Greenlam/Aica				
	Hardware- Ozone/Hettich/Godrej/Hafle				
	Lockes with SS Handles - Godrej, Hafele, Dorset, Ozone				
38	ACE PLASTIC EMULSION including 2 coats of painting/ putty Providing & applying plastic emulsion paint on walls, columns & ceilings (other than false ceiling). The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread, quality finish (roller finish) of approved make , shall be provided. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQM	550.00		0.00
	Make				
	Berger/ Asian/ Nerolac				
39	Painting of wooden door ,Iron grill and window surface with synthetic enamel paint 2 or more coats approved brand (Asian/Berger/Johnson/Nero-lac-Make) inclusive of repairing and scribing of surface if needed as per directed by the Bank. (This item includes removal of existing work before carrying out the new work. No extra payment will be made against the removal work.).	SQM	50.00		0.00
	Make				
	Berger/ Asian/ Nerolac				
40	RECEPTION TABLE (SIZE:- 6'-0" X 2'-6")				
	Providing, fabricating and placing in position Reception table (6'-0") , top to be 19mm thick Extreme Density High Moisture Resistance (EDHMR) Finished with Corian only Top as per design fixed with adhesives of approved quality, framing to be done with sal wood finished with flexiply faced with 1.0mm thick laminate fixed with adhesives of approved quality. including necessary wooden edging, laminated drawer units, stainless steel / mettalic laminate skirting melamine polishing, necessary hardwares etc. complete as per detail drawings.	NO	1.00		0.00
41	UTILITY COUNTER 600MM WIDE				

	Providing and fixing Utility tables made out of 19mm thick Extreme Density High Moisture Resistance (EDHMR) over hard wood frame work finished with 1.5mm thick laminate of approved shade. Top having steam beech wood edging of size 2" x 1 3/4". 10mm thick clear float glass with beveled edges shall be provided on the finished to 19mm thick Extreme Density High Moisture Resistance (EDHMR) of approved make clad with 1mm thk. laminate (color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden steam beech lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thick Extreme Density High Moisture Resistance (EDHMR) with 1.0 mm laminate finish in the front , and bottom to be made out of 6mm thick Extreme Density High Moisture Resistance (EDHMR) and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint & Table back side wil be 1mm laminate. A leg rest to be provided duly polished made out of 3"x2" Wooden Section. A shutter to be made by 19mm thick Extreme Density High Moisture Resistance (EDHMR) clad with 1.0mm laminate .The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. The necessary wire managers(SS) to be provided on the tables and provision for lights to be kept if required in the front of the table. All the exposed areas to be duly malamine polished The work to be completed as per design and approval of the Bank. The table should have key board tray and CPU Trolly to be Modular. All as per the design and instructions Bank .	R.MT	4		0
42	TEXTURED PAINT				
	Providing & applying Texture Paint (Okios/ Dulux/ Asian) in two or more shades as approved by Bank with roller & spray, after preparing the base for the same as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer. (Base Price of texture paint to be used to be Rs. 45/ sq.ft.).	SQM	20		0
43	BACK DROP RECEPTION & CONFERENCE ROOM				
	Structure made by 19mm thick Extreme Density High Moisture Resistance (EDHMR) finish with laminate/veneer, and 6 mm thk. Laquered glass. panelling with spot light,flower vase, abstrac paintings as per drawings. All as per the design and instructions Bank & Architects.	SQM	20		0
44	WOODEN FLOORING (RM CABIN & MEETING ROOM)				
	Providing and fixing 8.0mm thick WOODEN FLOORING complete in all respect as per architect choice.	SQM	25		0
45	CARPET TILES (CONFERENCE ROOM)				
	CARPET:Supplying and installation of imported carpet TILES of approved quality and shade(26 Oz.) in approved pattern, including transportation, custom clearance, taxes, local transportation, lead, lift, etc. complete as per detailed drawing and as per manufacturers specifications.	SQM	75		0
	Total amount (excluding GST)				INR 0.00
	Grand Total				INR 0.00
	GST as Applicable				

