|       | FINATIALBID FOR INTERIOR AND FURNISHING WO   | RKS AT NE | W PREMISES | OF SBI NEELB   | AD BRANCH     |
|-------|--|-----------|------------|----------------|---------------|
| S.No. | DESCRIPTION OF ITEM PART A: INTERIOR WORKS:  | Unit      | Qty        | Rate in figure | Rate in words |
|       |  |           |            |                |               |
|       | Mode of Measurements: Area of exposed and finished surfaces<br>will be measured  |           |            |                |               |
| 1     | False Ceilings :   |           |            |                |               |
|       | Note: i) Rate to be included for all kinds of profiles and cut outs required for light fixtures, Speakers, Smoke detector, trap doors and AC grill in the ceiling. Provision for light fittings, AC grills and diffusers have to be made at no extra cost supported with tees, Angles, etc. suitably fixed all complete as per drawing and direction. The area of these cutouts which is less than 0.5 sqmt for one unit will not be deducted while measuring the ceiling area. ii) The contractor must coordinate with electrical & AC contractor for working out various levels for the false ceiling & make the marking on the walls / columns before starting the false ceiling work.  |           |            |                |               |
| 1.1   | Gypsum Board False Ceiling :   | Sqmt      | 86.00      |                |               |
|       | Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9 mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 12.5mm tapered edge Gypsum board (conforming to IS 2095-1982) is then screw fixed to ceiling section with 25mm dry wall screws at contd  contd 230mm centres. Screw fixing is done mechanically with drilling machine with suitable attachment. Finally tapered edges of the Gypsum boards are to be jointed and finished so as to have a flush look |           |            |                |               |
|       | which includes filling and finishing with jointing compound, joint paper/fibre tape and two coats of dry wall top coat suitable for Gypsum board etc. complete as per the recommended practices / specifications of the manufacturer. Including two coats of primer suitable for gypsum board two or more coats of plastic emulsion paint of approved shade and also including making necessary openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification and direction. Rate to be inclusive of shadow profile at the junction of wall & ceiling, in between of ceiling, etc. complete. (Make: Gyproc/ Saint Gobain / Gold Bond)   |           | 04.00      |                |               |
| 1.2   | <b>Cove in ceiling :</b> Same as above but providing, making and fixing Gypsum cove (inside  | Rmt       | 94.00      |                |               |
|       | height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.   |           |            |                |               |
| 1.3   | Mineral Fibre Grid Tile Ceiling: Mineral Fibre Acoustic Ceiling Tiles: Providing, making & Fixing at all   | Sqmt      | 118.00     |                |               |
|       | heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanized Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete contd   |           |            |                |               |

|     | contd including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification. (Make: Armstrong / Diamond / USG Boral) |  |  |
|-----|--|--|--|
| 1 2 | PARITIONS:   |  |  |

|     | Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works for cabling, AC pipe works etc. Make: Archid / Century / Kitply  |      |       |  |
|-----|--|------|-------|--|
| 2.1 | Full Height Partly Glazed Partly Wooden Double Skin Plywood<br>Partitions :  | Sqmt | 15.00 |  |
| (a) | Providing and fixing full height partly wooden, partly glazed double skin partition with following specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit)  |      |       |  |
| (b) | Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members wherever used. The partition to be sandwiched with 8 mm thick exterior grade MR commercial plywood (Make: Century/Archid/ Kitply) from both the sides and finished with 1.0mm thick approved shades of laminated finish (Make of laminate: & match the panelling pattern. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete.   |      |       |  |
| ©   | The partition will be provided with 5 mm thick float glass fixed at 900 -1200 mm above the floor level with teak wood beading fixed on both sides of the glass finished with polishing as directed. The float glass to be etched as per approved design (film etching to be paid separately). The beading for fixing glass to be fixed on both sides of the partition in such  |      |       |  |
|     | a way that it would be projected from the partition. (Glass opening wherever applied shall neither be included in measurement nor costing and shall be considered as separate item)  |      |       |  |
| (d) | The top panel (above glass panel) and side panels shall be provided with 8.00 thick exterior grade MR commercial plywood (Make: Century/ Archid/ Kitply) double skin partition as per specification of a) & b) upto ceiling/top support. Making provision for items like softboards, white boards, electrical points, switchboards, telephone/ electrical/ data cables, etc. as & where required (but excluding the cost for items). All finishes shall be done as per details and as per instructions of Bank's engineer. The rate to include all materials, labour, transport, etc. complete.  |      |       |  |
| (e) | Providing 75mm - 150 mm high skirting having 8.00 mm thick exterior grade MR commercial plywood fixed on both sides of the partition finished with 1.00 mm thick lamination of approved make and shade( Make: Century/Greenlam/ Archid). All wooden structures are to be painted with anti-termite/borer paint as per manufacturer's specification.  |      |       |  |
| 2.2 | Low Height partitions With/Without Glass :   | Sqmt | 27.00 |  |
| (a) | P/F 66 mm thick low ht. double skin glazed wooden partition approx.<br>1200 mm to 1450mm. High including glass, with following<br>specifications:  |      |       |  |
| (b) | Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members wherever used. The partition to be sandwiched with 8.00 mm thick exterior grade MR commercial plywood from both the sides and finished with 1.0mm thick approved shades and make ( Make: Formica / Sunmica / Archid) of laminated finish & match the panelling pattern. The borders/edges to be laminated finish. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete. One additional section 50 x 50 mm shall be placed at 700 mm level from floor to fix the table. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals |      |       |  |
| ©   | P & F 12 mm thick (approx.) etched glass (film etching to be paid separately) as per design and shape fixed with stainless steel glass fixing brackets/crews etc. of length varying from 750 to 1550 mm and height appx. 300 - 400 mm. etc. complete as directed.  |      |       |  |

| (d) | P & F <b>wicket gate</b> wherever required with required SS hinges, SS tower bolts, automatic surface mounted spring door closer, Godrej Night latch, etc. Rubber wood capping made out of sect. 65 x 15 mm fixed at edges incl. natural polish / painting etc. complete as directed.   |      |       |  |
|-----|---|------|-------|--|
| (e) | Making provision for items like softboards, white boards, electrical points, switchboards, telephone/ electrical/ data cables, etc. as & where required (but excluding the cost for items). All finishes shall be done as per details and as per instructions of Bank's engineer. The rate to include all materials, labour, transport etc complete. Further the partitions should have provision for fixing/embedding of vertical toughened glass partition and also toughened glass in vertical/horizontal position on SWO counter top, which will be measured separately.  |      |       |  |
| 3   | Panelling Works (Walls, Columns etc): Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC contractor for cabling, AC pipe works, etc.  |      |       |  |
| 3.1 | Wall/Column Panelling - Type I:  Providing, making and fixing single skin paneling (type I using 8 mm thick exterior grade MR commercial plywood of approved make: Century / Archid / Kitply ) on walls, front face, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 mt. ht., as required, made out of 25x25x1.0 mm th weighing 0.467 kg/m aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick exterior grade MR commercial plywood shall be fixed over the frame ( either in one plane or at different levels) finished with 1mm thick decorative laminate of approved make and shade (Make: Formica/ Archid / Sunmica with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beading of 35mmx20mm finished with polish/painting as directed.  | Sqmt | 84.00 |  |
| 3.2 | Cabinet for Electric Panel :  | Sqmt | 4.50  |  |
| 5.2 | Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thick exterior grade MR commercial plywood (Make:Century/Archid/Kitply). All visible surfaces shall be laminated with 1.00 mm thick laminate on external surfaces of approved make and shades (Make: Formica / Sunmica/Archid) painting the internal surfaces with two or more coats of synthetic enamel paint (Make: Asian / Nerolac / Berger), including providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots (approx. 10 mm wide) to be cut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom) SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or Ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).  |      |       |  |
| 3.3 | ACP Panelling Works :   | Sqmt | 55.00 |  |
|     | ACP Panelling in ATM room & exteriors and Shutter boxing with trap door: Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, (or Aluminium tubular section of same sectional dimensions if required) of good quality, fixed/fabricated @ 600 mm c/c or less as per site requirement or members recommended by the manufacturer and in accordance with the specifications and recommendations of the manufacturer. The structure shall be fitted in place on walls/ beams/columns/ceilings/ MS fabricated structures etc. as instructed using recommended fixing method, with 3M or equivalent adhesive and with mirror screws, joints to be finished with silicon based sealant, etc. complete ACP to be in 600 mm width panels or distributed equally. It shall be of thickness of 3 mm minimum. (Make: Alubond / Eurobond / Fuji bond) to be used. Bright silver / shade to be as per Bank's approval. Additional sections to be provided to fix the indoor AC units. The AC units to be installed near the machine area at the highest position. Shutter trap door will be of 12 mm thick exterior grade MR commercial plywood finished with ACP. The cost shall include all scaffoldings, chase making, lifting, cutting, on site adjustments, plaster repairing, etc. complete. |      |       |  |
|     |   |      |       |  |
| 4   | Doors:  |      |       |  |

| 4.1   | Main Door ( Branch / ATM) - Toughened Glass: Providing, making and fixing 12mm thick single/double shutter toughened glass of make: (Saint Gobain/ Modi / Asahi/)doors, at entrance, etc. (each door shutter counted individually) of size 2.10 m x 0.85 m (approx. as per site requirement) as demarcated, swing type door openable both sides made out of 12 mm thk. clear toughened float glass, edge polished, fixed in wooden top and bottom rails of approved colour and finish, fixed on Everite/Ozone/ Hardwyn/ Dorma or equivalent floor springs set, upper patch, lower patch, lock key plate, provision of locking system, etc. as per approval. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of approved make & design on both sides. Including providing "PUSH" * "PULL" sticker lables of approved design & make. The rate to include all materials, labour, transport, taxes, delivered and placed in position at site of work. Each door shall be treated individually with complete set of accessories to be provided on each door. | Sqmt | 39.00 |  |
|-------|---|------|-------|--|
| 4.2   | Flush Doors   |      |       |  |
|       | Providing and fixing single shutter flush doors of approx size 2.10 m x 0.75 - 0.9 m as instructed, hinged type door openable one side as instructed, made up of superior quality waterproof flush door partially glazed (cost of glass included). The door shall be flush door of approx. 32-38 mm thickness of approved make (Archid, Duro/ Swastik), both sides 1.00 mm thick laminate of approved make and shade. The cost shall be inclusive of beadings, all accessories like SS hinges, medium quality mortise handles / locks, baby latches, stopper, etc. Fittings shall be in SS finish as per approval, the cost shall include providing and fixing of door closers of reputed brand as per approval with all doors.   |      | 9.00  |  |
|       | SUB TOTAL : PART A ( INTERIOR WORKS)  |      |       |  |
| В     | PART B : FURNISHING WORKS   |      |       |  |
| 5     | FURNITURES:   |      |       |  |
|       | Note: All tables and side storage units to be made out of a combination of 18mm, 12mm, 8mm and 6mm thick exterior grade MR commercial plywood of approved make ( Make: Century / Archid / Kitply) as mentioned in respective items. The top and exposed sides of the tables as well as storage units to be finished with 1.00 mm thick plain or textured laminate of approved make  |      |       |  |
|       | (Make: Formica / Archid / Sunmica) and shades and 0.8 mm thick lamination on internal surfaces of approved made and shade. All table tops to be provided with 12x40mm teakwood/Rubber wood/ steam beach wood beading on edges duly polished/ painted, unless otherwise mentioned in the respective items. For all exposed edges of the plywood, teak, wood lipping of size 20 x 6 mm to be provided finished with polish/ paint. No vertical edge of the table & storage units should be left sharp. All drawers in tables shall be provided with single multidrawer lock of Ebco or Godrej made and storage units to be provided with individual "Godrej" make multipurpose lock. Hardware will be SS brush finish / approved make/ design viz. Stainless Steel hinges, Magnetic ball Catches, Stainless Steel Locks, approved design Stainless Steel Handles, Stainless Steel Brush finish wire manager, (all SS brush finish) etc All the edges of the MR plywood in contact with floor also to be provided with teak wood lipping   |      |       |  |
|       | contd of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the tables and storage units fixed with screws, wherever required. ( Make: 18 mm thick exterior grade MR commercial plywood: Century/ Archid/ Kitply) & Make of 1.00 mm thick laminate : Formica/Archid/ Sunmica).   |      |       |  |
|       | TABLES:   |      |       |  |
| 5.2 1 | Providing and supplying Officer's table and other tables as detailed  |      |       |  |
| (a)   | below: The table shall be of size of 1500 x 750 x 750 mm height, with edges been double thick having one side drawer Unit, 350 mm wide (clear internal size) one M S powder coated keyboard tray with mouse tray (measured separately) as manufactured by ebco/ Hettich / Hafele including sliding channel as per manufactures specification.   |      |       |  |
| (b)   | Table top of size 1500 x 750 mm (excluding beading) made of 18 mm thick exterior grade MR commercial Plywood finished with 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved make (Archid / Century / Greenlam) and shade inclusive of TW half round beading of sect 20 x 12 mm duly polished. All vertical supports from tapron and gable ends of the table are to be made out of 18 mm thick MR plywood finished with 1.00 mm thick laminate (upto Rs. 900/- per Sqm.) on external surfaces and 0.7mm th lamination on internal surfaces of approved made and shade.  |      |       |  |

|       | 75 mm X 75 mm for base frame and vertical supports as per design provided. The glass shall be bevelled edged. The table edges shall be double thick and all visible surfaces shall be finished with 1.00 m thicl laminate of approved make and all the hidden surfaces shall be finished with 0.8 mm thicl laminate of approved colour. The cost shall include providing and applying putty sealers and fillers on all exposed lipping/wooden surfaces etc and finishing with melamine polish of approved shade and finish including thorough cleaning, rubbing and surface preparation, application of primer, sealers, colour tone and final coat as required. (Measurement: Top usable surface area of the table)   |      |      |   |
|-------|--|------|------|---|
|       | same as item no. 5.2.1 but providing and placing in position circular / oval / rectangular / squar type design, lunch room table of dimension bmm X B mm X 750 mm ht. or as specified in laminated board construction with 12 mm thock glass top and wooden members of size  |      |      |   |
| 5.2 4 | Dining Counter   | Sqmt | 3.50 |   |
|       | same as item no. 5.2.1 but providing and supplying Office<br>Relationship Manager/ Auditor Tables of size 1.6 - 1.50m x 0.75m x<br>0.75m ht.   |      | 0.00 |   |
| 5.2 3 | Branch Manager of size 2.1 - 1.80 m x 0.90 m x 0.75 m ht.  Officer / Relationship Manager/ Auditor Tables :  | Nos. | 8.00 |   |
| 5.2 2 | Executives Branch Manager Table : same as item no. 5.2.1 but providing and supplying Executives  | Nos. | 1.00 |   |
| 522   | lamination colour matching with skirting and 2 nos 50mm high bands of 1 mm thick lamination colour matching with apron lamination. All internal surfaces are to be finished with apron lamination. Foot rest of ply wood with support of section 70x 35 mm to be provided finished with painting.  | Nos  | 1.00 |   |
| (g)   | Apron or Modesty panel: made out of 18 mm thick exterior grade MR commercial plywood of make (Archid/ Century / Kitply). Outer surface finished with 1.00 mm thick post lamination at site of approved make and shade ( Make : Formica/ Sunmica/ Archid) as per design shown in drawing in colour with 2 nos. 25mm high bands of 1 mm thick  |      |      |   |
| (f)   | One M S powder coated keyboard tray with mouse tray as manufactured by Ebco ( KBTM 45 ) or EGL ( KBT-M-001) including sliding channel as per manufacturers specification to be provided below the working platform.  |      |      |   |
| (e)   | On the left side platform at bottom for CPU. The bottom compartment made up of 18mm thick. MR plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished.  |      |      |   |
| (d)   | Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved made and shade to bottom of table top, drawers & inside the drawer unit etc complete. One footrest of plywood / salwood of cross-section 70 x 35 mm finished with painting.   |      |      |   |
| ©     | Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer (or storage below one drawer as required). Each drawer to be made of exterior grade of 18 mm thick MR commercial ply wood for the front and rear 12 mm MR Plywood for sides and 6mm thick MR ply for the bottom sliding on guard rail slides as manufactured by heavy duty telescopic drawer slides (HTDS 50 of Ebco Make). inclusive. teak wood lipping of size 19 x 6 mm on edges for the drawer. The front face of the drawers to be finished with 1.00 mm thick laminate of colour matching with table top laminate.(Make: Formica / Archid/ Sunmica) All edges of the drawer unit to be provided with teak wood beading of sect. 20 x 6 mm after finishing the laminate and duly polished. No vertical edge of the drawer unit should be left sharp. |      |      |   |
|       | D 0 6 10 000 (1 1 1 2 2 1 2 1 2 1 2 1 2 1 2 1 2 1 2  |      |      | ı |

|          | same as item no. 5.2.1 but providing, making and placing in position Single Window Operators / Counters fitted to necessary partitions as per item 2.2 above (The partitions will be measured and paid separately as per item 2.2 i.e. Half Height Partition) with the following specification and per dimensions specified. The overall size of each Single Window counter to be 1500mm - 1350mm X 900mm-800mm X 750mm ht. The top drawer of the counter to have pigeon holes arrangement. The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood and all visible surfaces including table tops, facia of drawers and outside of shutters etc. shall be finished with 1 mm thick Plain or Textured Laminate as directed, the bottom and inside of table shall be finished with 1mm thick laminate of approved make, colour and design and all hidden areas like inside of drawers, cabinets, finished with 0.8 mm white laminate. The table shall have provision for concealed LED strip lighting (cove type). Further the table and partition should have provision for fixing/embedding of vertical toughened glass partition and also glass in vertical/horizontal position on counter top, towards transaction side. (Make of laminate: Formica / Archid / Sunmica) |      |       |  |
|----------|---|------|-------|--|
| <u> </u> | Mall Manage of Malein and a   | N1   | 1.00  |  |
| 3.2. 3   | Wall Mounted Writing desk:  Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050 mm made of 18 mm thick exterior grade MR commercial plywood and 12 mm thick glass top, and sides and edges shall be finished with 1.00 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed. The cost shall be completed with lippings, mouldings, fittings, and accessories etc as per specification. as per the drawing and instruction given by the Bank Engineer.  |      | 1.00  |  |
| 5.2.6    | Grahak Mitra: same as item no. 5.2.1 but providing, making and placing in position arch shape 1650mm long Grahak Mitra Table of approximate size 1650mm x 800mm - 900mm x 750mm with the following specifications and per dimensions specified. Grahak mitra table with transaction top of 370mm wide and height 150 mm made out of 12mm glass with blue laquered to be fixed with SS studs Exposed faces would be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shades.". The table shall have provision only for concealed LED strip lighting (cove type).   | No.  | 1.00  |  |
|          | Storages / Credenza :   | Sqmt | 7.50  |  |
| (a)      | Officer Storage/Side Credenza:  Providing, making and placing in position low height storage cabinets as storage and/or runners from 350mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and in 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete. It shall have 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. All drawers shall be fitted with telescopic channels and locking arrangement and cupboards shall have locking arrangement and all exposed edges of plywood shall be fitted with lamination / teak wood beading duly polished. All bidding shall have polish/painted of matching color. All visible surfaces shall be laminated with 1 mm thick plain or Textured Laminate on external surfaces and 0.7 mm thick white lamination on internal surfaces of approved made and shades. Providing two nos. shelves, one at 75 mm above floor level and one intermediate in contd  |      |       |  |
| (b)      | contd middle made of 18 mm MR grade plywood with TW lipping on exposed edges duly polished. Two equal side hung shutters of 18 mm th MR plywood with teak wood lipping of size 20x6mm on all edges for each compartment contd   |      |       |  |
| ©        | contd No vertical edge of the storage units should be left sharp.   |      |       |  |
|          | The rate to include for necessary hardware fittings (all SS brush finish) like shutters will be on ebco self closing hinges and drawers shall be on ebco plain slides, SS handle to drawers & shutters, one no. of brass magnetic ball catcher for each shutter, one no. 75 mm long SS tower bolt to relevant shutter and one "Godrej" made lock for each compartment & drawers with common key, etc. complete. All the edges of the BWR plywood in contact with floor also to be provided with teak wood lipping of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the storage units fixed with screws, wherever required. (Measurement area = Length x Height).  |      |       |  |
| 5.3 2    | The rate to include for necessary hardware fittings (all SS brush finish) like shutters will be on ebco self closing hinges and drawers shall be on ebco plain slides, SS handle to drawers & shutters, one no. of brass magnetic ball catcher for each shutter, one no. 75 mm long SS tower bolt to relevant shutter and one "Godrej" made lock for each compartment & drawers with common key, etc. complete. All the edges of the BWR plywood in contact with floor also to be provided with teak wood lipping of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the storage units fixed with screws, wherever required.  |      | 13.00 |  |

|     | same as item no. 5.3.1 but providing and supplying Back Credenza/Runner, low height storage cabinets as storage and/or runners, in 18 mm MR grade plywood in verticals at sides, 900 mm c/c so as to form storage units attached together, each of width 900 mm. (Measurement area = Length x Height).  |      |       |  |
|-----|---|------|-------|--|
| 5.4 | Corian Surfaces on Furniture / Partitions :   |      |       |  |
| -   | Supplying, Fabrication and Installation of Corian of 12 mm thick. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. To minimize material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Bank Engineer. the Architect/Bank Engineer. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed. The basic rate of the corian shall be Rs. 900/- per sqft.) (Make: Dupont or equivalent as approved. | Sqmt | 7.50  |  |
|     | Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed. The basic rate of the corian shall be Rs. 900/- per sqft.) (Make: Dupont or equivalent as approved.   |      |       |  |
|     | <b>Deduction</b> for lamination work wherever Corian is been used (area same as Corian).  | Sqmt | -7.50 |  |
| 6.1 | Glass Works: Toughened Glass Dividers For Single Window Counters and  |      |       |  |
| J.1 | Front Partition Glazing/ATM. Make: Saint Gobain/Modi/Asahi Providing, making and fixing in position 12mm thick toughened clear  | Sqmt | 10.00 |  |
|     | Counters of approximate size 1450mm x 400mm - 100mm in tapered shape. Also to provide toughened glass at the entrance as partition in Branch & at ATM. All the edges of the glass to be polished for a smooth finish and the glass is to be embedded in half partitions/ floor/ wall and fixed with "D" brackets/ SS fittings as required. The glass bottom to be min. 75 mm above tile surface at SWO and at floor level at partition. Etching of glass with film to be done as directed (measured separately). The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. The rates shall include the cost of etching/Film.   |      |       |  |
| 6.2 | Partition Glass / Glass on Transaction side of Single Window<br>Operator Counters: 12 mm glass work:  | Sqmt | 15.00 |  |
|     | Providing, making and fixing in position 12mm thick clear float glass in the front side, vertically of height 400 mm and to place & fix another float glass of 12 mm thickness with round edged to be placed horizontally (of width 400 mm) above the vertical glass of length, equal to the length of the counter. Above this horizontal glass, a glass of 12 mm thickness of approx. 300 mm height will be placed vertically above the horizontal glass. The top glass to have a arch type, semi circular opening of dia 150 mm. All the edges of the glass to be polished for a smooth finish and the glass is to be embedded in half partitions and fixed with "D" brackets/SS fittings. Etching of glass with film to be done as directed (measured separately). The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. (Make Saint-Gobain / Modi/Asahi). The rates shall include the cost of etching/ Film.   |      |       |  |
| 7   | Hardwares:  |      |       |  |
|     | The following hardwares may be provided as per make specified as directed:(to be provided if not mentioned in item & required at site)  |      |       |  |
| 7.1 | Providing and fixing Doorset / Sterling / Ozone or as approved heavy duty <b>floor spring</b> , upper patch, bottom patch, etc. complete.   | Nos. | 4.00  |  |
| 7.2 | Providing and fixing <b>night latch</b> with three keys at doors, etc.  | Nos. | 4.00  |  |
| 7.3 | Providing and fixing two lever <b>mortise lock</b> of Godrej Make with brass<br>handle  | Nos. | 4.00  |  |
| 7.4 | Providing and fixing SS <b>AL-drop</b> 300 mm long along with through nut & bolt fittings, etc. complete.  Misc. Works:   | Nos. | 4.00  |  |
|     |   | N'   | 1 00  |  |
| 8.1 | NOTICE BOARD:   | Nos. | 1.00  |  |

|          | I  |             |       | 1 |  |
|----------|--|-------------|-------|---|--|
|          | Providing & fixing at site notice board of size 3' $\times$ 2' to be made up of kail/pine wood frame of size 2" $\times$ 1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete.   |             |       |   |  |
| 8.2      | Zebra Blinds   | Sqmt        | 10.00 |   |  |
| 0.2      | Providing & installing Zebra Blinds of Trac / Mac/ Vista or equivalent, 36" to 54" size of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. All metal parts shall be corrosion resistant and rotating parts shall be self lubricating. The fixing of the top rail shall be with special GI brackets at approx 1meter c/c. complete as directed by the Bank  | <u>o</u> gc | 20100 |   |  |
| 8.3      | Drop & Complaint Box :   | Nos.        | 2.00  |   |  |
|          | Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.   |             | 2.00  |   |  |
| 9        | SUB TOTAL: PART B ( FURNISHING WORKS)  |             |       |   |  |
| <u>C</u> | PART C: Bought out Items:  |             |       |   |  |
|          | Sofa Set:  Providing, making and fixing in position sofa set with side arms made for best quality badam/hillock wood framework and legs fitted with rubber nylon shoes fixing with 8mm thick commercial ply back side. Providing 150 mm thick high density (min 40) foam rubber of approved quality to seat of zigzag spring of approved quality over 12 mm thick phenol formaldehyde bonded approved quality commercial ply and 50 mm thick foam rubber of approved quality, density mini. 32 to back covered with upholstery of rate not less than Rs. 450/- per mt. finish of approved quality materials including polish finish complete of approved quality and make selected by the Engineer in Incharge. Rate inclusive of cost of material, transportation, loading/unloading, labour tools & tackles up to any lead and lift etc. Measurement: No of Seats. | Nos.        | 6.00  |   |  |
| 10.2     | High back, revolving Executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej/Featherlite /Durain / Wipro/ Methodex make or equivalent as approved for BM.   | No.         | 1.00  |   |  |
|          | Medium back, revolving Executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej /Featherite /Durain Wipro/ Methodex make or equivalent as approved for officers viz. Sales Manager, Service Manager, Discussion room, SWO counters, Visitor Chairs for BM cabin, etc.  | Nos.        | 11.00 |   |  |
| 10.4     | Medium back fixed type chairs with cushioned seat and back and molded PVC hand rest Godrej, S-frame type, as per quality and design approved, of makes viz. Godrej /Featherite / Durain/ Wipro/ Methodex make or equivalent as approved for visitors, lunch room, etc.   | Nos.        | 20.00 |   |  |
|          | SUB TOTAL: PART C ( Bought out Items)  |             |       |   |  |
| 24       | TOTAL (A+B+C)  |             |       |   |  |
| 25       | Total Cost   |             |       |   |  |
|          |  |             |       |   |  |

| Amount | _ |
|--------|---|
| 7      |   |
|        |   |
|        |   |
|        | _ |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        | _ |
|        | _ |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        | _ |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        | _ |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        |   |
|        | - |