JOYSAGAR BRANCH (NEW PREMISES) BOQ for Electrical Installation Works

| SL No | DESCRIPTION | | | Rate (Rs.) | Amount (Rs.) |
|-------|--|------|------------|-------------------------------------|---|
| JE NO | BESCHI HON | UOM | <u>QTY</u> | (Exclusive of GST on work contract) | (Exclusive of GST on work contract) |
| 1 | a. Main Panel : Supplying, Installing, testing and commissioning of factory fabricated 2MM thick CRCA, floor mounted cubicle type districution Panel Board with 150 MM X 75 MM X 6MM ISMC base channel, suitalbe for 415 V TPN comprising of 300A suitable copper bus bars with color codded heat shrink insulation with the followings: 300 A, 4P MCCB, 65 kA with overvoltage protection as incommer, R-Y-B LED indicating lamps, Digital multifunction meter of minimum size 150 MM X 150 MM to measure Voltage, Current, PF etc with all excessories Outgoing:125 A 4P MCCB, 35kA for AC -1 Nos, 80 Amp 4P MCCB, 35kA for UPS - 1 Nos, 80 Amp 4P MCCB, 35kA for Spare- 1 Nos. and 63 Amp 4P MCCB, 35 kA -2 Nos. for External equipment and capacitor panel, -1 Nos. All MCCBs are strictly as specified above only. All outgoing must be in compartmentalized chamber fully isolated with 2 mm thick CRCA and 3 mm steel channel painted with 2 coats of red oxide primer paint followed by finishing paint with interconnection etc. as required. | Set | 1 | Commucity | Community |
| | b. Capacitor Panel: Supply and installation of 15 KVAR APFC panel, floor/wall mounted front operated totally enclosed vermin proof, indoor non-drawout-cubicle type power panel fabricated out of 16 SWG thick CRCA sheet having gasketed hinged cover on each cubicle fully powder coated with suitable bus bar for connecting the contactors, MCB's, Capacitors, etc with the following acessories A set of R-Y-B LED indicating lamp at incomer 63 A, 4P MCCB, 35kA as incomer - 1No 2 Nos. 32A 3P contactor for 5 KVAR, 2 Nos. 25A, 3P contactor for 2 KVAR and 1 No, 16A, 3P contactor for 1 KVAR 2 Nos. 5 KVAR, 2 Nos. 2 KVAR and 1 No. 1 KVAR. 1 no. 6-step APFC relay of minimum size 150 MM X 150 MM suitable for above arrangement ON/OFF push button for each capacitor ON/OFF LED type indication lamp for each capacitor | | 1 | | |
| 2 | Sub-main line:- Wiring in MS conduit of IS specification of Proper size with core PVC insulated stranded copper wire 11KV grade (Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with supply ,installation, commissioning of all the materials required including proper termination, connection in complete as required from main DB to various DBs:- | | | | |
| i) | with 2nos 4sq.mm + 1nos. 1.5sq.mm (1ECC) | RM | 200 | | |
| ii) | with 2nos 6sq.mm +1nos 4sq.mm (1ECC) | RM | 140 | | |
| 3 | Supply ,installation ,testing and commissioning of distribution board manufactures made sheet steel enclosure With the following MCBs (DB,MCB and MCCB Make-Legrands/ Havells/ L&T/ SIEMENS or equivalent) and connecting the same to the system. | | | | |
| i) | Computer/Raw power DB, 8-way, SPN double door with 40A (30mA)DP RCCB as incomer & 6 nos 10A SP MCB as outgoing. | No.s | 2 | | |
| ii) | DB with 40A DP MCB. | No.s | 4 | | |
| iii) | DB with 16A DP MCB.(Security light and digital signage) | No.s | 2 | | |
| iv) | DB with 32A DP RCCB. | No.s | 9 | | |
| V) | DB with 40A MCB Changeover 4-way, VTPN Double Door Distribution Board with 125 A 4 Pole MCCB (36kA) | Nos. | 1 | - | |
| V1) | as incomer and 12 Nos. 32A SP MCB's at outgoing (AC) | Set | 1 | | |

| SL No | DESCRIPTION | UOM | <u>QTY</u> | Rate (Rs.) (Exclusive of GST on work contract) | Amount (Rs.) (Exclusive of GST on work contract) |
|-------|---|------|------------|--|--|
| ∨ii) | 4-way, VTPN Double Door Distribution Board with 80A 4 Pole MCCB (36kA) as incomer and 4 nos. of 40 A SP MCB, 6 Nos. of 32A MCB and 2 nos of 16A SP MCB at out going | Set | 1 | | • |
| ∨iii) | Light DB, 8-way, SPN double door with 40A (30mA)DP RCCB as incomer & 5 nos 10A SP MCB as outgoing. | No.s | 2 | | |
| 4 | Supplying, installing and commissioning of PVC Armored cable complete with proper cable glands and two nos. of 8SWG GI wire (Havell's/Richa/RR kebel/KEI or equivalent) alongwith all the other materials required including proper connection in complete as required from main Panel, Power Distribution Board to various DBs. | | | | |
| i) | With 3.5 core x 35 sq. mm cable | RM | 120 | | |
| ii) | With 3.5 core x 70 sq. mm cable | RM | 80 | | |
| 5 | Supply, installing and commissioning of earth station including digging and refilling back the pit with black soil and with 3.15mm x300mm size copper plate duly tinned through out the surface of the plate, placed at least 1.5Mtr,below the ground level with 2nos 10sq.mm PVC insulated stranded copper conductor in 20mm GI pipe, fixed to the plate and providing 40mm,2mtr,long GI pipe with reducer and funnel at top for watering pipe with supplying and laying earth continuity wire of 2x10sq.mm copper stranded PVC green color in heavy duty MS conduit on the wall from earth plate to starting point of the line earth connector with proper earth pit. | Nos. | 5 | | |
| | i) Supplying and fixing 25x3 mm copper strip, insulated by heat pressurized heavy gauge PVC sleeve, duly jointed by full lap brazing and drawn underground in 40 mm class B GI pipe from the inspection pit to the inside of the branch premises. | RM | 20 | | |
| | ii)Supplying and fixing 2X8 SWG dia copper earth wire in PVC conduit on surface or in recess for loop earthing from panel to DB | RM | 80 | | |
| 6 | Computer/Raw Power point wiring in MS conduit of IS specification of proper size with 3nos 2.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade(Finolex/Havells/Polycab/ RR Kabel/ Richa/KEl or equivalent) and with all material supply installation and commissioning complete from /PDB(Raw). The wiring shall be carried out on surface above false ceiling by chiseling the existing surface and plastering the same with cement etc. after fixing the MS conduit with all accessories like saddles screws, bends T-joint etc. 2 coats of painting Matching to the surface including supply installing, testing, commissioning of modular plate type switch and socket (Legrands / MK or equivalent) for computer terminal on sheet steel enclosure (cadmium plated),duly fitted with screw to the steel conduit and fixed to the wall partition furniture with all interconnection and proper earthing .All the opening shall be covered with blank plate and be sealed to make the box vermin proof.B48(maximum three points in single circuit) | | | | |
| i) | With 3nos 6A socket with single 16A switch. | No.s | 20 | | |
| ii) | With 2nos 16A socket with individual switch. | No.s | 11 | | |
| iii) | With 1nos 16A socket with individual switch. | No.s | 3 | | |
| 7 | Supply & Fixing of 15Watt commercial down lights of system efficacy >100lm/W. The light should be recessed mounted slim circular type LED panel with die-cast aluminium housing and smooth powder coated finish with anti glare UV stabilized diffuser and separate energy efficient electronic driver having inbuilt surge protection upto 2.5kV. (Make - as in tender make list) | Nos | 45 | | |
| 8 | Supply, installation testing and commissioning of surface mounted circular LED downlighter with 15W LED lamp. Make :- Bajaj/Havels/Phillips/Wipro /Crompton or equivalent. (Make - as in tender make list) | Nos | 8 | | |

| SL No | DESCRIPTION | UOM | QTY | Rate (Rs.) (Exclusive of GST on work contract) | Amount (Rs.) (Exclusive of GST on work contract) |
|-------------|--|--------------|--------|--|--|
| 9 | Supply and fixing of 2'x2' LED commercial Luminaire of 36 Watt with system efficacy of 110lm/W. The light should be recessed mounted type and low depth with CRCA poweder coated housing, high transmittance diffuser for sysmmetric light distribution with non-integral enegy efficient isolated electronic driver and inbuilt surge protection upto 3kV. (Make - as in tender make list) | Nos | 34 | | • |
| 10 | Supply and fixing of LED commercial batten Single Tube light fittings with 20W with glare free light distribution wall mounted at ceiling/false ceiling level/. (Make - as in tender make list) | Nos | 15 | | |
| 11 | Supply and installation of Wall Mounted fan 400 mm full Metallic body and metallic Blade, 1400 rpm crompton/ bajaj/ usha/ orient make | No.s | 10 | | |
| 12 | Supply and installation of 5 star BLD Ceiling fan 1200 mm crompton/bajaj/usha/havells make (Make - as in tender make list) | No.s | 3 | | |
| 13 | Supply and installation of heavy duty Exhaust Fan 300 mm crompton/ bajaj/ usha/ havells make | No.s | 6 | | |
| 14 | Supplying, installation, testing & commissioning of Security ligh with 25W LED lamps with pressure die cast housing with epoxy coated dark graphite grey colour finish and prismatic polycarbonates cover with individual LED lenses, including necessary GI bracket with clamp. Make: Bajaj/ Havels/ Phillips/ Wipro/ Crompton or equivalent | Nos. | 4 | | |
| 15 | Supply and installation of 10 Meter roll 55W, IP20 Flexible LED Strip surface mounted alongwith required LED Driver as back lighting. Havells or equivalent make. | No.s | 10 | | |
| 16 | Supply, installation, testing & commissioning of celling mounted LED profile downlighter fitting, fixture should have minimum efficacy at System level (Not Chip Level) profile light has 10w – 30w or require 1a to 4 a driver or gives 900 lumens to 2500 lumens. its has all the colors like cool/warm white, Luminaries manufacture shall provide LM79 report from NABL accredited lab & LM80 report issued by LED manufacturer. | RM | 20 | | |
| 17 | Supply installation testing and commissioning of 10 W fixed track LED light with modern design, compact size with high power COB LED to provide focussed light. Make: Havells (Model: UNECOTRACKLIGHTTS 10WLED830S15WHT/BLK or similar design and specification approved by Bank's Engineer.) | Nos | 5 | | |
| 18 | Supply installation testing and commissioning of racess mounted adjustable 10 W LED downlight made of exturded Alumunium housing and high power LED with seperate electronic driver. Make: Havells(Model:SPARKLEROADJDLR8W830MOD40DWHTNEEM or similar design and specification approved by Bank's Engineer.) | Nos | 5 | | |
| 19 | Wiring for light/fan/exhaust fan points using 3 X 1.5 1.1 kV grade PVC insulated stranded copper conductor wire (Finolex/ Havell's/ Richa/ RR kebel/ KEI or equivalent) for phase, neutral and earth in 25 mm dia heavy duty MS conduit along with associated accessories like MS junction boxes, bends, saddles, screws et. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/Fan/Exhaust Fan point outlet. etc. to individual modular type switch boards, 10 Amp modular plate type switches etc. (MK/Legrands/Havel's or equivalent), as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and as per site requirement and as instructed by SBIIMS Engineer. | | | | |
| i) | Light/fan point (Two downlighter/ 2"X 2" rececced light fittings to be connected through one point) | No.s | 80 | | |
| ii) | Light/fan point (four downlighter/ two 2"X 2" rececced light fittings to be connected through one point) | | 30 | | |
| iii) i∨) | 6A socket & switch at same board Fan Point with electronic modular type regulator. | No.s No.s | 5 3 | | |

| SL No | DESCRIPTION | UOM | <u>QTY</u> | Rate (Rs.) (Exclusive of GST on work contract) | Amount (Rs.) (Exclusive of GST on work contract) |
|------------|---|------|------------|--|---|
| v) | 16A, 5 pin industrail plug & Socket with 25 A MCB protected (for Safe room & Record room) with 5 meter 3 core 10 sqmm copper wire | Nos. | 2 | | |
| vi) | Modular type with 6A SP MCB for Exhaust fan and wall fan LAN NETWORK | No.s | 19 | | |
| 20 | Supply, Installation, commissioning & Testing of LAN I/O box (CAT 6) | No.s | 18 | | |
| 21 | Supply of CAT-6 LAN cable(4 pair) (305 Meter per box) | No.s | 1 | | |
| 22 | Supply, installation & Testing of company Made CAT 6 Patch cord with RJ 45 | | | | |
| a) | 1 Meter length | No.s | 13 | | |
| b) | 3 Meter length | No.s | 5 | | |
| 20 | Laying, instllation & testing of LAN cable in PVC conduit from switch to each node. | RM | 300 | | |
| 23 | Supply, Installation & Testing rack mountable 24 Port Patch panel | No.s | 1 | | |
| 24 | supply and installation of wall mounting server 9U steel rack | No.s | 1 | | |
| | Total | | | | |