



STATE BANK OF INDIA
LOCAL HEAD OFFICE PATNA

ADMINISTRATIVE OFFICE MUZAFFARPUR

Name of the work:- INTERIOR DECORATION & FURNISHING WORK OF PROPOSED SME CHAPRA BRANCH UNDER RBO
CHAPRA

PRICE BID

Sl.No.	Description	Unit	QTY	Rate (RS)	Amount
1	COUNTER FOR CASHIERS (length UPTO 6'0" wide x7'6"depth as per site design)	Nos	2.0		
	Providing and fixing low height Single Window counters / Case Manager's table with a maximum width of 900 mm in required shape as per typical design. The main structure of the counter is to be made of 19mm thick BWP Phenol Formaldehyde block board (of approved or equivalent make). The width of the counter should have 1500mm (with disc credenza / cabinet of 400mm wide and maximum 1050mm length / depth (including width of counter). The vertical supporting members of counter are to be made of 19 mm thick BWP Phenol Formaldehyde block board (of approved or equivalent make). D-Tel box shall be fitted properly in right hand side. The key board pullout tray to be provided in addition to drawer with lock and key make arrangement of standard make. The left hand side should have cabinet made of 19 mm thick BWP, PF plywood and cavity keeping CPU as per design / drawing. The counter top have a neat hole to be made in the table for connecting the wires which is to be covered with a white colored PVC insert (wire manager) with moveable parts to put the wires and sockets to cover the hole neatly. The exposed block – board/ plywood to be covered with 0.8 mm thick blue / white high gloss/matt finish laminate of approved or equivalent make of approved shade and colour. Exposed portions to be also covered with 0.8 mm thick blue/white high gloss/matt finish laminate of approved shade and colour. The internal and non-visible side of all drawers, cabinets and counter table shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. Providing and fixing 12 mm thick toughen glass of approved make as per design and specification securely fixed in toughen section as per design and details and all necessary standard quality of fittings, hard wares, locks (make or equivalent). Door shutter of 19 mm BWP board to be fixed at the rear side of counter with automatic locking system from Godrej or equivalent (Door shutter lock to be paid separately). All work to be completed as per approved materials Colour & Laminate etc and specification and direction of Engineer-in-charge.				
2	Wooden stud partition near reception/Lounge	Sqm	6.5		
	Providing and fixing wooden partition up to 900 made by G.I frame section fixed 6mm MR ply finished with both sides and top 0.8mm thick high pressured laminates of approved make & shade etc.and 50x50 mm 9mm ply boxes as per design finished wooden texture laminate and				
	Providing and fixing panelling on wall. Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 25 mm @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 6mm thk. MR Ply finished in approved 0.8 mm. Thk. Laminate high pressure laminate / Veneer finished in melamine polish. Wooden moulding, lipping etc. as directed by Bank / architect shall be provided wherever required.				
	All electrical wires, accessories, telephone wires, etc, shall be run in the panelling as per Electrical Drawings and designs. Nothing extra shall be paid for the co-ordination of the same.				

	All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are specifically mentioned in the B.O.Q / tender documents / drawings.				
	All complete as per drawings, designs, specifications and directions of Engineer-in-Charge.				
3	Column / Wall Panelling (upto false ceiling ht)				
	The Panelling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically. The framework is to be fixed by means of Alumin-ium angles of appropriate size for proper fixity. The framework is to be covered by 9 mm thick BWR plywood /Exterior Grade MDF board of Green/Century or equivalent on exposed side with suitable fix-tures.				
	The surface is to be finished with 0.8 mm thick high gloss laminate of approved shade & make. Provisions are to be made for fixing LED strips. The work is to include all necessary materials, ac-cessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc.				
	Executed elevation area is to be measured for fin-ished				
3.1	Wall panelling	Sq.M.	130.0		
3.2	Column panelling	Sq.M.	5.5		
3.3	Providing and fixing Charcoal finishing on above specification panelling	Sq.M	4.0		
3.4	Providing and fixing Louvers plank 4.5"X9" thk 8'-9'6"long finishing on above specification panelling make dexaart/ europrateek or equivalent(Basic rate for each plank=1050/-	Sq.M	4.0		
4	FRAMELESS GLASS DOOR WITH PATCH FITTING MAIN ENTRY/CM CABIN				
4.1	Providing and fixing frameless fully glazed 12mm thk toughened glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length)	Sq.M.	5.9		
4.2	FIXED GLASS ABOVE OPENING DOOR AND AREA ADJACENT TO DOOR	Sq.M.	26.5		
5	DOOR				
	Providing and fixing solid/SEMI GLAZED doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 50MMx100MM WPC frame section shall be provided finished in 0.8MM high pressure laminate as per approved make and shade . Rate shall include approved make (Godrej Eppco) NIGHT LATCH LOCK, door closure, door stopper, a pair of handles 250mm SS Brushed finished, 150mm hinges 2 Nos., buffers, tower bolts, etc with necessary hardware items.	Sq.M.	4.5		
6	FROSTING FILM on clear glass	Sq.M.	12.0		
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.) 3M - CRYSTAL GLASS FINISHES 7725 SE325				
7	CABINET BELOW GRANITE COUNTERS IN PANTRY AREA/BACK OF TABLE OF 750MM HT	Sq.M.	7.0		

	<p>Making and fixing low type storage cabinet with drawer and cupboard with shelf as per the drawing / design all made of 19 mm thick BWP block board of Green/Century /Mayur/ ASEAN with top, exposed side and front laminated with 0.8 mm thick blue / white high glossive laminate of Green/Marino /century/Durian. Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per approved materials Colour laminate and specifications . It includes work of kitchen cabinet also.</p>				
8	GYPSUM FALSE CEILING				
	<p>Providing and fixing false ceiling at all height including providing andfixing of frame work made of special sections, power pressed fromM.S. sheets and galvanized with zinc coating of 120 gms/sqm (bothside inclusive) as per IS : 277 and consisting of angle cleats of size25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at1200 mm centre to centre, one flange fixed to the ceiling with dashfastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flangeof cleat fixed to the angle hangers of 25x10x0.50 mm of requiredlength with nuts & bolts of required size and other end of anglehanger fixed with intermediate G.I. channels 45x15x0.9 mm runningat the spacing of 1200 mm centre to centre, to which the ceilingsection 0.5 mm thick bottom wedge of 80 mm with tapered flangesof 26 mm each having lips of 10.5 mm, at 450 mm centre to centre,shall be fixed in a direction perpendicular to G.I. intermediate channelwith connecting clips made out of 2.64 mm dia x 230 mm long G.I.wire at every junction, including fixing perimeter channels 0.5 mmthick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with</p>				
	<p>wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be be fixed in a direction perpendicular to G. I. channel with connecting clips made out of 2.64 mm dia x 230 mm long G. I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long .</p>				
	<p>including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finishof tapered and square edges of the board with recommended jointingcompound , jointing tapes , finishing with jointing compound in 3layers covering upto 150 mm on both sides of joint and two coats ofprimer suitable for board, all as per manufacturer's specification andalso including the cost of making openings for light fittings, grills,diffusers, cutouts made with frame of perimeter channels suitablyfixed, all complete as per drawings, specification and direction ofthe Engineer in Charge including the cost of putty and painting with specification as below :</p>				
	<p>Plastic Emulsion paint on gypboard false ceiling: Wall/ceiling painting with plastic emulsion paint of approved brand and manufacture to give an even shade in Two or more coats on new work. White cement based putty on false ceiling: Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.</p>				
A	<p>12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) For the area where vertical design etc to be done measurement shall be made in running metre for the verticals and shall be payable additional to plan area.</p>	Sq.M	95.4		

9	Wooden false ceiling				
	Suspended wooden false ceiling in Conference room as per design Providing and fixing 9 mm BWR ply on gypsum false ceiling finished by 1.0mm laminate as per approved by Bank Engineers/ architect hanging false ceiling channel on gypsum board same as above item LAMINATE Basic rate 2250/- per sheet	Sq.M	4.0		
10	FALSE CEILING (GYPSUM TILE GRID)				
	Providing and fixing of Gypsum tile false ceiling tile of size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Prelude XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independent-ly. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	Sq.M.	103.0		
11	OFFICER'S TABLE				
	Providing and fixing the Officer's table made out 19mm BWP ply board with 0.8mm laminate as per drawing detail enclosed ,storage unit with 3 drawer, and keyboard and pencil drawer on channels, cable manager , and laminated apron to match decor. Drawer unit and verticals made out of 19mm BWP ply board with keyboard drawers ,PC stands for PC below worktop and 12mm ply board for footrest . All Drawers to be provided with Godrej lock & SS handle of approved make . The exposed side of front facade ,drawer front shall be finished with 0.8mm laminate as per drawing . the inside surface also finished with white/blue colour paint as per approved A/E/I/Bank				
	a CM TABLE	Nos	1.0		
	(6'6"X3'6"X2'6") LXWXH WITH 3'6"x1'6"x2'6"CREDENZA				
	b 5'0"X3'6"X2'6") LXWXH WITH 3'6"x1'6"x2'6"CREDENZA	Nos	2.0		
12	CORIAN WORK (TABLE TOP)	Sq.M.	12.0		
	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make of Du-Point/Mairino on table top, table front, & designer beads SBI fa-cia, back black color & rounding of edges to complete in all respect, as per site condition with rounding of edges etc to complete job. (s.wo COUNTER).				

13	STEEL T/U BEAT (Reception table & wall panelling as per design requirement)				
	Providing & Fixing SS Finished Aluminium strip in partitions / panelling, made of HETTICH / Enox E approved equivalent profile, elevation width of min 20mm or more, finish SS, all complete, with neat installation in perfect line & level, cutting, insertion, making good, matching, etc., in panelling / partition / etc. as required.	Rmt	20.0		
14	ROLLER BLINDS /ZEBRA BLINDS				
	a Supply and installation of dual layer zebra roller shades light filtering Share Dimout blinds (Zebra Blinds)for window of polyester based fabric of Vista make all complete and inclusive the all taxes as per the direction of Architect/E/I/Bank	Sq.M.	7.0		
15	FULL/LOW HT PARTITION FULLY PANELLED/SEMI GLAZED PARTITION AND WOODEN GATE				
	Providing and fixing full ht fully panelled 75mm thk partition Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50 mm or wooden framing @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 9mm thk. BWR Ply finished in approved 0.8 mm. Thk. Laminate high pressure laminate / Vineer/Taxture /glossy finished as directed by Bank Engineer/ Architect shall be provided wherever required.	Sqm	7.5		
16	ACP PANELLING/ROLLING SHUTTER BOX				
	Providing and fixing ACP for panelling and rolling shutter cover: Providing and fixing of ACP cover for rolling shutter set within inner Al box section cover frame work and covered with wooden placed at suitable spacing not exceeding 600mm/c. The framework shall be covered with 12mm thick BWR Plywood. The work is to be finished with 3mm thick exterior grade Aluminium Composite Panel (ACP) cladding of approved make and shade with grooves duly treated with silicon sealant. The work is to include all necessary materials, accessories, labour, tools & tackles. Executed covered area shall be measured for finished work.	Sq.M	4.5		
	TOTAL INTERIOR & FURNISHING WORK	Rs.			
	Note:-				
	1) Extra members, wherever required for stability / otherwise, to be provided with the required finish without any extra charges.	ALL PLY/EXTERIOR GRADE MDF MAKE - Green ply /Century/Austin/ACTION TESA/ASEAN/Green panel/as per technical specs Laminate/Mica - Greenlam/Marino/Century/Europrateek/Durian/AICA/as per technical specs Hard ware and fitting as mentioned in specification refer technical specs/item description. Use of exterior grade MDF as per direction of EIC. Vendor shall not be allowed to use the MDF at any place without prior permission by EIC in the layout.			
	2) Any damages caused to the walls, ceilings, floors, etc. shall be made good by the Contractor by refinishing the same in exactly the same manner, so as to leave the surfaces in a good-as-new condition. A final coat of paint on all painted surfaces shall be deemed to be included in the occupation, so as to leave the premises in a suitable condition for occupancy.				
	3) Contractor shall make and get approved shop drawings of all items prior to fabrication / manufacturing of the same.				
	4) In case of partitions / panelling / etc., if any corbellings, cornices, etc. are called for, these shall be done as shown in the drawings, designs, etc., or as per the requirement of the Employer / Architect, and these shall be paid for at the square foot rate quoted by the contractor. Nothing extra over and above the square foot rate shall be payable to the contractor				
	5) The contractor shall extend full co-operation to the other contractors viz. Electrical, Airconditioning, and any others who may be working in the said premises.				

(Signature)
AUTHORIZED SIGNATORY