

PRICE BID FOR CIVIL WORKS AT THE NEW PREMISES OF SBI RASMEC- BSNL BUILDING- 1ST FLOOR- IRINJALAKUDA

Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
1	Block work in CM 1:6 with CC blocks of 40/30x20x20 cm or AAC blocks for superstructure	34	Cu.m		
2	Plastering including patch plastering with cement mortar 1:5 (1cement 5 sand) 12mm thick, one coat floated hard and travelled smooth for the wall surfaces including all staging works, watering ,curing etc. complete.	620	Sq.M		
3	Cement Concrete 1:2:4 for lintel including shuttering, curing, cost of reinforcement etc complete as directed	2.00	Cu.m		
4	Dismantle brick masonry of 23 cm/ 15 cm and finishing the exposed surface with cement mortar 1:4 and disposal of all debris clear off the premises. The work includes making good the exposed surface of the walls after dismantling.	20	Sq.M		
5	Providing and fixing 120 x 60 cm vitrified (Double charged) tiles of approved make/ shade/ color by using tile oin tile adhesive/ cm 1:3 as the case may be, on to existing flooring (after scraping/ chipping and making rough the existing suface) and skirting. The joints shall be filled with 3-5mm thick glass epoxy filler. Basic price of tiles to be taken as Rs.60 per square foot.	780	Sq.M		
6	Flooring with Italian marble finish vitrified tiles of superior quality and approved colour and 9 mm thick or as per manufacture's specifications, 80x80 cm or higher size with basic price of Rs.1100/m2 and fixing the tiles to correct line and levels (The make of vitrified tiles is of Cera/Asian/ RAK/ bell. Tiles to be fixed to existing flooring using approved quality tile on tile adhesive (after scraping/ chipping and making rough the existing suface). The work includes pointing the tiles with approved colour epoxy joint filler (5mm).	50	Sq.M		
7	Provide/ fix the following with all required fixtures and ancilliary works				
a	25 mm PVC pipe (6Kg/ Cm2 grade, pasting type) for water lines including cutting the walls / floors, making good the walls/ floors after cleaning etc complete	40	RM		
b	20 mm PVC pipe for water lines -do-	40	RM		
c	110 mm 4 Kg/ cm2 grade PVC waste pipes -do-	30	RM		
d	63 mm 4 Kg/ cm2 grade pasting type PVC waste pipes	30	RM		
8	Supplying and fixing CP Brass Two way Bib cock jaquar or crab tree (,basic price of Rs.1370/No)	5	Nos.		
9	Supplying and fixing CP Brass Long Body Bib cock jaquar or crab tree (,basic price of Rs.1150/No)	5	Nos.		
10	Providing and fixing at site health faucet parryware make T9940A1 or equivalent including CP Brass Angle cock, CP connection pipe etc complete.	5	No.		
11	Supply & Installation of CP Brass Angle cock including the cost of material, labour etc complete.	3	Nos.		
12	Supplying and fixing 24" towel rod (basic price of Rs.1250/No) of approved quality.	5	Nos.		
13	Supplying and fixing CP towel ring (basic price of Rs.1100/No) of approved quality.	5	No		
14	Supplying and fixing CP soap holder (basic price of Rs.900/No) of approved quality.	5	No		

15	Providing and fixing stainless steel sink with drain board of size about 36" x 18" including all connection/ fittings such as sink mixer/ waste lines, waste coupling etc complete	1	Nos.		
16	Providing & fixing 600mm x 450 mm x4mm bevelled edge mirror of superior glass mounted on 6mm thick A.C.sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers.	5	Nos.		
17	Providing & fixing 1500 mm x 600 mm x 8-10 mm bevelled edge mirror of superior glass mounted on 6mm thick A.C.sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws/ Studs and washers.	1	No.		
18	Granite counter :- Providing & Fixing granite counter in MS Base framework with 18mm granite fixed to cement board fixed on framework , edge moulding etc complete. over a box of marine plywood of 19 mm thick with openable shutters and intermediate shelves	5	Sq.M		
19	Granite wash counter :- Providing & Fixing cantilever type granite counter in MS Base framework with 18mm granite fixed to cement board fixed on framework , edge moulding etc complete. (Necessary cutting shall be made for fixing counter top wash basins (3 nos). A box of marine plywood of 19 mm thick with openable shutters and intermediate shelves shall be hung from the wall (below the counter) for towel storage.	2.5	RM		
20	Granite wash counter :- Providing & Fixing cantilever type granite counter in MS Base framework with 18mm granite fixed to cement board fixed on framework , edge moulding etc complete. (Necessary cutting shall be made for fixing counter top wash basin (1 no). A box of marine plywood of 19 mm thick with openable shutters and intermediate shelves shall be hung from the wall (below the counter) for towel storage.	1.5	RM		
21	P & F 55x40 cm or nearest available size counter top wash hand basin jaquar or equivalent white colour with all fittings including 15 mm cp pillar tap, brackets, PVC connection, 15 mm cp angle cock, waste lines and couplings etc complete.	5	Nos		
22	P & F 55x40 cm wash hand basin ivory colour with all fittings including 15 mm cp pillar tap, brackets, PVC connection, 15 mm cp angle cock, waste lines and couplings etc complete.	5	Nos.		
23	Providing and fixing WPC door with frame of size about 90 x 210 cms with all fittings	6	Nos.		
24	Providing and fixing steel door of size 90 x 210 cms for ups and record rooms with necessary frame work and all other fixtures including painting with enamel paint of approved make over a coat of primer	4	Sq.M		
25	Providing and fixing at site wall mounting type European water closet and its all fittings with necessary bend , check nut etc and concealed flushing cistern and all its accessories, angle cock and PVC connection pipe, bolts and washers etc. complete (cera/ hardware make).	5	No.		
26	Providing and fixing floor trap with SS gratings. Rate includes material cost and labour charges etc. complete	14	No.		
27	Dismantling the existing floor/ wall tiles with its underlayers and wcs / wash basins, door frames, counter slab etc. in toilets (4 Nos) & its ante rooms and disposal of the debris away from site at no risk and cost to the bank	1	LS		
28	Plain Cement Concrete 1:3:6 for Bath room flooring (50mm thick) over a layer of brick bat concrete and finishing the top surface ready for tiling work including shuttering, curing, water proofing etc complete as directed	17	Sq.M		
29	Supplying and laying 1st quality glazed wall tiles of size 4'x 2' approved colour and brand for the toilet, make johnson/ bell or equivalent approved	110	Sq.M		

30	Supplying and laying 1st quality antiskid tiles of size 4'x 2'/ 2'x2' of approved colour and brand for the toilets. Make Johnson/ bell or equivalent approved	30	Sq.M		
31	Reinforced Cement Concrete M20 for walls including shuttering, curing etc complete but excluding reinforcement	45	Cu M		
32	Providing steel reinforcement of 12 mm dia for RCC works including bending, tying and placing in position [for strong room walls and floors, 12mm dia bars shall be placed vertically and horizontally at 15cm centre to centre in two rows, staggered centrally and placed along both faces of the walls with a clear cover of 40mm on either side of the walls/ floor].	4500	Kg		
33	Collapsible grill - Twin units/ double leafed, meeting at the centre of the span. The collapsible door is fabricated from vertical pieces of rolled steel channels, 16 to 20 mm wide, joined together with the hollows of the channels on the inside; leaving a gap between them of 12 to 20 mm. Both are offered to the roller on its top and bottom sides. The vertical channel is spaced at 10 cm center to center, and is joined to one another by means of hoop iron cross pieces or flats 16 mm to 20 mm wide and 4-5mm thick, allowing the door to open or unfold. The rollers shall be run over steel channels fixed at top and bottom. The bottom channel shall be embedded within the floor tile level to provide smooth transit of the men, wheel chairs etc. Both the grills (leaves) shall have Steel handles, Locking arrangements etc and are to be fixed firmly to the walls/ pillars, floor and ceiling as required.	12	Sq.M		
	TOTAL				

GST at applicable rates will be extra