Sl.no	Description	Unit	Qty	Rate	Amount
Α	Interior Pianting			(INR)	(INR)
1	Applying two coats acrylic emulsion paint of approved brand on previously				
	painted walls and ceilings at all levels upto 8 meters height after throughly	·			
	cleaning the surface free from dust and dirt etc. and scrapping off loose scales	·			
	of paints wherever necessray to give an even smooth and homogeneous finish	Sqm	1500		
ı	as directed and specified.(Berger/ Nerolac / Asian / Indigo) (Royal Shine or		1500		
į	equivalent quality). Rate shall be inclusive of cost of scaffolding and other tools	ļ			
ļ	& plants as required)	l			
2	+		+		
- ,	Applying two coats enamel paint of approved brand and shade on prevously	ı			
į	painted wood and steel surface at all levels upto 7 meters height after throubly	ļ			
	cleaning the surface free from dirt, grease etc. to give an even and lustrous look	Sqm	300		
	as directed and specified. (Berger/ Nerolac / Asian / Indigo)Rate shall be	·			
į	inclusive of cost of scaffolding and other tools & plants as required)	I			
3	Applying wall putty and primer of approved brand wherver required for surface		 		
- !	preparation before applying emulsion paint as directed	Sqm	500		
4	, , ,				
į	Paiting of MS roof girder fixed with the roof with minimum two coats duco	I			
	paint of approved shade over prevolusly painted surface with spray nozzle to				
į	give an even , smooth and lustrous look as directed. Rate is inclusive of hiring	RM	140		
	charge of compressor , labour , transportation, fixing of masking tapes or	·			
į	other materials to complete the works as directed.Rate shall be inclusive of	ļ			
į	cost of scaffolding and other tools & plants as required)	I			
В	Panelling works				<u></u>
	Removal of old panelling , loose plaster hardware etc. carefully and disposal of	Cam	250		
	debris outside the campus as directed	Sqm	250		
6	12 to 15 mm thick palstering with cement mortar in prop 1:4 wherever	Cam	150		
	required at all levels as directed.	Sqm	130		
7	Wall paneling with 8mm thick MR grade ply fixed over 40mm x 40mm hollow	·——-			
	aluminum tubes firmly fixed to the wall surafce in both hozinotal and vertical	·			
į	direction @600 c/c with necessary scerws and finishing on the top with 4 mm	Sqm	140		
į	thick vineer of approved brand and design including malamine polish after	эчш	140		
ļ	preparing the surface smooth by sand papering as directed and specified.	ı			
а	25mm corner beading teak wood	RM	120		
b	100 mm rubber wood beading	RM	100		
С	Decorative timber beading of approved design 10 MM thick	RM	100		
8	Polishing of existing vineer panelling, doors, windows and other similar surafce	C	450		
	to match the décor as directed.	Sqm	150		
				Total	
			1		GST Extra