

PRICE BID FOR INTERIOR AND FURNITURE WORKS OF IMPHAL NEW SECRETARIAT BRANCH, MANIPUR – NEW BRANCH

Sl.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	FURNITURE				
1	Single Level SWO Counters: Providing and fixing at site SWO counters each upto 5'6" long, 2'6" high and 3'0" wide, as per design and drawing. SWO counters to be made of 19 mm thick commercial ply with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. commer block board and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications.	Each	3		
	Three drawers with autolock running on both sides mounting Telescopic(channels) of EBCO make, made of 19mm thick commercial ply with 1mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick commercial ply. Non-Visible/ inside surfaces i.e. inside/ leg space of table, inside of drawer / cupboard shall be finished with liner / laminate of 0.7 to 0.8mm thk. off white / white colour and exposed Teak wood edges / teak wood lipping beading shall be spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also include foot rest, Space for CPU as per drawing, complete in all respects. The provision of swiping machine of green channel size 9"x6" with lid shall be provided at right side of each counter while facing from front.				
	Provision of LED strip light below curved counter.				
2	Providing & fixing 12 mm thk. Solid Surface (Acrylic Sheet) on counter top & required vertical position made to shape for Single window Counter at transaction level as per design and approved colour (White). Make: LG / Samsung / Gravia / Granimum.	SQM	24		
3	Tables Table made of 19 mm thk. Commercial ply with Table front and side visible vertical surfaces to be finished with 1.0 mm thk. laminate of approved colour & shade, with 40 mm X 12 mm thick teak wood all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels finished with laminate, as per manufacturers instructions / specifications. The table top should be finished with acrylic sheet (rate shown together) and should have 12mm thick toughened glass modesty panel with etching on front.				
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19 mm thick commercial ply finished with 1.0 mm thk. laminate and ¾" x ¼" teakwood lipping on all visible sides. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1.0 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand side. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick ply. A full length foot rest made of hard wood 3" x 2" section shall be provided at 4" above floor level. Non-Visible / inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be spirit (natural) polish.				
	8.0 MM thk glass on top of all tables. All the edges of the glass shall be grinded polished including Hole for cable manager.				
(i)	C.M. / B.M. - Size 2100mm X 900 X 750	Each	1		
(ii)	Officers tables - Size - 1800mm X 750 X 750	Each	3		
(iii)	Other tables - Size – 1350mm/1500mm X 750 X 750	Each	3		

(iv)	Providing & fixing 12 mm thk. Solid Surface (Acrylic Sheet) on table top & required fascia and side runner made to shape for tables as per design and approved colour (White). Make: LG / Samsung / Gravia / Granimum.	SQM	14.50		
4	Side Credenza For BM/Officers, etc: Providing and fixing side unit for Manager /BM table to detail as per drg. of size 1200/1050 mm x 450mm made of 19mm Plywood finished with 1mm laminate having covered with 2mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100mm long S.S brush finish handles, tower bolt, ball catch etc., complete. 12mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished With 1mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	SQM	4.15		
5	Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop & Suggestion Box Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall cost of spacers ect all inclusive complete.	Each	2		
6	Toughened Glass 12.0 mm thk. with etching including all / as per given below	SQM	110.00		
(i)	12 MM thk. toughend glass for Banking / SWO Counters with Etching- front (4 Nos.) Sides (4 nos.) & Front tapered shape (5 Nos.) Providing and fixing 12 mm thick, clear plain toughened glass of fixed in vertical position at counter level & to side partitions as per drawing, the counter top glass fixed on both sides to toughened glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L - shaped clamps / glass holders 2 no. on both sides. A 6" dia. semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free.				
(ii)	Fixed Glass / Glazing / Partition - Toughened Glass 12.0 mm thk. with etching on chambers (4 Nos.) Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass of size - as per site all sides edge grinded, polished to be fixed with necessary patch fittings (godrej / dorma) the glazing to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shap and size to accomodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall include necessary etching film / logo all inclusive, Complete.				
(iii)	Main Entrance Door , BM, ABM, Advance section & Cross Selling- Toughened Glass 12.0 mm thk. with etching: Providing & fixing frameless fully glazed 12.0 mm thk. Toughend float glass single leaf glazed Toughned door of size approximately, 1800 to 700 mm X 2400 / 2100 mm all sides (as per drg. / instructions) edge grainded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete.				
(iv)	The modesty guard to officials' Tables shall be finished with 12.0 mm thk. toughed glass in 3" / 4" wide S.S. Spacer.				
7	Hardware & Accessories for fixing Toughened Glass doors etc. Providing and fixing Floor spring, 1'-6" S S door handle (both sides) in door - pair, lock etc. all complete of godrej / dorma.	Each	6		
8	Hardware & Accessories for fixing Toughened Glass / glazing etc at SWO Superior quality stainless steel, S.S. Spacer / S.S. glass holders of required size & L - shaped clamps with cover / cap 2 no. on both sides to holding the front glass partition to S.W. Counter & fixed glazing including required glass holes to fix the clamps complete.	Each	9		
9	Door Closer - Providing and fixing silver colour (or matching with colour scheme / as per site) hydraulic door closer - Godrej / Hyper / Dorma make to Doors complete in all Respects.	Each	7		
10	Mortice Lock -Providing and fixing silver colour (or matching with colour scheme as per site) Godrej make to Doors complete in all respects.	Each	7		
11	Night latch in SWO door - Providing and fixing night latch lock Godrej make in aluminium / wooden doors, complete in all respects.	Each	4		

12	Full Height Partitions with etching on glass Providing and fixing partition made of 50 mm X 25 mm X 16 Gauge aluminium extruded sections @ 2'0" to 2'0" c/c vertically & horizontally. The bottom member shall be aluminium extruded sections of size 50 mm X 50 mm X 16 Gauge. The aluminium extruded sections frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs / steel lugs. The frame work to be clad with 8.0 mm thick commercial ply and finished with 1.0 mm thk. of approved laminate as per pattern on both sides upto 3'0" height and above 7'0" height and 5.00 mm thick glass with etching as per design fixed with teak wood moldings above 3'0" height and upto 7'0" height. The skirting shall be finished with 1mm thk brushed steel finish laminate. Work also includes providing and fixing of door as per drawing and specifications. All teak veneer / ply / wood to be treated with wood preservatives of approved ISI quality.	SQM	43.00		
	All wood shall be finished with high gloss Spirit polished of approved shade. The rate shall also include for providing grooves in veneer. All job to be done to Architect's satisfaction / as per bank direction. Measurements to be taken upto false ceiling level & Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made above false ceiling.				
13	Low Height Partition: 4.5 feet height Providing and fixing of Low height partitions for Single window system of 1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thick of approved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided.	SQM	24.00		
14	Panelling work Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza, storage etc.				
(i)	Panelling finished with laminate-1.0 mm thk of approved shade & white colour laminate to be provided horizontally on exposed wall surfaces in inside chamber surfaces of ABM, Advance Section, Cross Selling (excluding BM's chamber)	SQM	49.00		
(ii)	Panelling finished with laminate-1.0 mm thk of approved shade & white colour laminate including MDF jali with provision for LED strip on centre pillars (6 Nos.).	SQM	21.00		
(iii)	Panelling finished without laminate with provision for LED strip (backdrop of SWO)	SQM	15.00		
(iv)	Panelling with veneer with polish to wall (backdrop of SWO and inside surfaces of BM's chamber) Providing & fixing 4 MM thk. Veneer of approved shade & colour made to design & desired grooves / patterns with frame work as mentioned above including required wooden framework made of hard wood, soft wood, commercial board & ply of required size & thickness finished with 4 mm thk veneer over 8.0 mm thk commercial ply & The Veneer needs to be prepared sanded and melamine polish. The work includes all kind of coves & provisions of LED lights. The rate should be inclusive of making Coves for provision of LED / lighting / opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. veneer / pine wood ledge & Cove (s) / Steps / Vertical bands / shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc. Basic rate of Veneer Rs. 250 /sft.	SQM	35.00		

15	Electrical panel Niche / covering for branch. Providing and fixing electrical niche upto 18" to 24" deep as per drawing / instructions with outer frame made of 19 mm thick commercial block board with 1.0 mm thick laminate on all outer visible surfaces as per pattern / design / Battens for ventilation. The inner surfaces shall be finished with enamel paint. Work also includes providing and fixing of doors as per drawing and specifications. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall also include for providing grooves in laminate & wood, hardware like hinges, handles, chitkney & locks etc. The work should be done to the entire satisfaction of the Architect / Engineer. For measurements front shall be measured.	SQM	1.00		
16	Partly solid and partly glazed door (including SWO doors): Providing and fixing door shutter Using 35mm thick solid block board finished with 1mm thick laminate on both sides with grooves fixed with 8mm glass 600x900mm fixed with Beech wood beadings above 900mm. Each door shutter to be provided With 4nos. 150Mm SShinges, a pair of 300mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	SQM	19.00		
17	Back credenza / Storage Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 3'0" HT. made of 19 mm thick commercial ply board and 6 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The back credenza will have cupboard with shutters and one shelf. The shutters with handle and magnetic catcher shall be provided beneath the drawers and Non-Visible / inside surfaces i.e. inside of cupboard & shelves shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.	SQM	11.00		
18	False Ceiling With Steps. & Cove - Gypsum Board Providing and fixing suspended false ceiling (as per specification of manufacture) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).	SQM	200.00		
	The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.				
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps / Vertical bands / cove shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges,tools, lifts and all heights etc.				
19	Extra for cove over gypsum board false ceiling Providing and fixing cove in suspended false ceiling as instructed including all required sections / parameters & labour as per mentioned above. Measurement shall be made from bottom external band only.	Rm	100.00		
20	Providing & fixing in place Roller blinds of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, locks,etc.	SQM	25.00		
				Total	
	The rates are exclusive of GST				