

**BOQ FOR CIVIL WORKS OF COVERED PARKING SHED AT SBI STAFF COLONY, VIJAYNAGAR, JABALPUR**

S No	Item Description	UoM	Qty	Rate	Amount
1	Providing and Fixing M.S.Truss, Steel Column, base plate, Purlin other frame work etc. made out of MS (square pipes, Round Pipes, Rectangle Pipes, Plates,round pipes, square bars, channels, ISMB etc.) as per the design and details, supported on Concrete Bed. The structure shall be Welded by Arc Welding of superior quality using best quality Electrodes and Standard Welding Equipment, Chisel cutting, bending, grinding, drilling etc. hammering excess deposits and then finishing with surface grinders including erection. The Rates includes Cost of Anchor Bolts with thread, Washers, Nuts, Cost of Scaffolding , Two Coat Primer, Two or More coat Paint with Superior Quality, color shade any as per approved and the Cost of All Material , Wastages, Labour , Cost of T&P etc Complete. Rate also includes fixing of MS plate of size 300X300X16 mm and MS bolts of size M16X50 by making necessary holes in the predestal. Note:- Provide crane for erection and all safety parameters in vendor scope. NOTE:- MAKE OF MATERIAL ARE :- TATA STRUCTURE PIPE, TATA BLUESCOPE STEEL, JINDAL PIPE, APL APOLLOW PIPES, ERW PIPES APPROVED BY ENGINEER INCHARGE.	Kg	7500.00		
2	Providing & Fixing Color Coated Galvanised roofing sheet including vertical/curved surface fixed with polymer coated self screw with waterproof washer, J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. Note:- Profile & Color approved by Engineer In-Charge. MAKE OF MATERIAL:- JSW, TATA BLUSCOPE STEEL OR APPROVED BY ENGINEER INCHARGE.	SqM	720.00		
3	Boring, providing and installation of cast in situ piles of 300 mm diameter driven to depth of 2.0 m including excavation, steel reinforcement 4 nos 12 mm dia vertical upto 2 m height 8 mm dia tie @ 250 c/c spacing. RCC M-25 for concreting works finished as per direction of Engineer-in-charge.	Nos	55.00		
	<b>Amount (in Rs.) excluding GST</b>				