

## PRICE-BID

### PROPOSED INTERIOR RENOVATION OF HALL NO-2 ON 5TH FLOOR, SBI LHO BUILDING, SECTOR-17 A, CHANDIGARH

S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
<b>1</b>	<b>Laminate Ceiling (Designer laminate of 1.25-1.5mm thk.)</b>				
	Providing and fixing 1.25-1.5mm thk. Designer laminate of approved make in ceiling over 8mm thk. commercial ply screwed to existing GI ceiling sections also incorporating 2" x 2" soft wood sections wherever specified as per drawing. The work includes spirit polished of approved shade on wooden members. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge. The work shall include removing old gypsum board if required.	30	sq.m.		-
	<i>Makes: GREENLAM/ROYAL TOUCH/MERINO</i>				
<b>2</b>	<b>Wooden Flooring</b>				
	Providing and placing in position wooden laminate flooring with planks of size not less than 1200 mm X 190 mm (with unlin panels / tongue-groove locking arrangement) having a 0.2 mm thick top abrasive layer followed by decorative layer upon HDF (high density fiberboard) substrate core over raisin saturated backing layer installed using tongue-groove system over 2 mm thick underlayer of polyurethane foam on 250-micron polythene sheet over a smooth, flat, hard and free from moisture floor surface complete in all respect with required accessories like end profile, transition profile, reducer 'T' profile etc. and preparation of base including all other incidental works as per direction & satisfaction of Architect in charge. Cost of Laminate Floor Accessories, Skirting, End edge, T- molding, Reducer shall have to be added in the cost, wherever required. Grade : AC4	120	sq.m.		-
	<i>Makes: PERGO/Armstrong/Evolve/CCIL</i>				
<b>3</b>	<b>Wall Paneling</b>				
<b>a)</b>	<b>Acoustic Panelling</b>				
a)	Wall paneling made from 50mm x 25mm ,18Guage thick hollow aluminum sections, spaced 600mm c/c bothways, over which BWR grade ply of 8mm shall be fixed and 1/2" thk non-woven Polyester Fibre Acoustic panels as per colour & pattern given or as directed by Architect.	36.00	sq.m.		-
	<i>Makes: ABI(Acoustic board of India)/MMT ACOUSTIX/SILENZO</i>				
<b>b)</b>	<b>HDHMR with DUCO Paint</b>				

	Wall paneling made from framework of 50mm x 25mm, 18 Gauge thick hollow aluminum sections spaced 600mm c/c bothways, over which HDHMR wooden panel shall be fixed in 2 layers, first layer will be 10mm HDHMR ply, over which 12mm thick HDHMR shall be fixed as per design / pattern or as directed by Architect. The panelling shall be provided with PU paint finish, as per manufacturer's specifications. The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards.	68	sq.m.		-
	<b>FINISHING:</b> The PU Palette paint shall be of approved make and shade. The surface to be painted shall be first prepared smooth by applying proper grade of sandpaper/water-paper and then if any pores are noticed the same shall be filled with approved quality synthetic filler agent. The complete surface shall be then applied an even coat of sealer putty and permitted to dry. The surface shall be again grinded smooth and even using appropriate grade of water-paper. When the surface is properly smooth and leveled without any pores or cracks the same shall be spray painted with approved quality Duco paint. The adjoining surfaces which are not to be painted with this application shall be suitably masked using appropriate masking tape. The paint shall be permitted to dry at room temperature and attain smooth lustrous finish.				
	<i>Approved make:-</i>				
	<i>(a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank.</i>				
	<i>(b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank.</i>				
	<i>(c) HDHMR - Greenply, Century, Duro or equivalent approved by the Bank.</i>				
	<i>(d) Adhesive: Fevicol SH/Vamicol or equivalent approved by the Bank.</i>				
	<i>(e) Pu Paint - Asian, Nippon, Berger or equivalent approved by the Bank.</i>				
	<i>Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear paneling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.</i>				
<b>c)</b>	<b>Lacquered glass</b>				
	Providing & Fixing 6mm thick lacquered glass (St. Gobain "Planileque" or equivalent), fixed to wall panelling with Aluminium fram 50mm x 25mm spaced @600mm bothways With 8mm ply fixed above the frame. The glass shall be fixed to raw panelling/ply using clear silicone adhesive, complete in all respects. All the edges of glass shall be duly grinded & smooth.	8.00	sq.m.		-
	<i>Makes: St Gobain/AIS</i>				
<b>4</b>	<b>Conference table</b>				

	Providing and fixing Conference Table, as shown in layout plan, 2'-6" high & 2'-3" wide as per the standard design & drawing and made of 19mm thk comm ply (BWP- ISI marked) top & vertical support at inner ends, as shown in drawing, with 4mm veneer ( on top & visible vertical surface on one side, with 2 ½"x 1" teak wood moulding at edges. 3"x 1 ½" hard wood foot rest to be provided. All internal surfaces shall be provided with 1.0mm thick laminate as specified. All the edges of ply shall be provided with 19mm wide teak wood lipping. The fron face of the table shall have leather panel 10" high appx. made using faux leather/leatherette, fixed as per drawings & details.Teak wood edge moulding/ lippings. All the wood and veneer surfaces shall be provided wich 50% matt PU polished complete.	18	mtr		-
	<i>Makes: PLYWOOD : Century / Green / Archid</i>				
	<i>VENEER: Green / Century/Durian</i>				
<b>5</b>	<b>Paintwork</b>				
	Applying three or more coats of ACRYLIC EMULSION of approved shade including making of ground, rubbing, filling of putty base preparation with BIRLA/ JK Putty, applying a coat of cement primer, complete. In case where the surface has been earlier white/colour washed, the old white/colour wash shall be entirely removed and surface broomed/scrapped down before preparing the surface foe applying paint as described above. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	78	sq.m.		-
	<i>Makes: Asian Paints / Nerolac / Birla OPUS</i>				
<b>6</b>	<b>BANK LOGO &amp; LETTERS</b>				
a)	Providing , making to shape and size ( as per the design provided) and fixing to position SBI bank logo made out of ACP sheet of bank golden ( pre approved) fixed to position with aluminium framework with required screws, nutts bolts and hooks etc. of size 2' x 2'	1	no.		-
b)	SBI logo 10" dia (SS FINISH)	1	no.		-
c)	English letters 10" high (SS FINISH)	3	no.		-
c)	English letters 6" high (SS FINISH)	25	no.		-
<b>7</b>	<b>Roller blinds</b>				
	Providing and fixing Rolling Roman blinds made of fabric of approved design and shade, as approved by the Architect, including rolling channels and other fitting complete in all respect, as per manufacturer's specifications.	27.00	sq.m		-
	<i>Make : FARRARI/ VISTA/ MARVEL.</i>				
<b>8</b>	<b>Gypsum ceiling repairs</b>				
	Closing and repairing the cut outs of ceiling light & other misc. repairs of existing gypsum ceiling	1	l/s		-
	TOTAL (ITEMS 1-8)				-