

PRICE BID FOR INTERIOR FURNISHING WORKS AT FIRST FLOOR OF ANANDAWALLESWARAM BRANCH TO HOUSE HLST

| Sl.No | DESCRIPTION OF WORK | Qty | Unit | Rate | Amount |
|-------|--|-----|------|------|--------|
| 1 | Table Providing and fixing table of size 1200 x 600 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. 12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete. | 10 | No. | | |
| 2 | Providing and fixing table of size 1500 x 600 X 750 mm high to detail as shown in drg. as per specification in item no.1 above. 12 mm thick glass with polished edges to be provided on table top. | 1 | Nos. | | |
| 3 | Custom Made Low Height Partition: Providing and fixing in position of custom made low height partitions of the 600mm glass above the table. The glass may be fixed to the table top using necessary SS D bracket etc complete as per the site condition. | 5 | Sq.M | | |
| 4 | Custom Made Full Height Solid Partition: Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves. Measurement for the partition area shall be considered from floor level to false ceiling level only. | 3 | Sq.M | | |

| | | | | | |
|----|--|-------|------|--|--|
| 5 | Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above. | 4 | Sq.M | | |
| 6 | Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns. | 12 | Sq.M | | |
| 7 | Gypsum Board False CeilingProviding and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprisingFrame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. | 60 | Sq.M | | |
| 8 | Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate. | 14.00 | Sq.M | | |
| 9 | Providing and Fixing Zebra Type Roller Blinds of Vista Levton or approved equivalent make and colour. | 5 | Sq.M | | |
| 10 | Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shadeover a coat of putty including cleaning the surface. | 125 | Sq.M | | |

| | | | | | |
|----|--|-----|------|--|--|
| 11 | Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface. | 150 | Sq.M | | |
| 12 | Providing and fixing 60 x 60 cm vitrified tiles Johnson 'Marbonite' make by using cm 1:3 on to existing flooring and skirting. Basic price of tiles to be taken as Rs.60 per square foot (Tiles will be selected by the Bank). | 60 | Sq.M | | |
| 13 | Providing and fixing in position discussion table | 1 | No. | | |

GST EXTRA AS APPLICABLE