

# PRICE BID

## BILL OF QUANTITIES FOR FURNITURE WORKS FOR STATE BANK OF INDIA, REGIONAL BUISNESS MEHSANA.

**Note:** Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleanir wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the tirn of Bills

Sr. No.	Description	Quantity	Unit	Rate in words	Rate in figures
<b>[A]</b>	<b>FURNISHING WORK</b>				
	<b>TABLES</b>				
1	<b>THE ASSISTANT MANAGER TABLE SIZE: 7'-0" X 3'-0" X2'-6" HT. with Laninate finish on Table Top , sides and all other visible surfaces etc complete as follows</b>	1.00	NO		
	Supplying and installation of Table as per the following description : Size7'-0" x 3'-0". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the CABINET shall have laminate, Foot rest of 1 1/2" x 3" T.W members shall be provided. All internal surface will have 0.60 mm thick balacing laminate				
	<b>Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing</b>				
	<b>Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.</b>				
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laquer polished etc complete as directed				
	Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	<b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.</b>				
	All the surface without laminate / balancing laminate shall be lacquered polished of approved shade				
	<b>As per drawing and instruction of Architect/Bank work to be Completed.</b>				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				

**Note: Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleanir wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the tim of Bills**

	<b>1) Table Top :</b> 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished				
	<b>2) Front Apron &amp; Sides:</b> 1.0 mm thick Dark Laminate				
	<b>3) Facing of Drawers:</b> 1.0 mm thick Dark Laminate				
	<b>4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</b>				
1A	Same as above Item-no-2 but Size: <b>6'-0"x3'-0"</b> with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	4.00	NO		
1B	Same as above Item-no-2 but Size: <b>5'-0"x2'-6"</b> with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	21.00	NO		
2	<b>DINING TABLE Approx Size 7'-0"x 3'-6"</b>	2.25	SQ MT		
	Supplying and installation of Dining Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. <b>[ Only Top shall be measured for payment purpose.]</b>				
3	<b>CONFERENCE TABLE</b>	11.14	SQMT		
	Top shall be made from 18mm th Commercial plywood with necessary inbetween supports with both side laminate as directed complete. 1mm thick laminate with 18 + 75mm wide 18mm thick MR Grade plywood with 36mm moulded steam beach beading shall be provided to the top as per instruction of the Architects complete as directed. Providing foot rest by using 3" x 1/2" T.W member, making necessary arrangement for installing Audio and computer system as directed complete (data box pop up box cable cubby with wiring of HDMI, VGA, Audio, LAN and Power Ports (Black). All visible surfaces of Table shall have lacquer polish as per instructions of Architects. Preiliminary drawing of the Table is enclosed herewith there may be some modifications suggested during execution. All the non visible Inside and bottom portion of table should be 0.80 mm thick balancing laminate <b>[ Only Top shall be measured for payment purpose.]</b>				

**Note: Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleanir wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the tim of Bills**

	<b>SIDE CREDENZA (SIDE TABLE)</b>				
4	Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. ( For BM & Officer's) Rate for length Less than 3'-3"	17.50	SQ.MT		
	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3' 6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: Frosty White Laminate				
5	<b>STORAGE CABINET with Top &amp; Front laminate finished. Storage of any height</b>	45.50	SQMT		
	Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades)				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) <b>Front Apron &amp; Sides:</b> Dark Laminate/Frosty white Laminate as per design & instructions				
6	<b>P/F ELECTRIC CUB BOARD</b>	3.90	SQMT		
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.				

**Note: Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleanir wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the tim of Bills**

7	<b>P/F PANTRY PLATFORM CUB BOARD SHUTTER</b>	1.85	SQMT		
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiente for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiente surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface				
	<b>LOW HEIGHT PARTITION WORK</b>				
8	<b>P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS</b>	23.00	SQMT		
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.				
	<b>FULL HEIGHT PARTITION WORK</b>				
9	<b>P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR</b>	101.00	SQMT		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides,1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.				
	For purpose of payment partition height up to bottom of false ceilling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				

**Note: Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleanir wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the tim of Bills**

	<b>PANELLING WORK</b>				
10	<b>P/F Wall panelling with laminate finishing for wall and Pillar etc</b>	70.00	SQMT		
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of				
11	<b>P/A WALL PAPERS on Digital wall</b>	37.00	SQMT		
	Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				
12	<b>P/F GYPSUM BOARD FALSE CEILLING</b>	200.00	SMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section <b>of Gypsteel Serra ( Gypsteel Serra shall be used)</b> supporting system in line and level. Finishing the surface and <b>applying 3 coats of Plastic emulsion paint</b> as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	<b>After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.</b>				
	<b>Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMT and paid in SqM (3) Only finished visible surface area shall be measured for payment.</b>				
13	Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid	183.00	SMT		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. <b>Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose</b>				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				

**Note: Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of Bills**

14	<b>SOFT BOARD</b>	1.00	SQMT		
	Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.				
15	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST)	75.00	SQMT		
16	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.	20.00	SQMT		
17	<b>Supplying and installation 1'-9" x 1'-9"x 1'-3" height Center Tepoy as follows.</b>	2.00	NO		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as				
	<b>TOTAL COST "A"</b>				
<b>Note:</b>					
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden memb electrical/data cabelling and No extra amount shall be paid for this				
[b]	All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balancing laminate of & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.				

## OFFICE-2 AT

[illegible]

ing cutting  
ie of payment

[illegible]



ing cutting  
ie of payment

[illegible]

ing cutting  
ie of payment

[illegible]

ing cutting  
ie of payment

[illegible]

ig cutting ie of payment
ers to facilitate
approved make