

SCHEDULE OF QUANTITIES – RACC PALAKKAD

S.No	Description	Qty	Unit	Rate	Amount
1	LOW HEIGHT PARTITION:	5	Sq M		
	Providing and fixing of Low height partitions of 1200 mm height from finished floor level, as per the drawing.				
	Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure ,vertically at about 60 cm centers and 3 Nos Horizontally of the same size of frame at floor level, 750 mm and at1200 mm level. . 8 mm Plywood on both sides of framework finished with 1 mm laminate of approved color and shade with grooves on both sides. Top of the partition finished with laminate of 1mm thick. 12mm thk glass to be used above 750 mm height				
	Custom Made Full Height Solid Partition :				
2	Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing.	5	Sq M		
	<u>Frame Work Detail:</u> Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure,vertically at about 60cm centers varied along columns wall ends, junctions of walls, as necessary. Horizontally of the same size of frames at floor level,750 mm, 1500 mm,2100 mm, and roof level. same size at 350				
	<u>Lining Work:</u> 8 mm Plywood of approved make on both sides of framework from floor level to 6"above false ceiling level, and to be finished with 1mm laminate of approved color and shaped on both sides including necessary grooves and steam beach beadings.				
	Measurement for the partition area shall be considered from floor level to false ceiling level only.				

3	Fully glazed Door				
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings (Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items. (DORMA MAKE Top Pivot - PT 24 , Top Patch Fittings - PT 20 , Bottom Patch fittings - PT 10 , Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 32mm dia X 600mm length)	2.50	Sq M		
4	Fully Glazed - Fixed Glass Partition - Patch Fitting				
	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws, 3M Vinyl sticker as per approved, colour, design and pattern , sealants etc.complete.	2	Sq M		
	FALSE CEILING:				
5	NOTE:The false ceiling area will be measured in flat area only.				
	Gypsum Board False Ceiling				
	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising	20	Sq M		

	<p>Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with 2 coats of plastic emulsion paint of approved color and one coat of putty over a coat primer etc, complete.</p>				
	Officers Table				
6	<p>Providing and fixing Officer Table of size 1500 x 750 X 750 mm high to detail as shown in drg. Comprising table top out of 25mm thick Plywood Board post formed with 1mm thick flexy laminate of approved color and brand with both side half rounded edge and another two side edges with 3mm thick band strip.12 mm glass with edge rounded to be provided for the table top. Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick to be fixed on front vertical laminated Plywood Board with SS studs.</p>	7	Nos		
	<p>On front and side of drawer finished with 1mm thk laminate and additional 18mm Plywood is fixed on front side to pattern with necessary grooves and finished with 1mm thick laminate.</p>				
	<p>MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality .</p>				
	<p>One set of 4 drawers about 450mm wide, 712.5 mm high and 600mm deep to shape supported with 18 mm Plywood at bottom, sides and rear. 4 nos. of drawers out of which 3 nos. of equal height and 1 no. drawer at the top most of 75mm high made out of 12 mm thick</p>				

	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach beading polished to the satisfaction of the Bank. The inside faces of drawer should be waxed and finished with varnish of app color and shade				
	Side Tables For OFFICER				
7	Providing and fixing side unit for Cash Officer table to detail as per drg. of size 1200mm x 450mm, 18 mm Plywood for top, bottom, rear, sides and One intermediate with necessary reeper. The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickness flexy laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip. Side hung shutter in both the panels using 18 mm Plywood and finished with 1mm laminate of approved color and shade, including all necessary TW lipping, Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc,.complete.12 mm glass with edges rounded to be provided for the table top	7	Nos		
	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.				
	Low Level Storage :				
8	Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 1200mm high comprising. 18 mm Plywood for top, bottom, rear, sides and One intermediate with necessary TW reeper.The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickness flexy laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip.	15	Sq M		
	Exposed faces of Plywood at top and sides of unit to be finished with 1mm thick laminate of approved color and shade.				

	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.				
	Column/Wall paneling				
9	Providing and fixing wall paneling to detail as shown in the drawing with 18mm thick Plywood finished with 1mm thick laminate	15	Sq M		
10	Applying two coats of emulsion over one coat of putty for the walls in banking hall	100	Sq M		
11	Vertical Blinds - Providing and fixing 100mm wide vertical blinds of Vista or any approved equivalent make and approved colour.	8	Sq M		
12	Solid block works of approved qty of size 40x20x10cm & of compressive strength not<35 kg/cm ² in in C.M. 1:6 in super-structure above plinth level (first floor level) including staging if required watering ,curing etc complete.	6	M3		
13	Plastering with Cement Mortar 1:5, (1 cement 5 sand) 12mm thick one coat floated hard and traveled smooth to inside walls including all staging work watering,curing etc complete.	51	Sq M		
14	Dismantling the existing panelling, false ceiling, furnitures etc. and disposing the waste away from site at contractor's own risk and cost	1	LS		
	TOTAL (Excluding GST)				
	* GST as applicable will be paid extra				