

BOQ FOR PROPOSED LANDSCAPING WORK AT SBI BHOPAL					
S.NO.	Description	QTY.	UNIT	RATE	AMOUNT
<b>1</b>	<b>FILLING- FERTILE SOIL</b>				
	Supplying and stacking of fertile soil specific useful for plantation at site including royalty if any and carriage (earth measured in stacks will be reduced by 20% for payment).	400.00	CUM		
<b>2</b>	<b>PLANTING DIFFERENT VARIETY OF PLANTS</b>				
	Providing and planting different variety of plants of approved quality and sizes as mentioned including making pits of required size/depth as directed at site, refilled with B.C. Soil mixture manuring and pesticide etc. complete including watering and 90 days maintenance from the date of final bill as per direction of Engineer-in-Charge complete in all respect (Plant Like- Mango, Guava etc) (Basic cost ₹275/- per plant)	50.00	NOS		
<b>3</b>	<b>P.C.C. for road</b>				
	Providing and laying P.C.C. 1:2:4 levelling course with 25/30 mm down gauge aggregate, in foundations, pits, raft etc. below plinth including consolidation, curing etc., complete. Thickness 100mm	17.00	CUM		
<b>4</b>	<b>BRICK WORK -200MM THK. For nalla and along road</b>				
	Providing and constructing brick masonry 200mm thick with Chimney Ghol bricks with cement mortar 1:4 of 12mm thick joints with best quality locally available approved bricks minimum crushing strength 70 Kg/CM <sup>2</sup> ) in superstructure at all height & levels, including striking joints, scaffolding, curing, etc. complete as directed.	21.00	CUM		
<b>5</b>	<b>PLASTER (Existing drain, chamber , near road)</b>				
	Providing and applying 12/15mm avg. thick smooth finish cement Plaster in cement mortar 1:5 to all walls using fine sand and adding polypropylene fiber of approved quality in desired quantity per bag of cement as per manufacturers specifications complete. Rate includes providing chicken mesh/glass fiber mesh to all joints of RCC members with Brick walls in all positions in line, level & plumb at all levels and heights with necessary scaffolding, cleaning of surfaces, raking out joints, roughening of surfaces,curing etc complete as directed at site.	110	SQM		

S.NO.	Description	QTY.	UNIT	RATE	AMOUNT
6	Providing and constructing <b>MAIN HOLE</b> of approx Internal size 450mm(W) x 900mm(L) x 600mm(D) in 100/110mm thk. R.C.C.- M-20 Grade walls(125mm thk.) & Raft(100/110mm thk.), including centering & shuttering, internal plaster 1:4 cement sand mix in single coat about 12mm and with heavy duty Poly Vinyl cover (Size:- 450mm x 900mm) (Bearing capacity minimum 2.50 Tons) as per sample approved. The rate should include Chamber Raft Slab(M-20 Concrete grade) 100mm thk. and necessary earthwork in excavation, disposal of surplus material as directed, laying P.C.C. 1:3:6, 100mm thick leveling course, making neat cement finish smooth benching, hunches, channels etc. in CC 1:2:4 complete for smooth flow as required. Rate to include for making connections to stone ware/PVC pipes etc. complete in all respect. Note:- Excluding Steel Reinforcement but including Precast cover.	3.00	EACH		
7 a	<b>PRECAST SLAB (1200X750MM) for outer drain</b>				
	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete in shelves, including setting in cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering, shuttering and finishing with neat cement punning on exposed surfaces but excluding the cost of reinforcement, with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 12.5 mm nominal size).				
	outer drain	3.50	CUM		
7b	Steel reinforcement TMT Bars for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete	300.00	KG		
8	<b>GREEN GARDEN GRASS (korean/carpet Grass)</b>				
	Providing & Laying Green Garden Grass with leveling of ground and laying properly of grass at ground including all transportation, labour , material etc complete	550	SQM		
9	<b>KERB STONE</b>				
	Providing and fixing Concrete Kurb stone with placing of periphery of trees including all labour, material tec compele. Size100mmx300mm	2	CUM		

S.NO.	Description	QTY.	UNIT	RATE	AMOUNT
<b>11</b>	<b>EXTERNAL PAINTING (Boundary wall &amp; compost room)</b>				
	Finishing walls with Premium <b>Acrylic</b> Smooth exterior paint of Apex Ultima or Eq. with Silicone additives of required shade :New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm	350	SQM		
<b>12</b>	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.				
	Concealed work, including cutting chases and making good the walls				
	25 mm nominal outer dia Pipes	80	RM		
<b>13</b>	Providing and fixing gun metal <b>gate valve</b> with C.I. wheel of approved quality (screwed end) :				
	25 mm nominal bore	4	EACH		
<b>14</b>	Supply and fixing Bollard light 1X 18 Watt LED-L 18 PHILIPS for garden light.	12	NOS		
<b>15</b>	Supply, installation, testing of (3 x 2.5 sqmm) circuit wiring with ms conduit of suitable size	150	M		
<b>16</b>	P/f 18mm thk granite with cement mortar with machine polish and edges moulding. Basic cost of granite ₹150/- per sqft)	18	sqm		
<b>17</b>	Carefully dismantling the brickwork and throwing away the debris as directed by Bank	6.7	sqm		
	<b>TOTAL AMOUNT</b>				
	GST Extra as applicable				