

PRICE BID**DILIP KULKARNI & ASSOCIATES - ARCHITECTS, INTERIOR, LANDSCAPE DESIGNER & SURVEYOR.**

Add: 15/3, 2nd Floor, 'C' Wing, Metro House, Opp. Hotel Delhi Darbar, Shahid Bhagat Singh Road, Colaba, Mumbai 400 001.

E-Mail - dkulkarniasso@gmail.com / rajandk1956@gmail.com

Mobile - Mr.Rajan - 98200 76349 / 93216 29231

NAME OF CLIENT: - **STATE BANK OF INDIA- POYNAD BRANCH**

ADDRESS: - GROUND FLOOR,SHOP NO-1,2,3 ,SUPE COMPLEX,NEAR APLA BAZAR,
PEN ,ALIBAG ROAD.POYNAD-08

NATURE OF WORK: - **AIR CONDITIONING WORK (HVAC)**

MAKE -Mitsubishi /Hitachi/Daikin/ Voltas/Toshiba/ Carrier

NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
A	HIGH SIDE WORK				
A01	Supply, ceiling mounted (3 STAR rated Invertor) " CASSETTE" Air-Conditioner comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc complete.				
a	Supply, of 2.0 Ton cassette A.C. as per specifications given above.(banking hall)	4	NOS		
<input checked="" type="checkbox"/>	RATE IN WORDS				
A02	Supply, HighWall mounted (5 STAR rated Invertor) " Split" Air-Conditioner comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc complete.				
a	Supply, of 1.5 Ton Highwall Split A.C. as per specifications given above.(First Floor-2)	2	NOS		
<input checked="" type="checkbox"/>	RATE IN WORDS				
b	Supply, of 1.0 Ton Highwall Split A.C. as per specifications given above.(ATM+B.M Cabin)	3	NOS		
<input checked="" type="checkbox"/>	RATE IN WORDS				
TOTAL (A)					
ADD:GST@14%					
ADD:GST@14%					
GRAND TOTAL OF A					
B	LOW SIDE WORK				
B01	Supply, Installation, Testing & Commissioning of indoor & outdoor cassttee AC fixed indoor unit with GI heavy guage suspended load fixed with anchor fastner including Refrigerant gas charging (R32 or R410)etc as per site requirement.	4	NO		
<input checked="" type="checkbox"/>	RATE IN WORDS				
B02	Supply, Installation, Testing & Commissioning of indoor & outdoor high wall split AC fixed indoor unit with GI heavy guage suspended load fixed with anchor fastner including Refrigerant gas charging (R32 or R410)etc as per site requirement.	5	NO		
<input checked="" type="checkbox"/>	RATE IN WORDS				

B03	S.I.T.C. of 19 mm dia & 16 mm dia Copper Refrigerant Pipes with nitrile rubber insulation between Indoor & Out door units.with breaking of wall wherever required for 3 Tr Cassette/ Air conditioners. Both length should be considered as one for measurement.	55	MTRS		
✖	RATE IN WORDS				
B04	S.I.T.C. of 12.5 Sq.mm. & 6.25 Sq.mm. dia. Copper refrigerant pipe with foam Insulation between Indoor & Out door units with breaking of wall for making hole wherever required For Split Air- Conditioners.	68	MTRS		
✖	RATE IN WORDS				
B05	S.I.T.C. of 3 x 1.5 Sq. mm copper conductor flexible cable between Indoor & Outdoor units through holes as made above for Split A.C.'s / CASSETTE.	120	MTRS		
✖	RATE IN WORDS				
B06	S.I.T.C. of 20 mm PVC conduit pipe to be used as a drain water pipe. Through holes as made above with nitrile insulation.	60	MTRS		
✖	RATE IN WORDS				
B07	S.I.T.C. of 25 mm. PVC conduit pipe to be used as a drain water pipe. Through holes as made above with nitrile insulation.	20	MTRS		
✖	RATE IN WORDS				
B08	S.I. of L shape / suitable shape M.S. Frame stand for mounting Outdoor Units on wall / On floor with all fixing hardwares. Within above Catwalk for cassette & split A.C.'s. along with cat wak made of 50mm x25 mm x5mm thk.M.S. angle frame work with 25mm x 3mmthk.m.s. split angle to wall with anchor fasner ext.as per side requirement.	8	NOS		
✖	RATE IN WORDS				
B09	Supply, Installation, Testing & Commissioning stabilizer of approved make for AC machine.(microtek/ v guard)				
a	3.0 KVA	4	NOS		
b	2.0 KVA	5	NOS		
✖	RATE IN WORDS				
B10	Supply, Installation, Testing & Commissioning timer of approved make for atm	1	NOS		
✖	RATE IN WORDS				
TOTAL (B)					
ADD:GST@9%					
ADD:GST@9%					
GRAND TOTAL OF B					
TOTAL OF (A+B) (EXCLUSIVE OF GST)					