

PRICE BID OF FURNISHING OF CHARAMPA BRANCH					
No	Description	Unit	Qty	Rate	Amount
1	Dismantling the counters, wall and column panelling etc complete inclusig buy-back of the items and cleaning the premisies	Job	-1.00	4500	-4500
2	SWO Counter(5'x3'x2'6" and side unit of 3' to 3'6"x16"x30") : Made with 19mm MR grade BB table top, sides and 12mm thick ply on front modesty panel; with three drawer units with depth as directed by engineer) with auto locking system, telescopic sliding channels, one PVC KBT, cable manager. Customer side shall be rounded with 6mm flexi ply (350 to 400mm depth) followed by 6mm ply duly supported on each side by a profile frame of 19mm BB and as directed by engineer. Round / curve shape shall be made after 3' width of table top. 12mm glass shall be provided at 2'6" distance thus leaving 6" for customer desk space. (Cost of glass shall be paid extra). All the exposed surfaces shall be finished with 1mm thick laminate bi-colour as directed by engineer. If PVC laminates are provided, the cost of this laminte shall be deducted from the bill)	No	2	20000	40000
3	P&F PVC flexible laminate in the SWO counter top with suitable adhesive for PVC laminates including pasting, pasting and finishing without any joints (5' x4' including rounding portion and 5'x2" to 3' on the bottom edge and mouldng to edge sides.	Sqm	8	1400	11200
4	BM table 6'x3'00"x2'6"along with side unit of 18"x42": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units . All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished.	No	1.00	21000	21000
5	Officers table 5'x2'6"x2'6"along with side unit of 18"x36": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side unit shall have one shutter with provision of storage units . All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be polished.	No	5	19000	95000
6	Staff Table 42"x24" x2'6": Made with 19mm MR grade block board in table top, sides with one drawer unit of 400x450x150mm with one drawer along with sliding channels and one cup board with shutter. All necessary hardware, locks, hinges handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be polished. Edges shall be finished with 6mm teak wood lipping and polished for smoothness. Drawers shall be finished with lipping polished.	No	5.00	8500	42500

7	Full height and Low height Partition: (64mm thick) Providing and fixing solid and glazed partition made with GI Channel section 50mmx25mmx0.55mm thick spaced at 600mmx600mm grid and duly finished with 6 mm MR grade ply and 1mm thick laminate (colour & shade approved by engineer as solid/ teak wood / texture premium quality on each side. The frame shall be properly anchored at true ceiling, wall/ column sides and floor with long screws at 900mm centres. The glass panel shall be 5.5 to 6 mm thick duly supported by 6 mm MR ply and finished with laminate.	Sqm	75	2900	217500
8	Column and Wall panelling: P&F 12mm MR grade BB on all sides of column with full threaded screws and pasting 1mm thick laminated with premium quality textured finish bi colour as approved by engineer. Make: MDF interior grade: century/Green/ Kit ply, Laminate: Century/ Marino/Green/ equiv as approved.	Sqm	10.00	1900	19000
9	Column and Wall panelling: P&F 9mm MR grade BB on all sides of column and wall surfaces with backing ply frame of 19mm with full threaded screws and pasting 1mm thick laminated with premium quality textured finish bi colour as approved by engineer. 1200 mm height in FO, BM sies area, etc	Sqm	9.00	1700	15300
10	Wall panelling with Ply board: Providing and fixing aluminium frame 25mmx40mmx0.80mm with a grid of 600mmx600mm duly anchored with wall screws to the walls and finished with 9mm MR grade Ply and 1mm thick laminate of approved colour and shade. Make: MR Ply: Kit ply/Century/Mayoor/Green and laminate: Kit ply/Century/Green/Marino	Sqm	85.00	1800	153000
11	Storage units 450mm deep: Made with 19mm MR grade Block board on all five sides and 6mm backing ply. Vertical separators shall be provided at each 3' Centres with door leaf of each shutter of 18" wide supported by auto closing hinges. All inside surface shall be finished with 0.80mm thick laminate. Exposed surface including shutter edges shall be finished 1mm laminate of approved shade. Hardware like locks, handles shall be provided.	Sqm	10	9000	90000
12	P&F 30mm thickness MR grade flush door finished with 6mm thick teak wood lipping on all edges duly polished, three SS Hinges for each door, one door stopper, one cylindrical lock per door finished with 1mm thickness laminates on both sides of approved shade and colour (solid and glazed with 5.5mm thickness float glass).	Sqm	16.00	4208	67328
13	P&F 12.5mm thick Gypsum false ceiling of India Gypsum / Saint gobain make which includes G I perimeter channels , GI runners with perimeter of ceiling, screw fixed to brick work/ partition with the help of Nylon sleeves and screws at specified enters. Then suspending GI intermediate channels from the soffit at specified centres with ceiling angle fixed to soffit with GI cleat and steel expansion fasteners, ceiling section having knurled web etc complete. GI channels, runners etc shall be IS marked. Ceiling frame shall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc.	Sqm	70	750	52500

14	P&F modular grid pvc LAMINATED GYPSUM CEILING TILES of Indian Gypsum make/ saintgobai/equiv as approved and 600x600 x8mm as specified by manufacturer WITH BLACK REVEAL CHANNEL . Installation to comprise main runner at 1200 centres fixed to structural outfits and perimeter channel as per manufacturer's specification and it shall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc. Provision shall be made for light fitting, fire equipment, CCTV equipment. Extra support shall be given if necessary as per site requirement.	Sqm	130	950	123500
15	Finishing the walls and ceilings with primer in two or more coats including scraping the surface etc complete of Asian/ Berger	Sqm	400	26	10400
16	Putty to wall and ceilings including gypsum ceilings with a minimum of 1m thickness in a line and level and scraping the surface to make it good adhesion for paints.	Sqm	400	80	32000
17	Finishing the wall surface with tractor emulsion paint of Asian/ equiv as approved by engineer in charge with roller finish in two or more coats	Sqm	400	60	24000
18	Enamel paint with primer in two or more coats	Sqm	30	120	3600
19	P&F 12mm thick pre edge polished bevelled plain glass in table top of counters, tables, side units	Sqm	15	3000	45000
20	P&F 12mm thick pre-polished Toughened glass to two counters and ATM	Sqm	7.2	4000	28800
21	P&F 12mm toughened glass in fixed position with patch fittings, duly supported at top, bottom and sides as directed by engineer with edge polish. Cost of extra member for fixing glass (Aluminium sections, ply, door frames shall be paid extra.	Sqm	1.9	4500	8550
22	P&F 12mm toughened glass in Main entrance door with patch fittings, SS handles of 200mm duly supported by pivot at top and bottom with floor springs and top chord aluminium powder coated section as directed by engineer with edge polish. Cost of floor spring and alu section shall be paid extra.	Sqm	2.21	7000	15470
23	P&F frosted film of Garware make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc complete.	Sqm	15.00	600	9000
24	P&F floor springs to glass door including cutting the floors (granite/ tiles/ concrete floors) and embedding the floor springs and grouting the area by approved tile adhesive matching with existing floors complete.	No	1.00	5500	5500
25	P&F door closer two speed of Godrej/Dorma/Ebco/Dorset as approved with all accessories to the doors.	No	4	1500	6000
26	P&F mortise lock with handles, with all fixed accessories (SS colour) to the doors. Make: Godrej/Dorma/ Dorset(Alpine series) as approved	No	1	2000	2000
27	Supplying and Fixing Godrej Night Latch for SWO Doors outside opening 7 lever brown colour	No	4	1400	5600
28	P&F 6mm thick fiber cement board door fixed with aluminium frame of 50x25mm with grids of spacing 600mm c/c including partition made with 8mm thick fiber cement board, handles, hinges etc complete for	Sqm	33.30	3500	116550.00
29	Foot rest made of 19mm ply as per engineer's instruction	No	14	800	11200
30	CPU Trolley of made with 19mm block board duly laminated of size matching with CPU including clearance on each side.	No	9	900	8100

31	P&F wall/ column mounted writing desk having size of 4'x1'6"x8"depth with slots spaced @8" centers made of MR grade 19mm Block board on all sides and 6mm backing ply with slots of 8"x8"spaced @ 8"centers.All surfaces shall be laminated with 1mm thick laminates with edges teak wood lipping duly polished.	Rm	1.00	2000	2000
32	Preparation of in-built layout drawing & mentioning the dimension of partitions, counters, panelling and marking locational reference in the measurement sheet and submission of drawing in PDF format along with the bill.	No	1	5000	5000
33	P&F pin up notice board made of 12mm backing ply duly laminated on one side and other sided sandwiched with 12mm soft board. The soft board is covered by a light blue fabric (Rs 250 per rm) and the stripped with teak wood lipping all-around include edges with hooks for hanging.	Sqm	1.20	3200	3840
34	Complain box of standard sizes 12"x16"x8" with shutters made with 19mm ply and laminates, locks etc complete	No	2	1200	2400
35	P&F Zebra blinds of approved brand and colour in all windows and BM chambers of standard make with all accessories	Sqm	5	2200	11000
36	18mm Granite partition wall for urinal including polishing all edges etc complete	Sqm	1	3500	3500
37	Sal wood frame work panelled with 6mm ply and duly laminated with blue colour	Sqm	9	1200	10800
38	P&F 2nd class Sal wood frame 100mm x 75mm fixed to the walls or side partition as per site conditions with hold fasts including polishing the surface, rebating etc complete.	Meter	30	900	27000
39	P&L steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto 12m level	Kg	125	77	9625
40	Shifting of Gold and cash safe heavy weight including dismantling RCC embedding work and placing in the desired location	No	8	9000	72000
41	Supplying manpower for shifting of old records, files, almirahs, storage cabinets etc to a desired position as per instruction of engineer in charge	Each	20	700	14000
42	Embedding of safe with RCC work in CC 1:1.5:3 with 6" spacing inbetween two safes including centring and shuttering etc complete	no	2	18625	37250
43	Dismantling existing collapsible shutter of safe room and stacking at site	No	1	2500	2500
44	P&F 1mm thick MS sheet sliding shutter with frame and diagonal braces 40x40x6mm angle iron, 3mm MS gusset plate T iron angle hinges, handles as instructed by engineer including two or more coats of primer as directed by engineer.	Sqm	2.80	4000	11200
45	Labour charge for shifting of UPS to the desired location coordinating with UPS vendor including dismantling existing electrical connection and making temporary connection etc as per site conditions	Ps	1.00	12000	12000
46	Anti termite treatment to walls and floors through 12mm dia holes using pressure injecting with chemicals of approved quality diluted in water as per manufacturers specification for termite treatment. Holes shall be spaced @ 300 mm centers and to be filled with cement mortar. Contractor should submit a completion certificate from BM. Warranty 3 yrs	Sqm	300.00	90	27000

47	Cover to electric panel room with 12mm ply and laminates with 12mm dia holes	Sqm	6	1600	9600
	Total cost excluding GST				₹ 15,35,813.00
	QUOTE % ABOVE/BELOW OR AT PAR ON COST	%			₹ 0.00
	Net tender cost excluding GST				₹ 15,35,813.00
	Material Recommended	Brand Recommended			
1	Block Board, Ply, MDF, Flush door	Saburi, Kitply, Greenply(ecotech), Globe ply MR grade 303			
2	Autolatch	Ebco, Godrej, Hafle, Ozone			
3	Gypsum ceiling	India Gypsum, Saint-Gobain, Gypstar			
4	Grid ceiling	Armstrong, Saingobain, India Gypsum			
5	Hardware fittings	Ebco, Godrej, Hettich, Hafle			
6	Plumbing materials	Hindware, Parryware, Cera, Jaquar			
7	Tiles	Johnson, Nitco, Kajaria, Somany,			
8	Corian Solid surface	, Marino, LG, Green			
9	Miscellaneous materials	Engineer's Discretion			
If required brands are not available, contractor may use other equiv brand available for use at site.					