

PRICE BID FOR INTERIOR FURNISHING WORKS AT THE NEW PREMISES OF SBI RASMECCC, IRINJALAKUDA

Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
1	LOW HEIGHT PARTITION FOR SINGLE WINDOW SYSTEM/ TABLES :Providing and fixing of Low height partitions for Single window system of 1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thick of approved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided.	122	Sq.M		
2	Custom Made Full Height Solid Partition:Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to 15 cm above false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beadings. Measurement for the partition area shall be considered from floor level to false ceiling level only.	107	Sq.M		
3	Custom Made Full Height cement board partition:Supply and set in position of custom made cement board full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 10 mm cement board from the floor level to 15 cm above false ceiling level on both sides of the frame work including painting with plastic emulsion paint over a coat of putty. Measurement for the partition area shall be considered from floor level to false ceiling level only.	16	Sq.M		
4	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	10	Sq.M		

5	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	12	Sq.M		
6	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	50	Sq.M		
7	Gypsum Board False Ceiling: Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete. Additional GI pipe/ Aluminium channel support to be provided as required as the height from false ceiling to the ceiling is more.	370	Sq.M		
8	GRID Ceiling:- with fissured mineral fibre board (tegular type) tile 600mm x 600mm x 14-16 mm thick (amstrong or approved equivalent) over the suspended grid system with hot dipped precoated GI angle sections 24 x 24 x 0.9 mm size on walls / partitions, Curved/ grooved type T Sections 24 x 38x 0.7 mm size in bottom directions to form 600 x 600 grid. Neceswsary cutouts for lighting fixtures, air conditioner, air conditionin grills etc to be provided. Additional GI pipe/ Aluminium channel support to be provided as required as the height from false ceiling to the ceiling is more.	70	Sq.M		

9	GRID Ceiling:- with accoustic mineral fibre board tile 600 x 600 x 12-15 mm thick (amstrong or approved equivalent) over the suspended grid system with hot dipped precoated GI angle sections 24 x 24 x 0.9 mm size on walls / partitions, Curved/ grooved type T Sections 24 x 38 x 0.7 mm size in bottom directions to form 600 x 600 grid. Necessary cutouts for lighting fixtures, air conditioner, air conditioning grills etc to be provided. Additional GI pipe/ Aluminium channel support to be provided as required as the height from false ceiling to the ceiling is more.	30	Sq.M		
10	AGM Table : Providing and fixing Branch Manager's table of size 1800 x 900 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. 12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete. Additional horizontal support to be provided below the table top in order to avoid sagging.	1	No.		
11	Side Tables For agm: Providing and fixing side unit for Manager / BM table to detail as per drg. of size 1200mm x 600 mm made of 18 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc., complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.		
12	Providing and fixing Officer's table of size 1850 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.10 above. 12 mm thick glass with polished edges to be provided on table top.	10	No.		
13	Providing and fixing table of size 1400 x 600 x 750 mm high as per specification in item no. 10 above.	10	No.		
14	Providing and fixing table of size 1200 x 700 x 750 mm high as per specification in item no. 10 above.	3	No.		
15	Providing and fixing table of size 1600 x 750 x 750 mm high as per specification in item no. 10 above.	5	No		
16	Providing and fixing table of size 1400 x 700 x 750 mm high as per specification in item no. 10 above, but without drawer units.	4	No		
17	Providing and fixing table of size 1200 x 600 x 750 mm high as per specification in item no. 10 above, but without drawer units.	10	Nos		
18	Providing and fixing table of size 1500 x 700 x 750 mm high as per specification in item no. 10 above, but without drawer units.	4	No		
19	Providing and fixing table of size 1600 x 800 x 750 mm high as per specification in item no. 10 above, but without drawer units.	1	No.		
20	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 120 x 45 cm as per specification in item no.11 above	6	No.		

21	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 130 x 45 cm as per specification in item no.11 above	10	No.		
22	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 100 x 45 cm as per specification in item no.11 above	8	No.		
23	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 90 x 40 cm as per specification in item no.11 above	10	No.		
24	Low Level Storage :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exposed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	41	Sq.M		
25	overhead storage :Providing and fixing overhead storage to detail as shown in the drg. Size about 450mm wide, 500mm 600 mm high with openable shutters in front approx 400 mm wide fixed with Autoclosing/ box type hinges, locking arrangements, flush profile handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exposed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. 6mm thick glass shall be provided on shutters wherever required. Measurement shall be taken for the front elevation area.	2	Sq.M		
26	Providing and fixing Rectangular shaped Discussion Table of size 125cm X 90 cm high with curved edges as shown in the drawing comprising of table top out of 19mm thick Plywood with 1mm thick laminate of approved color and brand with side edges with 3mm thick PVC edge band. The table shall have 2 sets of 3 curved Legs joined together with a rectangular centre pillar, both connected with intermediate vertical support along the longitudinal direction, all made up with plywood and laminate as mentioned above. Table shall have cable managers and slot for keeping Mobile/ tablet, pens, cards etc. Legs shall have good quality antislip rubber bushes.	3	No		
27	Column/ Wall Paneling: Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate with necessary grooves, over the aluminium frame work. Anodised aluminium frame work with sections of size 50 x 25 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level.	91	Sq.M		
28	Providing and Fixing 100 mm wide Vertical Blinds of Vista Levton or approved equivalent make and colour.	5	Sq.M		
29	Providing and Fixing Zebra Type progressive designed Roller Blinds of Vista Levton or approved equivalent make and colour.	50	Sq.M		
30	Applying & Finishing existing exterior /interior wall area or ceiling with Acmatex brand texture coating (Latterite stone pattern and other design type) work with Asian Exterior primer coat and Asian apex exterior/Interior emulsion 2 type colour 2 coats each covering and finally acmatex long last clear coat applying	25	Sq.M		

31	Providing & Fixing 12mm thick polished toughened glass display stand for placing indoor plants, trophies etc with SS angle support/ patch fittings etc complete as directed -90x20cm	12	Nos		
32	Providing & Fixing 12mm thick polished toughened glass display stand for placing indoor plants, trophies etc with SS angle support/ patch fittings etc complete as directed -40x20cm	12	Nos		
32	Providing & Fixing 12mm thick toughened glass corner stand (with polished curved outer edge) stand for placing indoor plants, trophies etc with SS angle support/ patch fittings etc complete as directed - 30cm radius	12	Nos		
33	Providing & Fixing display shelf 20x30 cm using 18mm plywood with all exposed faces finished in 1mm laminate & inside faces finished with 6mm mirror/ 8mm glass. Cost includes all material, labour etc complete.	4	Nos		
34	Providing and fixing Acrylic LED backlit emblem & Letters with "SBI Logo" with its standard colour and approx 12" height and "RASMECCC IRINJALAKUDA" with steel/ silver finish with size of approx 8" to 10" height including LED Strip Light, Drive etc complete.	1	LS		
35	Panelling with 3 mm thick aluminium composite panel of approved make and shade cut and bind using router machine and curved using rol over aluminium frame work with 50 x 25 x 1 mm sections as per site condition and instructions of Engineer-in-Charge	25	Sq.M		
36	Full height partly solid and partly Glazed partition :- Providing and fixing in position partly panelled and partly glazed partition as per specification in item no.(2) above but with 8 mm thick float glass with etching between 900 mm and 2100 mm level between the solid partition as per size required at site fixed with necessary SS D brackets. The edges of partition is to be finished with 1 mm thick laminate. Measurement for the partition area shall be consider from the floor level to false ceiling level only.	20	Sq.M		
TOTAL					-

GST AT APPLICABLE RATES WILL BE EXTRA