

PRICE BID FOR CIVIL WORKS OF TUIBONG BRANCH, MANIPUR-RENOVATION					
Sl.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	REINFORCED CEMENT CONCRETE WORK (POST & LINTEL IN UPS ROOM, CASH ROOM & WASHROOMS, 150mm CASH SAFE EMBEDDING INCLUDING COST OF SHUTTERING)				
	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete.	cum	2		
2	IRON AND STEEL WORK				
	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto all levels TMT bars	kg	280		
3	BRICKWORK				
	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to all levels in Cement mortar 1:4 (1 cement :4 coarse sand)	SQM	28		
4	SOLING WORK FOR LEVELLING FLOOR in BACK PORTION BANKING HALL & WASHROOMS				
	Providing 150mm thick soling with approved quality of stone including carriage, watering, ramming, consolidation.	SQM	16.00		
5	PCC WORK				
	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8	cum	7.5		
6	PLASTERING (ON BOTH OLD & NEW WORK)				
	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand). The rate to include old paint and plaster.	SQM	170		
7	TILING WORK IN BANKING HALL AND WASHROOMS				
i)	Providing and laying vitrified anti skid floor tiles of size 600 x 600 mm of approved make and shade, laid on 15 mm thick cement mortar 1:3 (1 Cement :3 Coarse sand) complete at all levels as specified and directed.normal range.	SQM	225.00		
ii)	TOILET:Providing and fixing 1st quality ceramic glazed floor tiles up to 1500mm/2100mm height conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	SQM	35.00		
8	PAINTING WORKS				
i)	Painting Work – Plastic Emulsion with putty Applying three or more coats of plastic emulsion (Asian / Nerolac) including making of surfaces with oil based putty and rubbing, etc. and in case where the surface has been white / colour washed, the old white / colour wash shall be entirely removed and surface broomed / scrapped down before the new paint is applied. Rates include removing of old paint/cleaning splashes from glass panes, floor, furniture etc. The work shall be completed in all respects to the entire satisfaction of the EIC.	SQM	260.00		
ii)	Finishing walls with textured exterior paint of required shade including scaffolding and putty. The rate to include removal of old paint.	SQM	250.00		
iii)	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture.	SQM	200.00		

PRICE BID FOR CIVIL WORKS OF TUIBONG BRANCH, MANIPUR-RENOVATION					
Sl.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
9	SANITARY & WATER SUPPLY WORKS				
i)	Providing and fixing floor mounted, white vitreous china single piece, double traps siphonic water closet of approved brand/ make, shape, size and pattern including integrated white vitreous china cistern of capacity 10 litres with dual flushing cistern including all fittings and fixtures with seat cover, cistern fittings, nuts, bolts and gasket etc including making connection with the existing P/S trap complete in all respect as per directions of Engineer-In-Charge.	Each	2		
ii)	Providing and fixing pedestal wash basin of size 550x400 mm with a 15 mm CP Brass single hole basin mixer with C.I. brackets, 15 mm dia CP Brass single hole basin mixer of approved quality and make, including coupling, waste pipe, trap, painting of fittings and brackets, cutting and making good the walls wherever required.	each	2		
iii)	Urinal: Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350, including drain pipes, painting of fittings and brackets, cutting and making good the walls and floors etc. wherever required : (make:Cera/Parryware).	Each	1		
iv)	Providing and fixing C.P. Brass short body PILLAR cock of Jaquar BRAND weighing not less than 690 gms	each	2		
v)	Supplying fitting and fixing 2-in-1 bib cock of approved brand.	Each	2		
vi)	Supplying fitting and fixing chrome plated (C.P.) angular stop-cock of 15mm dia of Jaquar brand.	Each	5		
vii)	Providing and fixing glass shelf 440 mm long, 124 mm width and 36 mm height of approved quality and colour, weighing not less than 300 gms	Each	2		
viii)	Providing and fixing 1500x450 mm beveled edge mirror of superior glass (of approved quality) with SS screws and washers complete.	Each	2		
ix)	Providing and fixing health faucet of parryware, Jaquar brand.	Each	2		
x)	Providing and fixing PVC (6kg) drainage pipes complete with fittings and clamps, bends etc complete as per direction of engineer in charge:75 mm /100 mm dia	Rm	40.00		
xi)	Providing and fixing UPVC/HPVC pipes complete with fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 25 mm dia/15 mm dia	Rm	50.00		
Xii)	Constructing inspection chamber with brickwork of size 60x60x75cm with RCC top lid.	Each	1		
10	STEEL WORK:				
I)	METAL DOOR FOR UPS ROOM : Providing and fixing 1mm thick MS Sheet door with frame of 40x40x6mm angle iron and 3mm MS gusset plates at the junctions and corners, all necessary fitting complete, including applying a priming coat of approved steel primer. Using MS angles 40x40x6mm for diagonal braces.	SQM	2		
11	ROOF TRUSS				
i)	Structural steel work built up tubular (round, square or rectangular hollow tubes, etc.) trusses, etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding, and bolted with special shaped washers, etc. complete.	kg	1200.00		
ii)	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275 gm/ m ²	Sqm	300.00		
iii)	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ²	RM	33.00		
iv)	Providing and fixing 15cm wide 45 cm over all semi circular plain GS Sheet gutter with iron brackets 40x3mm size, bolts, nuts and washers etc i/c making necessary connections with rain water pipes complete.	RM	33.00		

PRICE BID FOR CIVIL WORKS OF TUIBONG BRANCH, MANIPUR-RENOVATION					
SI.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
12	COLLAPSIBLE GATE				
	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	SQM	13.00		
13	ROLLING SHUTTER				
	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	SQM	4.00		
14	Dismantling of existing brick walls, doors, etc and carting away to desired location as per Municipal bye-laws.	Job	1		
				Total	
	Cost is exclusive of GST				