

**PRICE BID FOR INTERIOR AND FURNITURE WORKS OF WANGOI BRANCH, MANIPUR-RENOVATION**

SI.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Single Level SWO Counters: Providing and fixing at site SWO counters each as per design and drawing. SWO counters to be made of 19 mm thick BWP ply with 1.0 mm thick laminate on outer visible surfaces (single color on horizontal surface & two colors on vertical surfaces), with 40 mm X 12 mm thick teak wood beading required all around, as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the counter. The top with Curvilinear profile shall be made out of 19mm thk. BWP block board and finished with 6mm thk. flexi ply as base for acrylic sheet as per design with provision for LED Light in bottom. Teak wood lipping will be provided on all the remaining edges of the counter, including bottom touching the floor and the drawers. The counter shall have a keyboard tray of size 600 X 270 finished with laminate on top side with back support, of EBCO make fixed on channels, as per manufacturer's instructions / specifications.				
	Three drawers with autolock running on both sides mounting Telescopic(channels) of EBCO make, made of 19mm thick BWP ply with 1mm thick laminate on front face and drawer locks to be provided on one side of the counter as per layout. The sides of the drawers shall be made of 12mm thick plywood, bottom of 6mm thick plywood & front of 19mm thick BWP ply. Non-Visible/ inside surfaces i.e. inside/ leg space of table, inside of drawer / cupboard shall be finished with liner / laminate of 0.7 to 0.8mm thk. off white / white colour and all exposed Teak wood edges / teakwood lipping beading shall be spirit (natural) polish as required. The drawers shall have partitions for keeping currency notes & the counter should also include foot rest, Space for CPU as per drawing, complete in all respects. The provision of swiping machine of green channel size 9"x6" with lid shall be provided at right side of each counter while facing from front.				
	Supplying, providing and fixing Auto lock at cash drawers and Godrej Cylindrical night latch lock at cash enclosure doors.				
	8.0 MM thk glass on top of all tables. All the edges of the glass shall be grinded polished including Hole for cable manager.				
(I)	1800mm length, 750mm height and 750mm depth	Each	2	₹ 25,000.00	
(ii)	2000mm length, 750mm height and 750mm depth	Each	1	₹ 26,000.00	
2	<b>Tables</b> Table made of 19 mm thk. BWP ply with Table front and side visible vertical surfaces to be finished with 1.0 mm thk. laminate of approved colour & shade, with 40 mm X 12 mm thick teak wood all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer / electrical cables at appropriate place will be made in the top surface of the table. The wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 of EBCO make fixed on channels finished with laminate, as per manufacturers instructions / specifications. The table top should be finished with 1mm thick laminate.				
	A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, at 4" above the floor level and 3" away (horizontally), from vertical end which will be made of 19 mm thick BWP ply finished with 1.0 mm thk. laminate and 3/4" x 1/4" teakwood lipping on all visible sides. One drawer with lock and one cupboard with shutter made of 19 mm commercial ply with 1.0 mm laminate on front side of cupboard shutter with shutter having good quality locks, magnetic catcher, hinges, handle / knob etc. is to be provided. The shutters shall be provided beneath the drawers with each counter on its right / left hand side. The sides of the drawer shall be made of 12 mm thick plywood / 19 mm ply, bottom of 6 mm thick plywood & front of 19 mm thick ply. A full length foot rest made of hard wood 3" x 2" section shall be provided at 4" above floor level. Non-Visible / inside surfaces i.e. inside / leg-space of table, inside of drawer / cupboard shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be spirit (natural) polish.				
	8.0 MM thk glass on top of all tables. All the edges of the glass shall be grinded polished including Hole for cable manager.				
(I)	Branch Manager: 2100mm (L)x 900mm (D)x 750mm (H) with side credenza. The front portion of table should have yellow color 10mm thick lacquered glass modesty panel.	Each	1	₹ 31,000.00	

**PRICE BID FOR INTERIOR AND FURNITURE WORKS OF WANGOI BRANCH, MANIPUR-RENOVATION**

SI.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
(ii)	Field Officer: 1800mm (L)x 7900mm (D)x 750mm (H) with side credenza	Each	1	₹ 26,000.00	
(iii)	Officer/Assistant: 1500mm (L)x 7900mm (D)x 750mm (H) with side credenza	Each	1	₹ 26,000.00	
(iv)	Fabricating and installing Grahak Mitra table of overall size - 1500mm x 600mm x 750 mm in straight or curved profile made up of 19mm thick block board of approved brand all around and finished with not less than 1mm thick laminate of brand, colour and shade as approved by the Bank. The table cost to include three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide, foot rest & CPU stand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type. All exposed edges to have wooden lipping/bidding of required size, stained to match the desk and melamine finished. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on table and necessary cut-out to accommodate wires, edges to be m/c polished, with m.s. powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy.	Each	1	₹ 25,000.00	
3	<b>Writing desk / Customer Voucher Stand / Forms Stand including Pass Book, Cheque Drop &amp; Suggestion Box</b> Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L shaped, wall hung) including provision of Pass Book, Cheque Drop & Suggestion Box as per drawings made of 19 mm thick BWP ply with 1.0 mm thick laminate to be fixed and 3/4" x 1/4" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall cost of spacers ect all inclusive complete.	Each	2	₹ 5,000.00	
4	<b>Back credenza / Storage</b> Providing & fixing back credenza 18" deep (top surface 18" to 24" as per site) & 3'0" HT. made of 19 mm thick BWP ply board and 6 mm thick plywood on back side & finished with 1.0 mm thk. laminate of approved colour on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The back credenza will have cupboard with shutters and one shelf. The shutters with handle and magnetic catcher shall be provided beneath the drawers and Non-Visible / inside surfaces i.e. inside of cupboard & shelves shall be finished liner of 0.7 to 0.8 mm thk. off white / white colour and teak wood edges / lipping / beading shall be Spirit polished with matching pigment.	SQM	5.00	₹ 7,500.00	
5	Providing & fixing <b>counter Front 12 mm thick float glass</b> with polished edges, fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Rate shall includes fixing of frost film as per design & directed, cost of studs, making cut-outs for transaction and <b>voice hole</b> .	SQM	3.00	₹ 3,500.00	
6	Providing & Fixing <b>12 mm thick float glass</b> of size 320mm (width) x 1100mm (height) & tapering towards bottom as per the design and shape as shown in Bank's new uniform colour, layout & elevation policy, fixed with silicon and T.W beading support on wooden partition as directed, on either sides of SWO as per design. Rate shall includes etching of glass as directed by bank. All edges of glass shall be duly beveled & polished as directed complete. Make: Saintgobin/ Modiguard or equivalent.	SQM	2.00	₹ 3,500.00	
7	Fabricating and fixing column & wall paneling ( <b>inside BM's chamber &amp; back of SWO counters</b> ) with 6mm thick ply finished with not less than 1mm thick laminate of approved shade & brand over framework at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface. Design and detail shall be as per direction of EIC.	SQM	74.00	₹ 2,800.00	
8	Fabricating and fixing <b>low/full height solid/semi-glazed partition</b> , made of 6 mm ply approved brand both side and to be finished with not less than 1mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood bidding/lipping of required size with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate to include etching work.	SQM	54.00	₹ 3,000.00	

**PRICE BID FOR INTERIOR AND FURNITURE WORKS OF WANGOI BRANCH, MANIPUR-RENOVATION**

SI.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
9	Electrical panel Niche / covering for branch. Providing and fixing electrical niche upto 18" to 24" deep as per drawing / instructions with outer frame made of 19 mm thick BWP block board with 1.0 mm thick laminate on all outer visible surfaces as per pattern / design / Battens for ventilation. The inner surfaces shall be finished with enamel paint. Work also includes providing and fixing of doors as per drawing and specifications. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall also include for providing grooves in laminate & wood, hardware like hinges, handles, chitkney & locks etc. The work should be done to the entire satisfaction of the Architect / Engineer. For measurements front shall be measured.	SQM	1.00	₹ 4,000.00	
10	Providing and fixing <b>solid/Semi glazed doors shutter</b> made up of 38 mm thick block board of approved brand and quality, finished both side with not less than 1mm thick laminate of approved brand, colour and shade. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Saintgobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as required by bank.	SQM	11.00	₹ 5,000.00	
11	WICKET GATE: Providing and fixing low height door shutter in back side of SWO counter made up of 38 mm thick block board of approved brand and finished with not less than 0.8 mm thick laminate of approved shade and brand as per design and direction of bank. The door shall includes all hardware such as: ss hinge with countersunk ss screw, handle, door coloser, door stoper etc. of approved make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent	SQM	2.50	₹ 4,000.00	
12	<b>ALUMINIUM GLAZED DOOR FOR UPS ROOM &amp; ATM ROOM</b> : Providing & fixing aluminum openable door comprising of approximate 83.5mm vertical members, black powder coat (minimum thickness of powder coating 50 micron) and thickness of section not less than 1.5mm, 6mm float glass openable with 4 nos 3" SS hinges, handle, door closer, etc. The rate to include design etching as directed by EIC.	SQM	4.00	₹ 5,000.00	
13	<b>ALUMINIUM GLAZED PARTITION FOR ATM ROOM</b> : Providing and fixing glazed black color aluminium partition with 6 mm thick clear float glass both side, having 12 mm air gap, including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. as per specifications, drawings and direction of Engineer-in-charge complete	SQM	8.00	₹ 4,500.00	
14	<b>MAIN DOOR</b> : Providing and <b>fixing glazed door</b> made of 12 mm thick float glass (Make: saintgobin, modigurd) with frosted film fixed in between top & bottom rail and wood framework of size 125 mm x 50 mm with melamine polish. Glass to have etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring. Rate shall includes all hardwears such as: Two nos S.S. finish handle, lock, door stopper, hinge, tower bolt etc. of approved make.	SQM	3.20	₹ 6,000.00	
15	<b>False ceiling (Mineral fibre)</b> Providing and fixing false ceiling at all heights, made of 600 mm X 600 mm X 16 mm, RH 99 mineral fibre ceiling tiles of type – Fine Fissured micro lock with silhouetted grid (black reveal), Tegular edge, laid on Manufacturer's exposed grid systems. The frame work comprises of main rubber spaced at 1200 mm c/c, securely fixed to the structural soffit by approved hangers of spacing not more than 1200 mm c/c. Hangers (G.I. wire of 4 mm dia.) to be fixed by approved rawl plugs, level adjusters & screws etc. The last hanger at end of each main runner should not be more than 450 mm from the adjacent wall.	SQM	80.00	₹ 2,000.00	
	Flush fitting 1200 mm long Cross T's (with double stitching) to be interlocked between main runners at 600 mm c/c to form 1200 mm X 600 mm modules. Cut cross T's longer than 600 mm to be supported independ-ently. 600 mm X 600 mm modules to be formed by fitting 600 mm long flush fitting cross T's centrally between the 1200 mm Cross T's. The rates shall be inclusive of making opening with frame etc. for electrical / air conditioner & finishing of ceiling in all respect, the work includes provision of trap door if required.				

**PRICE BID FOR INTERIOR AND FURNITURE WORKS OF WANGOI BRANCH, MANIPUR-RENOVATION**

SI.No	Description of items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
16	<b>False Ceiling With Steps. &amp; Cove - Gypsum Board</b> Providing and fixing suspended false ceiling (as per specification of manufacture ) including steps as per design with 12.5 mm tapered edge Gyp-board / 12 mm thick Elephant Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20 mm X 27 mm X 37 mm X 3.5 M) fixed round the perimeter to receive and of the ceiling section (MF5) and the outer edges to gyp-board. The intermediate channel (MF7 of dimensions 15 mm X 45 mm X 0.9 mm X 3.6 M) at 1200 mm c/c in the one direction and the ceiling section (MF5 of dimensions 80 mm X 26 mm X 0.5 mm X 3.6 M) at 450 mm c/c in the other direction are connected by a connecting clip (MF9).	SQM	92.00	₹ 1,200.00	
	The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25 mm X 0.5 mm at 1200 mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts / fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together. The gypsum board layers are screwed to the M/F ceiling sections with gyp-board drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. A/C ducting etc. The work should be complete as per instructions of Architect or Engineer in charge. The rates should be inclusive of two or more coats of plastic emulsion over a coat of primer to give an even shade.				
	The rate should be inclusive of making opening with frame etc. for electrical / air conditioner, A.C. grills & trap door etc. if required & finishing of ceiling in all respect. Steps / Vertical bands / cove shall be measured in square feet. Payments shall be made only for exposed surfaces & actual measurement at site. The work includes cost and conveyance of materials and labour charges including. All operational charges, tools, lifts and all heights etc.				
17	<b>Extra for cove over gypsum board false ceiling</b> Providing and fixing cove in suspended false ceiling as instructed including all required sections / parameters & labour as per mentioned above. Measurement shall be made from bottom external band only.	Rm	73.00	₹ 270.00	
18	Providing & fixing in place 100 mm. <b>Vertical blinds with scotch guard</b> of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate.	SQM	11.00	₹ 1,500.00	
19	<b>OUTSIDE OF BRANCH &amp; ATM ROOM :</b> Providing & fixing in position Aluminium Composite Panel (ACP) /Shutter boxing Panelling with framing in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.	SQM	52.00	₹ 3,000.00	
				<b>Total</b>	
	<b>Cost is exclusive of applicable GST</b>				