

PRICE BID						
FALSE CEILING WORK ON 9th FLOOR, CCPC, SBI, AT LAL DARWAZA (OLD LHO BUILDING), AHMEDABAD.						
Note:Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage & removing of existing gypsum board false ceiling and grid ceiling as per instruction by bank etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills						
SN	Description	Quantity	Unit	Rate/Unit in Figures	Rate/Unit in Words	Amount in ₹
	FALSE CEILING WORK					
1	P/F GYPSUM BOARD FALSE CEILLING	450.00	SMT			
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA/Serra (Gypsteel Ultra/Serra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification. Note : (1) Rate includes dismantalling of existing GYPSUM/ AMF/ POP false ceiling including stacking of servicable materials & disposal of unservicable materials & making necessary cut outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.					
2	Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceilling system with fine fissured (micro lock)edge tiles with Armstrong Silhouette Exposed Grid. Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only cost of tiles will be deducted for payment purpose. After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications. Rate includes dismantalling of existing Mineral fibre ceiling.	285.00	SMT			
3	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)	350.00	SMT			
	Providing and applying (with rollers only) Acrylic emulsion paint of required shade and approved make on old/new surface in two or more coats to give an even shade including the preparation of surface for painting, applying full primer and putty at all heights complete as per manufacturer's specification and as directed.					
	TOTAL COST					
						Plus GST as applicable