

**PRICE BID**

**AIR CONDITIONING WORKS FOR 9th FLOOR, CCPC, SBI, ADMIN. OFFICE, LAL DARWAJA, AHMEDABAD.**

Sr.	DESCRIPTION	UNIT	QTY	RATE	TOTAL
1	Air distribution ducting made out of G.I. sheet including collars, class VIII conforming to IS 655 including supports, bracing, flanges, turning vanes, fasteners, rivets, gaskets, nuts & bolts, etc. complete at every 2.4 m c/c & at bends etc. as per specifications. 0 - 750 mm : 24 Gauge (Rectangle Duct)	SQMT	10.00		
2	Supply & Installation having <b>19 mm</b> thick closed cell nitrile <b>class 'O'</b> rubber insulation with aluminium sheet/foil on Supply/Return GI Ducting	SQMT	650.00		
3	Supply and Installation of MS Supporting of proper size for Duct work (Min. 35X5 MM Angle for MS support)	JOB	1.00		
4	Existing Duct Dismantling /lowering down and Re-installation of duct with removing and re-installation of existing grill after insulation work	JOB	1.00		
5	Supply and Installation of Aluminium powder coated grill as per specifications complete as required.	SQMT	20.00		
	<b>Total Amount</b>				