

PRICE BID FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR HLST IN OLD SBI ZONAL OFFICE AMBAWADI AT AHMEDABAD					
Rate should be inclusive of material, labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.					
Sr. No.	Description	Quantity	Unit	Rate	Amount
1	TABLES				
1.01	TABLE SIZE: 6'-0" X 3'-0" X 2'-6" HT. (AGMs Table)	2.00	NOS		-
	Supplying and installation of Table as per the following description: Size 6'-0" x 3'-0". Table top shall be made from 18 mm thick commercial plywood with necessary support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawer Storage Unit- 1'-4" W x 2'-0" D shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make, grouplock, S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the CABINET shall have laminate, All internal surface will have 0.80 mm thick balancing laminate.				
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate as per drawing				
	Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.				
	Readymade CPU trolley with caster and metallic cable Manager shall be provided in table. All exposed edges of teak wood shall have polished with smooth edges & corners				
	All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate of approved shade. Etc. complete.				
	As per drawing and instruction of Architect/Bank work to be Completed				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 18 mm thick commercial plywood with equal sized 10mm thick back painted toughened glass				
	2) Front Apron & Sides : 1.0 mm thick Dark Laminate				
	3) Facing of Drawers : 1.0 mm thick Dark Laminate				
	4) All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate				
1.02	TABLE SIZE: 5'-0" X 2'-6" X 2'-6" HT.	12.00	NOS		-
	Same as above Item-no-1.02 but 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. (For Sales and Service)				
1.03	LINEAR TABLE SIZE: 4'-0" X 2'-0" X 2'-6" HT.	4.87	RMT		-
	Providing and fixing Linear Table having width of 2'-0" using 18 mm thick Commercial plywood for Top and verticle support at 4'-0" c/c, Providing storage cabinet 3 drawers at Every 4'-0" c/c, Group lock, SS handle in counter as directed complete. 1.0 mm thick Laminate finish on table Top and front side of shutter. Providing ready made Foot rest CPU stand trally with castor and metallic cable Manager shall be provided in table top All internal surfaces shall have 0.80 mm thick balancing laminate as directed. [FOR DETAIL REFER DRG] (For Assit.)				
2	STORAGE				
2.01	SIDE CREDENZA	9.80	SQ.MT		-

PRICE BID FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR HLST IN OLD SBI ZONAL OFFICE AMBAWADI AT AHMEDABAD					
Rate should be inclusive of material, labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.					
Sr. No.	Description	Quantity	Unit	Rate	Amount
	Supplying and providing side cabinet for keeping computer and printer size 1'-4" width 2'-6" height and 3'-6"/3'-0" length. Openable shutter with 1.0mm thick laminate finish on Top, front side shutter and 35 mm x 6mm thick Burma Teak beading on Top Edges with melamine polish. Laminate to be provided only on visible surface etc complete as follows. Having openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood with 1.0mm thick laminate Finish. back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18mm thick commercial ply wood with laminate finished and approved make group lock, S.S. handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All internal surfaces shall have 0.80 mm thick balacing laminate as directed.				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. As per drawing and instruction of Architect/Bank Complete				

PRICE BID FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR HLST IN OLD SBI ZONAL OFFICE AMBAWADI AT AHMEDABAD					
Rate should be inclusive of material, labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.					
Sr. No.	Description	Quantity	Unit	Rate	Amount
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : Dark Laminate & Burma Teak beading on Edges with polished				
	2) Front Apron & Sides: Dark Laminate				
2.02	BACK SIDE STORAGE CABINATE				
	Supplying and providing storage cabinate with 1.0mm laminate on Top, Front Shutter & 35mm x 6mm thick Burma Teak beading on Edges with polish. Laminate to be provided only on visible surfaces.	8.60	SQMT		-
	Size : Depth 1'-4", 3'-0" ht. having openable shutter as directed. storage Cabinet shall be made from 18mm thick commercial ply wood for Top with 1mm laminate finish and 18mm thick ply wood for verticle, shelves, shutters and 6mm commercial plywood for backing with 1mm laminate on all exposed surface. with verticle (at 3'-0" c/c) shelves at 1'-3" c/c Openable shutters in 18mm thick commercial ply wood with all S.S hinges, towers bolts, S.S. handle, ball catches, S.S approved make (group lock) multi purpose lock complte. Edges to be finished with teak wood lipping etc. Laminate to be provided only on over visible surface. Front surface area shall be measured for payment purpose. All internal surfaces shall have 0.80 mm thick balacing laminate as directed.				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : Dark Laminate & Burma Teak beading on Edges with pilished				
	2) Front Apron & Sides: Dark Laminate				
2.03	P/F ELECTRIC CUB BOARD	5.00	SQMT		-
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, S.S. hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-6". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.				
3	PARTITION WORK AND DOORS				
3.01	LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS	33.60	SQMT		-
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass with machine cut eadge as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed. The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, etc., complete as per drawings and as directed by the Engineer-in-charge at site. contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabelling and No extra amount shall be paid for this.				
3.02	BOTH SIDE LAMINATE PARTLY GLAZED / SOLID FULL HEIGHT PARTITION WITH DOOR	18.50	SQMT		-

PRICE BID FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR HLST IN OLD SBI ZONAL OFFICE AMBAWADI AT AHMEDABAD					
Rate should be inclusive of material, labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.					
Sr. No.	Description	Quantity	Unit	Rate	Amount
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 8 mm thick float glass as directed in the partition. Including Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 8 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, door closer, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed. [REFER DRG]				
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid. The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. No extra payment shall be made for members going up to slab/beam bottom. contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this.				
3.03	FULL HEIGHT FULLY GLAZED PARTITION WITH 12MM TOUGHENED GLASS	14.4	SQMT		-
	Providing & fixing full height glazed partition with 12mm Toughened glass of approved make up to 7'-0"/8'-0" level height with solid partition above 7'-0"/8'-0" level up to false ceiling bottom.				
	The glazed panels shall be fixed to the existing floor and false ceiling with all necessary SS brackets (D, C or U type) Vertical joints between the glass panels shall be sealed with suitable transparent sealant.				
	The solid partition above 7'-0"/8'-0" level shall be made with aluminium framework of size 50mm X 25mm X 1.50mm box section. The spacing of the Horizontal and Vertical members are approximately 600mm c/c (maximum) and the top of the frame shall be fixed to the RCC slab bottom. The exposed surfaces on both sides of framework are covered with 6mm BWR ply finished with 1.0mm thick laminate as per direction including 3M glass film of approved design up to 4'0" height.				
4	PANELLING WORK				
4.01	PANELING WITH ALUMINIUM FRAMING (FINISH: LAMINATE)	39.20	SQMT		-
	Providing and laying panelling on walls & pillars having 12mm thick approved make BWR plywood + 4mm MDF and 1.0mm thick laminate fixed on wall & pillars with 4mm x 4mm groove pattern as per detail. Aluminium framing of 50mm x 25mm x 1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed. The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, etc. complete as per drawings and as directed by the Engineer-in-charge at site. panelling as per design and instruction of Architect. contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this.				
5	DOORS				
5.01	FULLY GLAZED DOOR - - Size 900mm x 2100mm	7.60	SQMT		-
	Providing and fixing in position frameless glass door shutter made using 12mm thick toughened glass fixed to the partition (glazed / solid / gypsum partitions) using heavy duty floor spring with pivot of approved make including necessary cutting of floor and making the surface good to its original position including all necessary Patch fittings of approved make and fixtures & hardware.				

PRICE BID FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) FOR HLST IN OLD SBI ZONAL OFFICE AMBAWADI AT AHMEDABAD					
Rate should be inclusive of material, labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.					
Sr. No.	Description	Quantity	Unit	Rate	Amount
	Approved make: DORMA Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Handle - TG DIH600 - 600mm length) or equivalent brand fittings from Hettich / Hafele / as per sample approved by the Bank. Rate should also include providing 3M Glass Film as per design/ instructions of Bank.				
	Mode of Measurement: Door opening size shall be measured.				
6	ROLLER BLINDS	29.70	SQMT		-
	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shed. (Basic Price of Rs 135=00 Per Sq.Ft)				
7	GRID FALSE CEILING	136.20	SQMT		-
	Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid.				
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose. Item includes Removing of Existing false ceiling with frame, sheet etc.and disposal of unserviceable material behind the Municipal limit.				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications.				
8	GYPSUM BOARD FALSE CEILING	57.40	SQMT		-
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA/Serra (Gypsteel Ultra/Serra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India. Item includes cove pattern as per detail drawings and as directed by Architect/Bank's Engineer.				
	After completion of work to certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification				
	Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.				
	TOTAL COST OF FURNITURE WORK			Rs.	-
	GST will be extra as applicable				