ART-A: ELECTRICAL WIRING WORKS 1 ENRRGY METER CUBICLE: Fabrication, Supply, Installation, testing & Commissioning of energy Meter cubicle made out of 16 SWG CRCA sheet consisting of the following. (to be fixed outside the building). FOR 3-PHASE ENERGY METER- for Branch,separate chamber for energy meter (with fixing plate, view glass and holes with rubber gromets), CTs, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4 pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (CA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor SKVAR Resin Capacitor with Harmonic fitter	ı	Particulars : Detailed Specifications			Rate	Amount
1 ENERGY METER CUBICLE: Fabrication, Supply, Installation, testing & Commissioning of energy Meter cubicle made out of 16 SWG CRCA sheet consisting of the following. (to be fixed outside the building). FOR 3-PHASE ENERGY METER- for Branch,separate chamber for energy meter (with fixing plate, view glass and holes with rubber gromets), CTS, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,V,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 2D KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 2SkA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor SKVAR Resin Capacitor with Harmonic fitter	ΔRT	· ·	Offic	Kaaricid	Nate	Amount
& Commissioning of energy Meter cubicle made out of 16 SWG CRCA sheet consisting of the following. (to be fixed outside the building). FOR 3-PHASE ENERGY METER- for Branch,separate chamber for energy meter (with fixing plate, view glass and holes with rubber gromets), CTs, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (RY, B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor SKVAR Resin Capacitor with Harmonic fitter						
CRCA sheet consisting of the following. (to be fixed outside the building). FOR 3-PHASE ENERGY METER- for Branch,separate chamber for energy meter (with fixing plate, view glass and holes with rubber gromets), CTs, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A 5P MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25KA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter	_					
building). FOR 3-PHASE ENERGY METER- for Branch,separate chamber for energy meter (with fixing plate, view glass and holes with rubber gromets), CTs, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,V,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,V,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter						
chamber for energy meter (with fixing plate, view glass and holes with rubber gromets), CTs, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c O.S) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter			Sot			
with rubber gromets), CTs, Cutouts & switchgear etc. and consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with fons of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		, ,	361	"		
consisting of the following. 3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter						
3 Nos. 63A Open Type bakelite cutout fuse unit with 63A HRC fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25KA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter		1				
fuses 1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter						
1 no. 63A 4 pole SFU with 63A HRC fuse (HPL/C&S/Indoasian) Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter						
Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter						
BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter		I				
2 BUILDING MAIN PANEL: MAINS CHANGE OVER PANEL Supply and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter		l · · · · · · · · · · · · · · · · · · ·				
and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set — ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		INAL 7032 Siemens grey.				
and installation of 63A 4pole ON Load Change over switch with suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set — ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		BUILDING MAIN PANEL : MAINS CHANGE OVER PANEL Supply				
suitable metallic enclosure with cable entry Box and Powder coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set – ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAR Resin Capacitor with Harmonic fitter	_	1				
coated painted with 6nos of 2A SP MCB and LED (R,Y,B) indicators for the identification of EB/ DG Set — ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter						
for the identification of EB/ DG Set — ON & neat marking thereof: (GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		·	Set	1 1		
(GA drawing to be got approved from consultant/Engineer before fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter				_		
fabrication & supply) a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		· · · · · · · · · · · · · · · · · · ·				
a. Change over switch: 63A On-Load COS b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter						
b. MFM - (c 0.5) to show the V,A,pf,kW,kVA,etc details (L&T or Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter						
Schnider) c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		l -				
c. SPD - Type-1+2 d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter						
d. R,Y,B Indicators for EB & DG supply (6nos) e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		·				
e. 1A SP MCB - 6 nos Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		I				
Complete with all inter connections and powder coated painting-RAL 7032 siemens grey. 3 Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		1				
RAL 7032 siemens grey. Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter						
Supply & Installation of 20 KVAR automatic capacitor panel cubical type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		l · · · · · · · · · · · · · · · · · · ·				
type, floor mounting made of 16.SWG CRCA sheet., Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter	3			_		
Incoming 63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		· · · ·	Set	0		
63A, 25kA, 4P MCCB with spreader 0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		1				
0-100A ammeter with selector switch RYB indicating lamp 0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		l -				
0-500 Volts, Voltmeter 6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		•				
6 Stage A.P.F.C. Relay Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		RYB indicating lamp				
Outgoing 63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		0-500 Volts, Voltmeter				
63A TPMCB Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		6 Stage A.P.F.C. Relay				
Capacitor duty contactor 5KVAr Resin Capacitor with Harmonic fitter		Outgoing				
5KVAr Resin Capacitor with Harmonic fitter		63A TPMCB				
		Capacitor duty contactor				
ON-OFF push button & Ind Lamp		5KVAr Resin Capacitor with Harmonic fitter				
		ON-OFF push button & Ind Lamp				

	<u></u>		1	I	1
4	Main DB – (VTPN - DB): Supply, Installation, testing and				
	Commissioning of Double Door TPN DB consisting of the	Set	0		
	following.				
	Double door 4-way VTPN MCB VDB				
	Incomer				
	1				
	63A, 25kA, 4P MCCB				
	Outgoings:				
	63A, TP MCB (C-series) -0nos				
	40A, TP MCB (C-series) -2nos				
	25A, TP MCB (C-series) -1nos				
	16A, TP MCB (C-series) -2nos				
	16A, SP MCB (C-series) - 3nos				
	10A, SP MCB (C-series) - 0nos				
	160A COPPER Bus-bar for 3 phase				
	Complete with all inter connections.				
5	DB – (TPN - DB): Supply, Installation, testing and Commissioning				
	of Double door (6-way) TPN MCB DB consisting of the following.	Set	1		
	, ,,	_			
	Double door 6-way TPN MCB DB				
	_				
	Incomer				
	32A,300mA 4P RCCB +32A MCB C-series				
	Outgoings :				
	16A,100mA 2P RCCB + 16A 2PMCB C-series -1nos				
	16A,30mA 2P RCCB +16A 2PMCB C-series -1nos				
	25A, TP MCB (C-series) -0nos				
	16A, TP MCB (C-series) -0nos				
	16A, SP MCB (C-series) - 4nos				
	10A, SP MCB (C-series) - 4nos				
	6A, SP MCB (C-series) - 4nos				
	80A COPPER Bus-bar for 3 phase				
	Complete with all inter connections.				
	complete with an inter connections.				
-	DDDD: Supply Installation testing and commissioning of Double				
6	RPDB: Supply, Installation, testing and commissioning of Double	Set	0		
	door TPN MCB DB consisting of the following.				
	Double Door 6-way TPN MCB DB				
	Incomer:				
	16A,100mA 4P RCCB +40A 4PMCB C-series				
	Outgoings :				
	16A, SP MCB (C-series) -Onos				
	10A, SP MCB (C-series) -6nos				
	6A, SP MCB (C-series) - 4nos				
	Complete with all inter connections				
7	ESSENTIAL DB: Supply, Installation, testing and Commissioning of	Set	1		
	Double door SPN MCB DB consisting of the following.	Jel			
-	· '		-	-	-

	Double door 4-way TPN MCB DB				
	Incomer :				
	32A TP MCB (C-series)				
	Outgoings :				
	25A MCB TP (B-series) - 2Nos UPS INPUT				
	6A, SP MCB (B-series)-2				
	24hr digital timer 1NO,1NC - 1 nos signage board lighting				
	Complete with all inter connections.				
	complete that an inter-connections.				
8.a	LDB: Supply, Installation, testing and commissioning of Double				
	door TPN MCB DB consisting of the following.	Set	0		
	Double Door 4-way TPN MCB DB				
	Incomer:				
	32A,30mA 4P RCCB +40A 4PMCB C-series				
	Outgoings :				
	16A, SP MCB (C-series) -Onos				
	10A, SP MCB (C-series) -6nos				
	6A, SP MCB (C-series) - 4nos				
	Complete with all inter connections				
	Complete with all inter connections.				
9	BUS BAR Box – Supply, Installation, testing and Commissioning of				
	single door Bus bar box with following.				
a.	100A Copper bus bars-25mmX3mm X150mm -4nos with				
	insulators mounted on insulator bushes. \ / for remote UPS	Set	0		
	Rooms				
b.	200A Copper bus bars-25mmX4mm X150mm -4nos with				
	insulators mounted on insulator bushes. \ / for remote UPS	Set	0		
	Rooms				
С	100A 4P Isolator with suitable enclousure	Set	1		
10	UPS IN PUT DB Supply and installation of 40 A FP MCB ISOLATOR	Cat	2		
	in suitable metallic enclosure for UPS Input.	Set	2		
11	UPS OUT PUT DB Supply and installation of 32A DP MCB	Cot	2		
	ISOLATOR in suitable metallic enclosure for UPS Input.	Set	2		
12	UPS CHANGE OVER PANEL: Supply erection testing and				
	commissioning of 2 Nos. 32A rotary type change over switch in				
	suitable metal box with 4 Nos. LED indicator for input / output	Set	1		
	identification. UPS Output change over switch board. Complete				
	with all inter				
13	COMPUTER DB: Supply, erection, testing and commissioning of				
	wall mounted type double door dust and vermin proof SPN MCB	Set	2		
	DB fixed on wall comprising the following:				
	SPN MCB DB - 8Way				
	Incomer :				
	· '	'		1	1

conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Separate of the suitable weather proof enclosure(IP65) for local control of 3ph air conditioners.	Set 0 Set 0 Set 0	
10A, SP MCB (C-series) -2 6A, SP MCB (C-series) - 4 Complete with all inter connections. 14 Supply and installation of suitable weather proof enclosure for local control of 3ph/1ph air conditioners. a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 16 Supply and installation of DOL starter for PUMP motor with Septimber 16 Supply and installation of DOL starter for PUMP motor with Septimber 16 Supply and installation of DOL starter for PUMP motor with Septimber 16 Supply and installation of DOL starter for PUMP motor with Septimber 17 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Supply and installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter for PUMP motor with Supply and Installation of DOL starter	Set 0	
6A, SP MCB (C-series) - 4 Complete with all inter connections. 14 Supply and installation of suitable weather proof enclosure for local control of 3ph/1ph air conditioners. a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 15 Supply and installation of DOL starter for PUMP motor with	Set 0	
Complete with all inter connections. 14 Supply and installation of suitable weather proof enclosure for local control of 3ph/1ph air conditioners. a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 16 Supply and installation of DOL starter for PUMP motor with Septimber 17 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Septimber 19 Supply and installation of DOL starter for PUMP motor with Septimber 19 Supply and installation of DOL starter for PUMP motor with Septimber 19 Supply and installation of DOL starter for PUMP motor with Septimber 19 Supply and installation of DOL starter for PUMP motor with Septimber 19 Supply and installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter for PUMP motor with Septimber 19 Supply and Installation of DOL starter	Set 0	
14 Supply and installation of suitable weather proof enclosure for local control of 3ph/1ph air conditioners. a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. September 15 Supply and installation of DOL starter for PUMP motor with September 15 Supply and installation of DOL starter for PUMP motor with September 16 Supply and installation of DOL starter for PUMP motor with September 17 Supply and installation of DOL starter for PUMP motor with September 18 Supply and installation of DOL starter for PUMP motor with September 19 Supply and installation of DOL starter for PUMP motor with September 19 Supply and installation of DOL starter for PUMP motor with September 19 Supply and installation of DOL starter for PUMP motor with September 19 Supply and installation of DOL starter for PUMP motor with September 19 Supply and installation of DOL starter for PUMP motor with September 19 Supply and installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supply and Installation of DOL starter for PUMP motor with September 19 Supp	Set 0	
local control of 3ph/1ph air conditioners. a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 15 Supply and installation of DOL starter for PUMP motor with Septimber 16 Supply and installation of DOL starter for PUMP motor with Septimber 17 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18 Supply and Installation of DOL starter for PUMP motor with Septimber 18	Set 0	
 a. Supply and installation of 64A FP MCB (D-series) in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Supply and installation of DOL starter for PUMP motor with See 	Set 0	
weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. September 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners.	Set 0	
conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. See Supply and installation of DOL starter for PUMP motor with See See Supply and installation of DOL starter for PUMP motor with	Set 0	
conditioners. b. Supply and installation of 20/32A DP MCB in suitable weather proof enclosure(IP65) for local control of 3ph/1ph air conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. See Supply and installation of DOL starter for PUMP motor with See	Set 0	
proof enclosure(IP65) for local control of 3ph/1ph air Seconditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Seconditioners. Seconditioners.	Set 0	
proof enclosure(IP65) for local control of 3ph/1ph air Seconditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. Seconditioners. Seconditioners.	Set 0	
conditioners. c. Supply and installation of 20/32A TP MCB in suitable weather proof enclosure(IP65) for local control of 3ph air conditioners. See 15 Supply and installation of DOL starter for PUMP motor with See	Set 0	
proof enclosure(IP65) for local control of 3ph air conditioners. See proof enclosure(IP65) for local control of 3ph air conditioners. 15 Supply and installation of DOL starter for PUMP motor with See		
proof enclosure(IP65) for local control of 3ph air conditioners. See proof enclosure(IP65) for local control of 3ph air conditioners. 15 Supply and installation of DOL starter for PUMP motor with		
15 Supply and installation of DOL starter for PUMP motor with Se	Set 0	
l l''''	Set 0	
thermal overload protection, for 2kW motor	per U	1
		1
16 CABLE LAYING AND TERMINATIONS: Supply, laying and dressing		
of the following size of 1.1 KV grade XLPE insulated armoured		
cable with aluminium conductor concealed or clamped on wall /		
ceiling / trench / cable tray if necessary.		
i) 4x240 Sq.mm AYFY m	m 0	
ii) 4x95 Sq.mm AYFY m	m 0	
iii) 4x70 Sq.mm AYFY m	m 0	
iv) 4x50 Sq.mm AYFY	m 0	
v) 4x35 Sq.mm AYFY m	m 0	
v) 4x25 Sq.mm AYFY m	m 30	
vi) 4x16 Sq.mm AYFY m	m 10	
	m 0	
viii) 3x6 Sq.mm AYFY	m 0	
		1
17 End termination of the following size of cables using flange type		
cable glands and heavy duty tinned aluminium crimping type		
cable sockets including gland earthing.		
i) 4x240 Sq.mm AYFY se	set 0	
ii) 4x95 Sq.mm AYFY se	set 0	
iii) 4x70 Sq.mm AYFY se	set 0	
iv) 4x50 Sq.mm AYFY se	set 0	
v) 4x35 Sq.mm AYFY se	set 0	
vi) 4x25 Sq.mm AYFY se	set 6	
	set 4	
	set 0	
]

18 GI - CABLE TRAY : Suppy and installation of medium duty G Ladder type cable tray of following size. (Rate shall be inclusive o all bends supports,etc. And supports to be not more than				
	f	1		
all bends supports,etc. And supports to be not more than		I		
	n			
1000mm apart)				
i) 500mmx50mm(WxH)	m	0		
ii) 650mmx50mm(WxH)	m	0		
iii)300mmx50mm(WxH)	m	0		
				1
19 EARTHING AND LIGHTING PROTECTION				
a. Supply and providing ISI pipe earthing as per IS 3043 with 2.5m	n			
long 40mm dia B class G.I. pipe providing GI clamp at the top o				
the GI pipe test joint, filling around the GI pipe at the radius o				
15cm with homogeneous mixture of charcoal, common salt and	<u> </u>			
river sand up to height of 2.5m from the bottom and the rest o	I Set	2		
the portion with excavated soil, providing brick work masonries				
plastering, fixing cast iron cover of 30x30cm size etc. complete.				
p				
b. Making of Copper plate(600mmx600mmx3mm) Earth-pit as per IS	5			
3043 complete with charcoal, funnel set etc., including making o				
450 x 450mm brick masonary chamber with CI / stone / fabricated	ıl			
/ RCC cover with lifting handles stone / fabricated / RCC cove	I Set	2		
with ligting handles etc., complete as required.				
The state of the s				
c. EARTH CONDUCTORS Supply and laying of the following size o	f			
bare copper conductor along with above cables, fo				
interconnections between panels, DBs, change over switches		30		
etc.and also for interconnections between earth pits. i) No.10				
SWG				
d. Supply and laying of 2 X No. 10 SWG copper conductor through	,			
20mm PVC conduit for UPS earthing.	m	30		
e. Supply and laying of 25x3mm GI strip/tape supported or	n			
porcelain insulator on every 1m distance for lighting arreste				
system – the strip shall be insulated from having any direct		Ιo		
contact from the building -shall use UPVC conduits while crossing				
the wall etc.	Ί			
f. Supply and installation of - Copper Lightning arrestor spike – o	f			
1m supported over proper insulator and connected to GL strip		lo		
using proper nut bolt system.				
g. Supply & installation of 4m length 40mm dia C-class GI pipe to be				
fixed over the terace of the building to erect Copper lightning	,			
arrester spike. The pole shall be mounted on insulators.	Set	0		
and a state of the				
h. Supply and providing tinned copper earth bench using 25 x 3 mm				
copper strip (25 Cm in length)	Set	3		
[+	+	 	1

20	WIRING FOR LIGHT, FAN, PLUG, SOCKETS ETC: Point Wiring: Supply and wiring for light /fan/exhaust fan/calling bell/mirror lamp/ bulkhead light/ wall fans etc. With 3plate ceiling rose and by using 3x1.5 sqmm. (1.5sqmm). PVC insulated copper conductor wire in 20mm dia 1.5mm thick rigid PVC conduit, controlled by 5A modular switches with provision for modular type Ceiling fan regulator on separately fabricated MS Box. The M.S box should be earthed properly. One way point.			
a	Single light point controlled by a 6 Amp switch.	Nos	25	
	each Secondary light point connected to the single light points			
	controlled by a switch.	Nos	20	
c.	2-WAY controlled lighting point for staircase, bed switch etc.	Nos	1	
d.	Wall fan / Exhaust fan point - 6A, 3 pin modular socket on suitable metal box for wall fan controlled by switch in common SB	Nos	7	
e.	Ceilingl fan point - controlled by 6A switch in common SB with modular stepped regulator.	Nos	4	
21	Supply and fixing of Modular type 5A 3pin plug points controlled by 5A modular switch mounted on suitable box (on common switch board) only in Strong room, Record/ Stationary rooms & Pantry	Nos	6	
22	Supply and fixing of Modular type 5A 3 pin plug points with 5A modular type switch in separate location.	Nos	3	
23	Raw Power Switch Box : Same as above but for 2 Nos . modular type 5 A 3 pin plug points with 2 nos . 5A modular type switch in separate location. (both sides of cash cabin desk, nodes etc)	Nos	3	
24	Supply and fixing of modular type 15A plug socket with 15A modular type switch mounted on suitable Box(for Mgr cabin, Cash Cabin, Pantry, Water cooler, etc.).	Nos	2	
25	Supply and installation of combined 5A modular plug socket with 5A modular switch & 15A combined modular plug socket with 15A modular switch in single box.(for EB supply at cashier counters / Manager cabin/UPS for ATM)	Nos	0	
26	Supply and providing 16A plug top and 1.5m long 3 core 2.5Sqmm flexible copper cable (FRLS Type) for taking incoming supply from 16A socket. (For UPS/EB supply to back office manager & EB supply to strong room, line printer and record/ stationary rooms)	Nos	2	
27	Supply and Installation of 25A Modular type 3 pin plug socket with suitable metallic box for air curtain/ air conditioners.	Nos	2	
28	Supply and Installation of 20A /32A Modular type DP switch having indicator with suitable metallic box for the local control of the air conditioners/air Curtain.	Nos	3	

29	UPS Power Stations ::: Supply install Test and commissioning of computer power stations with 3nos 5A modular type socketswith 1nos 15A modular type sockets controlled with(1nos. 15A modular type single pole switch with indicator mounted on M/S Box.) / controlled by master switch (item 39) The boxes should be Fixed on – wall/ partitions(wooden, concealed or open as required at site. Maximum 3 sets per Circuit.		4	
30	Same as above but for 2 Nos. modular type 15 A 3 pin plug points with 2 nos. 15A modular type switch in separate location.(for Data Kraft rack / I/O Rack/ Cash cabin)	Nos	2	
31	Same as above but for 2 Nos. modular type 6 A 3 pin plug points with 2 nos. 6A modular type switch with indicator in separate location.(for countrers, Head cashier, etc on wall panel/ partition Above the tabe and on wall for token machine, CCTV, TV etc)	Nos	2	
	Supply, install, test and commissioning of 16A modular type master switch with indicator with suitable PVC box for the main control of UPS stations in the counters. (common switch to control all UPS station in each counter)	Nos	4	
33	Supply & Installation of USB charger oulets controlled by 6A switch (in Privillage lounge/ Hall)	Nos	1	
34	CIRCUIT WIRING: Supply and wiring wall / floor etc. / recessed / surface as per colour code with 3 runs of 1.1KV grade 1.5 Sqmm PVC insulated flexible copper wire for phase neutral and earth conductor with standard colour coding, through ISI marked 20mm dia(medium) rigid PVC conduit with all accessories. The rate includes the cost of complete wiring from switch box to switch box. THE WIRING SHALL BE DONE CONSEALED.	m	0	
35	Same as above but with 3 x 2.5 Sq.mm PVC Insulated copper wire(FRLS Type).(for lighting main circuit, 15A plug points & UPS point wiring) (power circuit to VRF IDUs)	m	250	
36	Same as above but with 3 X 4sqmm. PVC insulated copper wire(FRLS Type). (for 1.5 / 2 T AC and UPS Out put COS to computer DB and for the Name Boards if there are multiple name boards or extra ordinary lengthy—Name Boards)	m	50	
37	Same as above but with 3 x 6 Sq.mm PVC Insulated copper wire through rigid conduit (32mm) on wall and flexible conduit on floor for UPS Input.(4m length x 2 UPS) , AC input 3Tr/ 4Tr inv AC	m	20	
38	Same as above but with 4 \times 2.5 Sq.mm with 2 \times 1.5 sq.mm (for3ph 3T inverter AC units) in 32mm dia conduit	m	0	
39	Same as above but with 4 x 4Sq.mm with 2 x 2.5 sq.mm (for3ph 4T inverter AC units)	m	0	
40	Same as above but with 4×6 Sq.mm with 1×4 sq.mm (for3ph UPS input)	m	30	

41	Same as above but with 4 x 10 Sq.mm + 1 x 6 sqmmPVC Insulated copper wire through rigid conduit on wall of 38mm dia	m	0	
42	PVC CONDUITS:Supply and Fixing of following sizes of FRLS PVC conduit along with the accessories in surface in ceilling/ recess in walls, flooring including cutting the wall / floor etc., and making good the same in case of recessed conduit as required.			
a.	32mm dia. Conduit (Medium)	m	20	
b.	25mm dia. Conduit (Medium)	m	20	
c.	20mm dia. Conduit (Medium)	m	20	
43	LIGHT FIXTURES & FANS			
	Supply and Installation of 36~40W 600mmx600mm Square recess mounting (gypsum board ceiling) LED type luminaire (including required fixing frame, chain for suspending fron RCC ceiling) - Wipro, HPL, Havells, Orcus, 595mmx595mm cut out	Nos	10	
b	Supply & installation of 20 $^{\sim}18$ Watts DLED type LED light fitting with lamps and white reflector on false ceiling (UPS Light points) - $^{\sim}205$ mm cut out		4	
С	Supply & installation of 9^10 Watts DLED type LED light fitting with lamps and white reflector on false ceiling - 135 mm cut out	Nos	20	
d	Supply and Installation of minimum 5m lenght flexible LED strip lights of 22~24 watts in false ceiling coves of Blue / warm White shades with necessary LED driver of same make	m	0	
е	Supply and fixing of $2^{\sim}3$ watts LED spot lamp / swivel downlight - warm light for photoframe / decor lighting	Nos	0	
	Supply and fixing of 1 X 20W LED Batten light set on wall /ceiling. Slim with metal body	Nos	9	
g	Supply and Installation of 20~40W 2'x2' suspended / (drop) ceiling hanging type Round luminaire decorative (including required fixing frame) -Wipro, HPL, Havells, Orcus, Philips		0	
h	Supply and Installation of 36~40W out door type street light fixture LED including required fixing frame/pipe,) -Wipro, HPL, Havells, Orcus	Nos	0	
i	Supply & installation of 60 Watts LED light down lighter and on false ceiling (for double height area) - Wipro, HPL, Havells, Orcus, CGL.	Nos	0	
i	Supply & installation of calling bell	Nos	1	
	Supply and installation of 9" size medium duty exhaust fan.			
	(Toilets/ dinning)	Nos	2	
l	Supply and installation of 12" size medium duty exhaust fan. (UPS Room)	Nos	2	
m	Supply and Installation of 400 mm sweep wall fan with metal body and blades	Nos	3	

	1			1	
n	Supply amd installation of 1200mm sweep ceiling fan. 5 star rated. (High Speed)	Nos	4		
0	Supply and providing fan rod with painting (upto 1m length) (other than that supplied with fan and if required)	Nos	4		
р	Supply and providing fan hook on ceiling.	Nos	4		
	Supply and installation of 9W LED bulb with suitable batten holder		4		
	(Toilets & UPS light points)	Nos	1		
r	Supply and Installation of step type modular electronic regulator,	Nos	4		
44	100W Electrical safety - RUBBER mats of 1.1kV grade 1.8mx.0.9m	Nos	1		
	Supply and fixing of : 1nos First aid kit, Safety chart, Danger				
	boards-2nos , No Admission boards-1nos	Set	1		
46	Marking of Panels, DBs, its switch and fuse ratings, cable size,				
	location etc (Neat identification from top to extreme load end of				
	both light and power distribution including EB / UPS plug sockets	L.S	1		
	and generator switch boards) using white / black paint and stencil.				
	(free hand writing not allowed). Good quality stickers may also be used.				
47	Charges for Preparation of SLD (Single Line Diagram) , Network				
	diagram of the whole electrical & LAN installations using	L.S	1		
	AutoCAD, Lamination and displaying it inside the UPS room. (Size	L.3	1		
	– A3 /A2/A1).				
48	Service charges for liaison work with EB authorities on behalf of				
	bank for getting sanction for additional load, getting order for				
	statutory payments, shifting/replacements of suitable. Energy meter meter if necessary, submission of completion report,	L.S	0		
	obtaining final load sanction from concerned EB and displaying it				
	in the UPS room after lamination. Etc.				
49	Arranging temporary wiring for counters and cabins during	L.S	_		
	renovation work		0		
50	Removing old and unwanted wirngs, panels, fixtures from the	L.S	0		
	premises, and disposing the same.				
	PART - A TOTAL AMOUNT IN FIGURES				
	FART - A TOTAL AMOUNT IN FIGURES				
PART-	B TELEPHONE WIRING				
1	Supply and wiring using 2 pair telephone cable (0.5mm2) in 20mm				
	PVC conduit from the KRONE Box to the individual points. One				
	separate cable for each point. Number of cables in one conduit				
	limited to 5.				
	2 pair telephone cabling	m	100		
b.	10 pair telephone cabling	m			
2	Cumply and fiving of PL 11 type modular telephone cocket on				
2	Supply and fixing of RJ 11 type modular telephone socket on suitable PVC / metal boxes.				
a.	Telephone socket - single (modular type)	Nos	1		
	Telephone socket - double (modular type)	Nos	5		
	, , , , , , , , , , , , , , , , , , , ,				'

3	Supply and installation of KRONE connector telephone junction				
	box of 40 pair (double door type).	Set	1		
4	Supply and installation of KRONE connector telephone junction				
	box of 20 pair.	Set	0		
	,				
	PART - B TOTAL AMOUNT IN FIGURES				
PART-	C: PA & MUSIC SYSTEM				
1	Supply and wiring as per colour code transparent speaker cable				
	1.50sqmm PVC insulated stranded copper wire 2 runs through ISI	m	0		
	grade 20mm conduit for speakers.				
2	Supply and providing 9W recessed type speakers on ceiling CS				
	663 T Ahuja make speaker.	Nos	0		
	PART - C TOTAL AMOUNT IN FIGURES				
PART-	D: DATA CABLING			•	
1	Supply and laying of CAT 6 UTP cable through 25mm dia rigid PVC				
	conduit with all accessories etc.(2 run for SBI Connect also)	m	250		
2	Supply and fixing of 2nos of CAT 6 Modular Information outlet				
	with SM box on wall / partitions etc.	Nos	Nos 2		
3	Supply and fixing of 1nos of CAT 6 Modular Information outlet				
	with SM box on wall / partitions etc.	Nos	2		
4	Supply and installation of 17U wall mounted type rack.				
	(HCL/Valrack make)	Nos	1		
5	Supply and Installation of CAT6 24 port patch panel in the				
	floor/wall mounted type rack. With cable manager	Nos	1		
6	Supply and installation of CAT6 26 port (1000Mbps) switch in the	Nos	0		
7	Supply and installation of 1 m long patch chord. (CAT 6)	Nos	3		
8	Supply and installation of 2 m long patch chord. (CAT 6)	Nos	6		
9	Supply and installation of 3 mlong patch chord. (CAT 6)	Nos	1		
10	Supply and installation of 5 mlong patch chord. (CAT 6)	Nos	1		
11	Testing of NODES with reports. (with PENTA scan reports)	Nos	6		
	PART - D TOTAL AMOUNT IN FIGURES				
	PART - A				
	PART - B				
	PART - C				
	PART - D				
	TOTAL				