

**PROPOSED INTERIORS FOR STATE BANK OF INDIA, UNIFORM LAYOUT FOR
BRANCHES. AMBERPET BRANCH.**

SCHEDULE OF QUANTITIES AND DETAILED SPECIFICATIONS.

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
I.	INTERIOR WORKS:				
1.0	FIXED FURNITURE:				
1.1	FULL HEIGHT PARTITIONS:	46		Sq.M.	
	Providing and fixing metal stud dry wall partition with following specifications:				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm HDF Board fixed on both sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Partition from floor level upto 2350mm level to have 100mm bottomline expression skirting (aqua blue color) at bottom + from 100mm to 300mm level to have 1mm High Gloss Laminate (aqua blue color) + from 300mm level to 950mm level to have 1mm High Gloss Laminate (white color) + from 950mm level to 1100mm level 1mm High Gloss Laminate (aqua blue color) + from 1100mm level to 2250mm level to have 1mm Textured High Gloss Laminate (white color) + from 2250mm level to 2350mm level 1mm High Gloss Laminate (aqua blue color) on both sides as shown in drawing.				
	(d) Partition to have 8mm clear float glass fixed with 85mm x 15mm alround jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete.				
	(e) Partition above 2350mm level to have NO VOC or LOW VOC plastic emulsion paint finish on both sides as shown in drawing.				
	(f) All beech wood members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				
	(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.2	HALF HEIGHT PARTITIONS:	34		Sq.M.	
	Same as item 1.1 above, but for height of 1100mm from finished floor level, to a neat finish as per drawings and directions etc., complete and the following:				
	(a) Beach wood capping of 20mm thk on top & both sides of the Partitions horizontally and vertically up to skirting as per drawing and directions. Etc				
	(b) Partition from floor level upto 1100mm level on both sides to have 100mm bottomline expression skirting (aqua blue color) at bottom + from 100mm to 300mm level to have 1mm High Gloss Laminate (aqua blue color) + from 300mm level to 950mm level to have 1mm High Gloss Laminate (white color) + from 950mm level to 1050mm level 1mm High Gloss Laminate (aqua blue color) + from 1050mm level to 1100mm level to have 1mm High gloss Laminate on both sides as shown in drawing.				
	(c) The cost to include all materials and hardware required etc., as per site conditions. The rate is for a finished item of work etc., complete as directed.				
	(d) All beech wood members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				
1.3	DOORS IN PARTITIONS:				
1.3.1	35MM DOORS IN PARTITIONS:	8		Sq.M.	
	Providing and fixing 35mm thick solid core flush shutter with 85mm x 15mm beech wood jamb around and 12mm x 12mm button beading fixed 1mm Laminate as specified on both sides and 8mm clear float glass with 3M privacy film fixed as per drawing with 50mm x 15mm beech wood jamb around the glass opening and 12mm x 12mm beech wood beading for fixing of glass on both sides.				
	The rate to include necessary hardware viz., door stopper, door buffer, pair of " H " type handles, Mortise Dead Lock and Euro Profile Cylinder - Key and Knob 70mm SS, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), door closer (all of approved make and quality), ZERO VOC or NO VOC duco paint finish for all beech wood members, etc., complete as directed.				
1.4	FIXED GLASS WORKS: (12MM TOUGHENED GLASS WORK WITH MAIN ENTRANCE DOOR AND GLASS	31		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass as fixed glass from Floor to available Ceiling level along with Main Entrance Door and for Partitions. The glass is to be fixed with patch fittings and all the edges of the glass have to be polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.5	12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:	11		Sq.M.	
	Providing, making and fixing in position Fixed 12mm / 10mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1800mm x 2250mm - 2400mm in two pieces, and Partition Doors of approximate size 900 - 1000mm x 2250mm - 2400mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(a) Entrance door - Providing, fixing in position glazed entrance Double door and Single door with patch fitting or approved make (Double Door approx. Size: 1800mm - 1500mm x 2400mm - 2250mm and Single Door approx. Size: 900mm - 12mm x 2400mm - 2250mm) using 12mm / 10mm toughened glass edge polished. The Door to consist of Heavy Duty Floor spring, Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing.				
	(b) The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions etc., complete.				
1.6	WALL PANELLING:				
1.6.1	WALL PANELLING IN BANKING HALL:	35		Sq.M.	
	Same as item 1.1 above, but for Wall Panelling. The basic frame work to comprise all cladding specified only from one side to a neat job as per drawings and directions etc., complete.				
	(a) Providing 15mm thick jamb for door and window openings of suitable depth as per site conditions.				
	(b) All beech wood members to have NO VOC or LOW VOC duco paint finish.				
1.6.2	WALL PANELLING WITH SPECIAL HIGH GLOSS LAMINATE FOR E-LOBBY:	22		Sq.M.	
	Same as item 1.4 above to be cladded with 1mm Laminate (Laminate Base Rate Rs - 600/- Sq.M.) from one side to a neat finish as per drawings and directions etc., complete.				
1.6.3	WALL PANELLING (BEHIND SWO COUNTERS)	28		Sq.M.	
	Providing and Fixing of Wall Panelling with following specifications				
	Providing & fixing of Paneling on walls, made of 12 mm thick MDF Board.(Interior Grade) Paneling shall be finished with blue and white shade high gloss PU coat. All inside frame shall be made of aluminum member's size of 25 mm x 50 mm x 1.2 mm thick section at maximum 600 c/c. including all necessary hardware fittings. All other finishes shall be done as per detail drawings and as per directions.				
	Anti termite solution to be sprayed before using the MDF Board in the work and making complete as per the design and drawing.The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.7	COLUMN PANELLING:	60		Sq.M.	
	Providing and fixing metal stud column panelling with following specifications:				
	(a) Supporting system comprising of 51mm / 50mm x 35mm / 34mm x 0.5mm metal studs at 600mm c/c and 51mm / 50mm x 32mm x 0.5mm metal tracks at floor, middle, door and ceiling level with joints staggered to avoid through joints. The vertical members should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should also include necessary strengthening with studs / tracks or channels at doors and other openings.				
	(b) 12mm HDF Board fixed on all four sides with 25mm dry wall screws for the entire height of the partition.				
	(c) Column Panelling from floor level upto 2350mm level to have 100mm bottomline expression skirting (aqua blue color) at bottom + from 100mm to 2350mm level to have 1mm High Gloss Laminate on two longer sides of the column as shown in drawing.				
	(d) Column Panelling to have 6mm toughened lacquered glass in aqua blue color fixed with 12mm x 12mm button beading on two shorter sides of the column, to a neat finish as per drawings and directions etc., complete.				
	(e) Column Panelling above 2350mm level to have NO VOC or LOW VOC plastic emulsion paint finish on all four sides as shown in drawing.				
	(f) All beech wood members to have minimum two coats of LOW VOC or NO VOC duco paint finish.				
	(g) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.				
1.8	WALL PAPER	15		Sq.M.	
	Providing & applying of wall paper on the finished surfaces. The surfaces shall be thoroughly cleaned, line and level on all sides, dried and made free of all loose dirt, chalk, grease, fungus and algae, wax or flanking paint. Unwanted elements, hardware, clamps etc. shall be removed to make surface clean. The item also includes doing necessary touching work wherever required, by pop/putty for application. To shape actual areas on site will be considered for the measurement purpose. Wall paper of selected design of Basic rate of Rs. 1500 per sq.mtr.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.9	LACQUERED GLASS WORK FOR E-LOBBY:	14		Sq.M.	
	Providing and fixing in position 8mm toughened lacquered glass (colour - Black or blue) for glass partition. The work to include making necessary template for all the glasses and then cutting the glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required viz., single corner patch, bracket etc., The approximate size of each glass will be 1950mm x 450mm to 1200mm as per site conditions. The rate is for a finished item of work etc., complete as directed.				
1.10	DIGITAL WALL BEHIND GRAHAKMITRA (GREETING AREA)	9		Sq.M.	
	Providing and fixing display boards (behind Help desk & counters) using twin perplex sheets of highly transparent clear acrylic sheets of 5mm thick sandwiched with display sheet (placed in between) with required information display sheets made with 3M thickers material as per banks approved design and write up of Uniform layout policy of SBI and fixed to walls with suitable SS studs. The information or display material to be printed should be strictly as per banks approved patterns and contractor must arrange designer for making sample approval of the image. A Caption "THE BANKER FOR EVERY INDIAN" to be printed on the flex in bold and standard specified color as above caption. The subject to be displayed for the DIGITAL wall has to be designed by the vendor as directed by the Engineer.				
	The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item.				
1.11	ROLLING SHUTTER BOX	14		Sq.M.	
	Supplying and fixing 50mmx50mm TW frame and closing with 18mm thk MDF Board (Interior Grade) on all sides as per the design and finished on all internals and exposed areas of bank with 3 mm thk ACP with natural silica as per the design and directions of the architects.The rolling shutter box shall be provided with trap door in 18mm thk MDF board (Interior Grade) with necessary locks ,handles as directed .				
	Anti termite solution to be sprayed before using the MDF Board in the work and making complete as per the design and drawing.The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.12	FALSE CEILING:				
	Providing, making and fixing in position the following types of different false ceilings with different materials as specified below for a finished item of work as per drawings and directions etc., complete.				
1.12.1	GRID FALSE CEILING:	195		Sq.M.	
	<p>Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance $\geq 87\%$, Thermal Conductivity $k = 0.052 - 0.057 \text{ w/m K}$, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%.</p> <p>The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M² & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M² and need to be installed with Suspension system as per manufacturers details.</p> <p>The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p> <p>Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.12.2	PLAIN FALSE CEILING:	132		Sq.M.	
	<p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p> <p>(a) 27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.</p> <p>(b) All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from <u>the manufacturer on usage of their specified sections.</u></p> <p>(c) Further the rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.</p>				
1.12.3	VERTICAL FACES IN FALSE CEILING:	20		Sq.M.	
	Same as item 1.9.2 above but for vertical faces in false ceiling as per drawing including cut outs for AC grilles etc., complete as directed.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
1.13	STORAGE UNITS:	15		Sq.M.	
	Providing, making and placing in position Storage Units with horizontal partitions of 1200mm high abutting wall and 750mm high as back credenza or abutting partition made in 18mm HDF Board to all members except table top and 25mm block board for table top. All The exposed faces of the unit to have 1mm High Gloss Laminate as specified and NO VOC or LOW VOC enamel painting with putty finish on all unexposed faces including NO VOC or NO VOC duco paint finish for all wooden members and all necessary hardware viz., 'W' or wing hinges, locks, handles, tower bolts etc., and beech wood beading 40mm x 40mm at top and beech wood edge lipping 20mm x 6mm etc., as per drawings and directions etc., complete.				
2.0	LOOSE FURNITURE:				
2.1	BRANCH HEAD TABLE:	1		Each.	
	Providing, making and placing in position Executive Table and Side Table of approximate size 2100mm x 900mm x 750mm + 1050mm x 450mm x 750mm with following specifications.				
	(a) Main Table and side Table top and to be made in 25mm block board with 6mm thick acrylic solid surface. The front side of the table to have a inverted " C " made with 2 x 18mm thick HDF Board cladded with 6mm acrylic solid surface on the front and the verticals towards the modesty panel. The modesty panel to have 19mm HDF Board cladded with 1mm Laminate as specified.				
	(b) The " L " shaped table top on the back side to have 50mm edge alround and to be cladded with 6mm acrylic solid surface.				
	(c) All other members to be with 18mm HDF Board and all exposed faces of the table to have 6mm acrylic solid surface OR 1mm HD Gloss Laminate as specified above to be used.				
	(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	<p>(h) One Side Table with shutter unit of 400mm made with 18mm HDF Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p> <p>(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
2.2	OTHER OFFICER'S EXECUTIVE TABLES:				
2.2.1	OFFICER'S AND SIDE EXECUTIVE TABLES:	3		Each.	
	<p>Providing, making and placing in position Executive Table and Side Table of approximate size 1650mm - 1550mm x 750mm x 750mm + 1050mm x 450mm x 750mm with following specifications.</p> <p>(a) Main Table and side Table top and to be made in 25mm block board with 1mm High gloss Laminate. The front side of the table to have a inverted " U " made with 2 x 18mm thick HDF Board cladded with 1mm High gloss Laminate on the front and the verticals towards the modesty panel. The modesty panel to have 19mm HDF Board cladded with 1mm HD Gloss and 1mm Laminate as specified.</p> <p>(b) The " L " shaped table top on the back side along with side tabe to have 49mm edge around, which is to be achieved by adding a 75mm piece of 18mm HDF Board to the table topl from bottom and this vertical edge is to be cladded with 1mm High gloss Laminate.</p> <p>(c) All other members to be with 18mm HDF Board and all exposed faces of the table to have 1mm HD Gloss Laminate as specified above to be used.</p> <p>(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.</p> <p>(e) One readymade CPU mobile pedestal.</p> <p>(f) One Molded Key Board Tray with channels etc.,</p> <p>(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(h) One Side Table with shutter unit of 400mm made with 18mm HDF Board and 19mm plywood with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				
2.3	GRAHAK MITRA/ TECH MITRA TABLE:				
2.3.1	GRAHAK MITRA TABLE:	1		Each.	
	<p>Providing, making and placing in position Grahak Mitra Table of approximate size 1500mm x 800mm - 900mm x 750mm with following specifications.</p> <p>(a) Main Table Top to have 25mm block board with 6mm thick acrylic solid surface. The vertical supports of the table is to be made with two side boxing of 75mm x 800mm x 750mm made with 18mm HDF Board and the front side boxing to 200mm x 450mm x 750mm on either sides and central boxing of 250mm x 600mm x 750mm, all made with 18mm HDF Board clad with 6mm acrylic solid surface on all the exposed sides and top.</p> <p>(b) The front of the table to have a 600mm x 1050mm proud portion with provision for cove lighting at bottom and this central portion to be clad with 6mm thick aqua blue colored lacqued glass.</p> <p>(c) All other members to be with 18mm HDF Board and all exposed faces of the table to have 6mm acrylic solid surface and the drawer unit to have 1mm High Gloss Laminate as specified to be used.</p> <p>(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.</p> <p>(e) One readymade CPU mobile pedestal.</p> <p>(f) One Molded Key Board Tray with channels etc.,</p> <p>(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,</p> <p>(i) All the unexposed faces to have minimum two coats of <u>NO VOC or LOW VOC enamel paint with putty finish.</u></p> <p>(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>				
2.4	SINGLE WINDOW COUNTERS:	7		Each.	
	<p>Providing, making and placing in position Single Window Counters along with necessary partitions as per item 1.2 above (The partitlions will be measured and paid as per item 1.2 i.e., Half Height Partitions) with following specifications and per dimensions specified.</p> <p>(a) The overall size of each Single Window Counter to be 1650mm - 1500mm x 900mm - 975mm x 750mm + 1050mm x 450mm x 750mm.</p>				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	(b) Tabletop of main table and side table to be made in 25mm block board with 6mm thick acrylic solid surface and double thickness at edges around. The acrylic solid surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.				
	(c) All other members to be with 18mm HDF Board / 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 6mm thick acrylic solid surface OR 1mm High Gloss Laminate as specified in the drawing to be used.				
	(d) All the edges of 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.				
	(e) One readymade CPU mobile pedestal.				
	(f) One Molded Key Board Tray with channels etc.,				
	(g) One Three Drawer Unit made with 18mm HDF Board and 12mm HDF Board. The unit to have one vertical filing drawer at bottom and two equal drawers on top. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and 20mm x 6mm beech wood edge lipping etc.,				
	(h) One Side Table with shutters made with 25mm block board top and 18mm HDF Board for all other members				
	(i) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	(j) Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.				
	(k) All wooden members to have minimum two coats of NO VOC or LOW VOC duco paint finish.				
	(l) Each Single Window Counter to have half height partitions on either sides as per item 1.1.2 above.				
	(m) Each Single Window Counter to have 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets.				
	The cost to include the " L " shaped Single Window Counter, two Side Partitions and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.5	SBI LIFE,GENERAL & CASH COUNTING TABLES	6		RMT	
	Providing and Fixing Back office table of size 1500 mmx 600 mm x750mm with following specifications				
	The Table Top shall be made of 18 mm thk MDF Board (Interior Grade)with 1mm thk laminate on all the exposed surfaces, and 0.8 mm thk laminate on all internal surfaces as per the drawing.				
	The sides (Verticals) shall be made of 18 mm thk MDF Board (Interior Grade)with 1mm thk laminate on all the exposed surfaces, and 0.8 mm thk laminate on all internal surfaces as per the drawing.				
	The Table shall be provided with Drawer unit Comprising of 3 nos of sliding drawers with sleek Telescopic channels, Handles ,locks and Necessary Hardware,ss cabel manager, required as per the Drawing				
	The Table shall be provided with Moulded CPU Trolley with castors and Moulded Key board Tray with Telescopic Channels.				
	FOOT REST in CRCA sheet: Ergonomic Footrest Angle Adjustable Promotes Stress Free Posture Slip resistant surface Reduces pressure on the back of the thigh Platform Size : 445mm (W) x 295mm (D)				
	Anti termite solution to be sprayed before using the MDF Board in the work and making complete as per the design and drawing.The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item.				
2.6	12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS:	9		Each.	
	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1150mm x 400mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.				
2.7	12MM TOUGHENED GLASS ON TRANSACTION SIDE FOR SINGLE WINDOW COUNTERS:	7		Each.	
	Providing, making and fixing in position 12mm thick clear float glass in the front side of approximate size 1650mm x 450mm with a central cut out of 200mm x 175mm. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and diretions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
2.8	WRITING DESK:				
2.8.1	FLOOR MOUNTED WRITING DESK:	1		Each.	
	Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 750mm with following specifications.				
	(a) A Octogonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 12mm HDF Board cladded with 1mm High Gloss Laminate. A top to be provided at 900mm level from floor to be made with 25mm Block Board cladded with 1mm High Gloss Laminate which will have verticals made with 12mm HDF Board cladded with 1mm High Gloss Laminate upto the table top level of 1050mm from floor level.				
	(b) The Writing Desk Circular Top to have 12mm dia toughened clear float glass with 25mm champered bull nosing around.				
	(c) All members to be with 12mm / 18mm HDF Board and all exposed faces to have 1mm High Gloss Laminate as specified.				
	(d) All the edges of 12mm / 18mm HDF Board to have 20mm x 6mm beech wood edge lipping.				
	(e) All the unexposed faces to have minimum two coats of NO VOC or LOW VOC enamel paint with putty finish.				
	The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
3.0	OTHER WORKS:				
3.1	PLASTIC EMULSION PAINTING:	385		Sq.M.	
	Cleaning the surface of the wall & then applying one coat of altex putty followed by one coat of primer & then applying second coat of putty to give smooth finish exactly in line and level & then finally applying a minimum of two coats of NO VOC or LOW VOC Plastic Emulsion Paint of approved shade to give a neat finish including cost of all materials necessary scaffolding etc., complete for walls & ceiling.				
3.2	ROLLER BLINDS:	15		Sq.M.	
	Providing and fixing in position of Roller Blinds of approved Fabric (Fabric Cost - RS. 1,000/- per Meter) of Hunter Douglas / Mac / Vista make or approved equivalent of approved shade etc., as directed.				
3.3	DESIGNER FILM WORK:	25		Sq.M.	
	Providing and fixing in position Designer Film with elipse design on all glasses as per draswings and heights mentioned. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.				
3.4	SELF WATERING FLOWER POTS WITH NATURAL PLANTS:	10		Each.	
	Providing and placing in position PVC Flower Pot with self watering arrangement with water absorption granules and red earth etc., of base 300mm - 400mm and 600mm - 750mm tall with Indoor Plant viz., Lady Palm (Raphis Excelsa) / Peace Lily (Spathiphyllum Walllisii) / Spider Plant (Cholorophytum Comosum) / Gerbera Daisy (Ferbera Jamesonii) etc., complete as directed.				
3.5	ENTRANCE - VINYL SCRAPER MATTING:	2		Each.	
	Providng, fixing in position 3M™ Nomad™ Scraper Matting 7150, Gray / Red. Entrance coiled vinyl scraper matting designed for heavy traffic applications over the existing flooring to a neat finished job as per drawings and directions etc., complete.				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
3.6	ACP CLADDING:	36		Sq.M.	
	Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges etc., complete for finished item of work but excluding cost of structural steel fabrication, scaffolding charges, if any, ACP Cladding - 4 mm thick.				
3.7	ACRYLIC LOGO:	1		Each.	
	Providing SBI Logo 1500mm diameter made with 6mm Inky Blue color acrylic sheet with provision for back lighting as per drawings and directions etc., complete.				
3.8	Buy Back value of old & existing furniture , where it is and as it is basis (LS		LS	
	TOTAL FOR FURNISHING WORKS (A):				
CIVIL WORKS					
1.0	BRICK WORK				
1.1	Providing and constructing 230mm thick brick masonry in CM 1:6 using approved quality table moulded bricks of minimum 50kg / Sq.cm including raking, curing,scaffolding and staging, lead and lift, in all situations such as walls / pillasters / pillars / stub supports etc. complete as per drawing and as directed at all levels and heights				
	FOR E-LOBBY, SAFE ROOM,ENTRANCE STEPS, CLOSING WINDOWS AND OLD ENTRANCE	20		CU.M	
1.2	Providing and constructing 115mm thick Brick masonry in CM 1:4 straight or curved walls, piers and architectural features at all levels including a concrete band of 75mm thick with 3-nos of 8mm dia reinforcement rod at every 750mm ht with M20 grade concrete mix including shuttering, staging, scaffolding, centering, formwork, curing, etc., cement mortar of 1:4 including packing the residual space between masonry & other structural members like columns, beams, slabs etc., providing openings as directed and finishing neatly around the same, the cost of all materials including reinforcement steel, cost of labour, cost of equipment and machinery, work at all leads and lifts, loading and unloading, transportation, and all other incidental charges etc., complete. The work shall be carried out as per the directions of the Engineer in charge				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quantity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	FOR TOILETS	20		SQ.M	
2.0	FINISHING				
2.1	Plastering in 2 coats with 16mm thk 12mm thk in CM (1:6)prop and top coat 4mm thk in CM (1:4)prop for internal walls with dubara sponge finishing including cost and conveyance of all materials seignorage fee, all taxes, water to work site and all operational, incidental labour charges such as scaffolding, mixing, motor, lift charges, curing etc. complete for finished item of work as directed by the Engineer in charge/Architect				
	FOR INTERNAL WALLS	115		SQ.M	
2.2	Plastering in 2 coats with a base coat of 20mm thk 16mm thk in CM (1:6) and 4mm thk in CM (1:4) prop for extenal wall with dubara sponge finishing including cost and conveyance of all materials seignorage fee, all taxes, water to work site and all operational, incidental labour charges such as scaffolding, mixing, motor, lift charges, curing etc. complete for finished item of work as directed by the Engineer in charge/Architect				
	FOR EXTERNAL WALLS	30		SQ.M	
3.0	FLOORING				
3.1	Providing and laying vitrified floor tiles 600X600 mm (10/12 thickness to be specified by the manufacturer) Double Charged ,with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), or LATICRATE including Skirting if any required during laying,and grouting the joints with white cement and matching pigments etc., complete..				
	Including Dismantling and Removal of Existing Flooring and carting away to a distance of 5km to the nearest municipal dump yard. The rate shall be inclusive of all the,labour, transportation, material necessary required for the complete execution of the item. The Basic Rate of the Tile shall be RS 65-70 Excluding GST Note The Rate for the Skirting shall be Paid as per the Rate Quoted for the Flooring				
a	BRANCH	265		SQ.M	
b	E-LOBBY	22		SQ.M	
3.2	GRANITE FLOORING ON ENTRANCE STEPS	12		SQ.M	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
	Providing and fixing with polished granite slabs of 20mm thk.(ex showroom rate not less than rs 180/Sft) for flooring of size not less than 1800x1200mm as per design set over a base of CM(1:5) prop. Jointed neatly with cement putty to full depth mixed with matching colour pigment full and half rounding and polishing on edges and including cost and conveyance of all materials seignorage fee, all taxes, water to work site and all operational, incidental labour charges such as scaffolding, mixing, motor, lift charges, curing etc. complete for finished item of work as directed by the Engineer in charge/Architect				
3.3	Flooring with Rustic /Non skid tiles of 1st quality of KHAZARIA / JOHNSON / ASIAN make of 7.3 mm thick of approved colour not less than 300x600mm set over a base coat in C.M (1:6) , 12 mm thick including applying neat cement slurry honey like consistency spread at the rate of 3.30kg/Sqm and filling the joints with white cement mixed with pigments of matching shade laid over existing concrete bed/RCC slab including cost of base coat, cost and conveyance of all materials, excluding CC bed/RCC slab, labour charges for mixing cement mortar , laying of tiles to required slopes/levels, curing etc complete for finished item of work for all Floors in Toilets.BASIC COST OF THE TILES 85				
	FOR TOILETS	18		SQ.M	
4.0	DOORS				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
4.1	Providing and fixing frame made from 1.2 mm powder coated cold rolled steel profiles of overall section size of 60 mm x 45 mm with 21 mm rivet for shutter with necessary stiffeners hinges and screws. V- Board shutter with alround style "U" lipping of size 15 x 18 x 15 mm made from 0.8 mm thick CRCA powder coated steel profile with 16 mm thick V-board with necessary screws fixed at every 1'-0" interval 250 mm long aldrops 2 nos. M.S. nickel coated 250 mm long 1 no. M.S. Tower Bolts Including cost and conveyance. with 1.5mm thk laminate on either side as per approved colour, labour charges etc.,1 No. eye viewer and 1No. rubber bush including fixing the fixtures to door with required number of screws, bolt and nuts including all labour charges for making and fixing the frame in position as directed by the Engineer in charge, fixing the shutter duly fixing required fixtures to the frame etc., complete for finished item of work (The vertical frame of door shall be embedded in flooring for a depth of not less than 10 mm)				
	FOR TOILETS 750 mm X 2100mm 7 NO.S	12		SQ.M	
5.0	ALUMINIUM WINDOWS				
5.1	Supplying fabricating and fixing of aluminium glazed sliding windows 2 track with aluminium of 63.5x38.1x1.5 mm of box section and shutter section of 40mmx18mmx2mm thk of jindal make or equivalent and panel filling with 5mm thick saint gobain plain glass including rubber beeding, standard accessories like rollers, handles etc., powder coated to required colour for sliding windows including cost of supply and fixing of aluminium grill with F channel fixing to window frame etc., complete and as directed by Engineer-in-charge/ Architect.				
	1200mm x1200mm 5 NO.S	8		SQ.M	
6.0	ALUMINIUM VENTILATORS				

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
6.1	Supplying fabricating and fixing of aluminium ventilators with outer Z section 46mmx44mm x2mm thickness and shutter with z - section 46mmx44mmx2mm thick of all jindal make or approved equivalent and with and panel filling with 5mm thick saint gobain plain glass including rubber beeding, standard accessories like rollers, handles etc., powder coated to required colour for sliding windows including cost of supply and fixing of aluminium grill with F channel fixing to window frame etc., complete and as directed by Engineer-in-charge/ Architect.				
	600mm x600mm 5 NO.S	2		SQ.M	
7.0	Dismantling Work				
7.1	Dismantling and Removal of Brick works,RCC Chajja's RCC Lintal's And Existing Flooring and carting away as directed covering the entire work area of dismantling with green mesh to avoid fall of debris as per the directions of the Engg of the Bank. The rate shall be inclusive of all the,labour, transportation necessary required for the complete execution of the item.	16.75		CU.M	
8.0	SANITARY AND WATER SUPPLY				
8.1	Dadoing in toilets with Rustic tiles 300x600 MM , 1st quality) over a base coat of 12 mm thick in CM (1:5) prop includng applying neat cement slurry honey like consistency spread at the rate of 3.30kg/Sqm and jointed with white cement mixed with pigment of matching shade including cost and conveynce of all materials and labour charges etc. complete for finished item of work to walls in toilets as directed by the Department. BASIC COST OF THE TILE IS RS 85	68		SQ.M	
8.2	Supplying and fixing of 150mm x 100mm SWG gully traps of ISI make confirming to ISI 651 & 4127 with C.I grating & constructing brick masonry in CM (1:6) prop. intermediate chamber and fitted with 304.8 mm X 288.6 mm (12"x9") C.I Frame with hinged cover of standard make as approved including cost and conveyance of all materials to site, labour charges., etc complete for finished item of work.	4		NOS	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
8.3	Supplying and fixing 100 mm dia inlet - 75 mm (3") outlet CI floor traps 1st quality ISI marked conforming to IS 1729-1979 with C.P grating fixing with white cement as per the site requirements with standard practice including CP cockroach trap with grating, black painted for all floors including cost and conveyance of all materials to site, labour charges etc, complete for finished item of work.	8		NO.S	
8.4	Providing & Fixing star white colour vitreous china wall mounted wc with heavy duty soft close seat cover & concealed dual tank. Complete with all accessories including cutting & making good wall & floor wherever required. Model - CROMA - 2085, 550X367X355mm, 2385 seat cover	4		NO.S	
8.5	Providing and fixing Jaquar make white vitreous china battery based infrared sensor operated urinal of approx. size 610 x 390 x 370 mm having pre & post flushing with water (250 ml & 500 ml consumption), having water inlet from back side, including fixing to wall with suitable brackets .	3		NO.S	
8.6	Providing & fixing 12 mm thick toughened frosted glass partition Between the Urinals of ht 900 mm up to 5' ht & fixed to wall.Special patch fittings at directed locations.Patch fittings having side patch with EPC lock. The rate shall be inclusive of all the hardware necessary for the complete execution of the item as per the design.	1		SQ.M	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
8.7	Counter Wash Basin Fixing ¾" thk machine cut, machine polished, first quality selected granite counter top with 1:2 cement and mortar base in shape and size as shown in the drawing. 1 1/4th " Kadappa base to be provided below finished granite slab for necessary support. Fixing a wash basin KOHLER -make with all necessary fittings.Model-(K-14715IN-1 Parliament Vessels.lavatory in white available only with single-hole drilling) complete with necessary support and filling up joints with white cement with relevant matching colour, including curing, rubbing, polishing, manual rubbing wherever required on the granite counter & cutting hole for wash basin. 3" band in granite to be provided on the front edge of the counter as per detail drawing and / or as directed. SELECTED GRANITE: BELGIUM BLUE STONE KALINGA to be used as countertop. KOHLER - make single lever basin mixer to be fixed inside wash basin.Model (K-18057IN-ND Touchless cold only lavatory faucet without drain in Polished Chrome Rate to be without wash basin and wash basin mixer & other	2		NO.S	
8.8	Supplying and Fixing of Towel ring Jaquar make continental , Chrome plated with 7 years warranty with necessary screws etc., complete including cost and conveyance of all materials, labour charges for finished item of work in all floors.	2		NO.S	
9.0	WATER SUPPLY WORKS				
9.1	Providing and fixing chlorinated poly vinyl chloride(CPVC) pipes having thermal stability for hot and cold water supply, including all CPVC plain and brass threaded fitting, including fixing the pipe with clampsat 1m spacing. This includes jointing of pipes and fitting with one step CPVC solvent cement and cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 20 mm OD pipe	10		RMT	
9.2	Supply and fixing of Health Faucet of the closet mounting type with hose connected Two Way Bib Cock with flow restrictors/ aerators with complete fittings. (All fittings of approved make) Fittings of PARRYWARE MAKE, MODEL Nos. T9941A1, T9915A1, G3434A1) (Flow rate - 1.3 LPM@ 58 PSI)	4		NO.S	

<u>S.No.</u>	<u>Item. / Particulars.</u>	<u>Quan- tity.</u>	<u>Rate.</u>	<u>Unit.</u>	<u>Amount.</u>
9.3	Supplying and Fixing of Short Body Bib Cock of ISI make , Chrome finish with 3 years warranty with necessary fittings etc., complete including cost and conveyance of all materials, labour charges for finished item of work in all floors.	2		NOS	
	TOTAL FOR CIVIL WORKS (B):				
	TOTAL RUPEES (A+B)				
	DISCOUNT IF ANY				
	GRAND TOTAL				