

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00PM ON 26.10.2018

BOQ FOR INTERIOR WORKS					
HR SECTION, ZONAL OFFICE-1					
Item No.	Description	Qty.	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Doors in partitions: The door frame made of approved quality Beach/Safeli wood. The Shutter to be 35mm thk BWR Block Board with both side finished with 1mm thk laminate with necessary inlays and grooves as per drawing. The door inlet with 8mm thk glass ith etching design as directed. The edges of the door and four side of the glass shall be fixed with beading. The door to be provided with handles, locks of Doorset, door closers and stoppers etc. and other necessary hardware. All beading surface to be finished with melamine polish as instructed by Bank's Engineer/architects, all complete as per drawings. All materials to be approved by Bank's Engineer/architects.	2	Sq.M		
2	Making of Partition using existing old partitions materials: Removing and fixing of old partition materials as per the direction of Engineer-in Charge at site with all required materials to making it good and complete. Supporting system comprising of best locally available make 51 X 35 mm GI metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. 9mm plywood with 1mm laminate (dark for bands and light for body) on both sides .85 X 15mm beech wood capping on top and sides of openings. The beech wood members to have melamine polish finish. d) 8 mm glasses with edges polished and with etching design above 3'-0" height at specified areas as directed.	64	Sq.M		
3	Low Height Partition: Providing and fixing GI metal stud low height partitions with the following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm GI metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 9mm plywood with 1mm laminate (dark for bands and light for body) on both sides c) 85 X 15mm beech wood capping on top and sides of openings. The beech wood members to have melamine polish finish. d) 8 mm glasses with edges polished and with etching design above 3'-0" height at specified areas as directed.	12	Sq.M		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00PM ON 26.10.2018

BOQ FOR INTERIOR WORKS					
HR SECTION, ZONAL OFFICE-1					
4	<p>Wall Panelling: Providing & fixing GI metal stud wall panelling with the following specification:</p> <p>a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick GI metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom.</p> <p>b) 9 mm BWR plywood fixed on one side with 25 mm dry wall screws for the entire height of panelling.</p> <p>c) 1 mm laminate (dark for bands, light for body) upto false ceiling level. e) All beech wood members to have melamine polish finish. length X height up to false ceiling will be measured for payment.</p>	22	Sq.M		
5	<p>Storage Units: Providing/making and placing in position low height storage units upto 0.762m (2'-6") height or height as directed and 0.457m (1'-6") deep made with 18/19 mm BWR plywood front sides and middle shelf and back side with 6 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete.</p>	7	Sq.M		
6	<p>Storage Units: Providing/making and placing in position low height storage units using existing old storage units as per the direction of Engineer-in Charge at site with all required materials to making it good and complete. The storage unit should be upto 0.762m (2'-6") height or height as directed and 0.457m (1'-6") deep made with 18/19 mm BWR plywood front sides and middle shelf and back side with 6 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete.</p>	7	Sq.M		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00PM ON 26.10.2018

BOQ FOR INTERIOR WORKS					
HR SECTION, ZONAL OFFICE-1					
7	<p>Plain Gypsum False Ceiling:- Providing and fixing Concealed Grid suspended ceiling system of 12.5mm India Gypsum Plaster Boards fixed to Frame Work of the company, Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape, two coats of emulsion paint over a coat of primer etc., complete as directed.</p>	34	Sq.M		
8	<p>0.609mX0.609m (2'-0"X2'-0") Silhouette Grid False Ceiling:- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries/Insula/Daikin etc.. The suspension system shall be 2'-0"X2'-0" plain grid system with 15mm wide flanges main runners and cross tees to have mitred ends with "birds mouth " notches to provide mitred cruciform junctions. Main runners to be spaced at 4'-0" fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 4'-0" c/c maximum and 4'-0" cross tee of size 15mm x 44mm x 1200mm at every 2'-0" c/c maximum and 2'-0" cross tee of size 15mm x 44mm x 600mm at every 4'-0" c/c maximum and 19mm x 19mm x 3000mm wall angle around the wall to form grid size of 2'-0" x 2'-0" and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 4'-0" intervals at the main tee and laying of 15 mm thick mineral fiber tiles manufactured by Armstrong/Insula/Daikin etc. of size 2'-0"X 2'-0" 15mm over the formed grid etc., complete as directed.</p>	47	Sq.M		

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00PM ON 26.10.2018

BOQ FOR INTERIOR WORKS					
HR SECTION, ZONAL OFFICE-1					
9	<p>Tables for CM of 1.52mX0.76mX0.76m with side table of 1.06mX0.41mX0.76m (Size 5'-0"X2'-6"X2'-6", Side table 3'-6"X1'-4"X2'-6"): Providing, making & placing in position executive table and side table ('L' Shaped) using of existing old table with the following specifications:</p> <p>a) Table top made in 25 mm block board/BWR ply & all other members with 18/19 mm BWR plywood with 1 mm laminate, except on top (which has to have Corian Top as per item no.18 and will be paid separately) all edges to have 20 X 6 mm beech wood lipping.</p> <p>b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc.</p> <p>c) One CPU pedestal.</p> <p>d) One plywood key board tray with channels to be provided</p> <p>e) One foot rest</p> <p>f) Side table with shutters to be made with 25 mm block board/BWR ply with 1mm laminate or top and other members with 18/19 mm BWR plywood & 1 mm laminate with necessary hardware viz: cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech wood beading and 20 X 6 mm beech wood lipping etc.</p> <p>g) All the exposed surfaces to have 1 mm laminate of approved shade and brand. All unexposed surfaces to have two coats of enamel paint with putty. All wooden members to have melamine polish.</p>	1	Nos.		
10	<p>Table for Officers of 1.37mX0.76mX0.76m with side table of 1.06mX0.41mX0.76m (Size 4'-6"X2'-6"X2'-6", Side table 3'-6"X1'-4"X2'-6"): Specifications are same as item no. 9 but for new table and for the change in size.</p>	9	Nos.		
11	<p>12 mm glass on table top:- Providing & placing in position 12 mm glass on top of BM's table, side table, corners grounded properly, making hole for wire manager etc. complete.</p>	2	Sq.M		
12	<p>Soft board of size 1500X1200 as directed.</p>	1	Each		
13	<p>Vertical Blinds:- Supplying & fixing in position of vertical Blinds of "Vista" or "Touch".</p>	14	Sq.M		
14	<p>PVC flooring:Supplying and fixing in position Premium quality PVC flooring of 1 mm thickness as per design in line without gaps, leveled with chemical (Laticrete) over existing flooring complete as per manufacturers specification.</p>	65	Sq.M		
15	<p>Aluminium Sliding Windows:Supplying and fixing of powder coated sliding aluminium framed with glass shutter including star locking arrangement at windows,if required.</p>	3	Sq.M		
Sub Total					
16	<p>Buy Back of old counters, partitions, wooden table etc.: Minimum amount coated should be of Rs 10,000.00.If any vendor coat less than the amount mentioned above,the coated amount will be considered as Rs 10,000.00 or whichever is higher.</p>	LS		LS	
GrossTotal					

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00PM ON 26.10.2018

BOQ FOR INTERIOR WORKS

HR SECTION, ZONAL OFFICE-1

Signature of the Contractor

Tenders are to be submitted on the printed forms issued by us. The Contractor should quote the rates in figures as well as in words. Special care should be taken to write the rates in figures only in such a way that interpolation is not possible. The total amount should be written both in figures and in words. In case of figures, the words "Rs." should be written before the figure of rupees and words "P" after the decimal figures e.g. Rs. 2.15P and in case of words the word "Rupees" should precede and the word Paisa should be written at the end, unless the rate is in whole rupees and followed by the words only, it should invariably be up to two decimal places. While quoting the rate in schedule of quantities, the words "only" should be written closely following the amount and it should not be written in the next line. The amount of each item shall be worked out and the requisite total shall be given. All corrections shall be attested by the initials of the Tenderers.

GST WILL BE PAID EXTRA AS PER THE ACTUAL

NOTE:

- 1) The quantities put to tender are tentative only. Payment would be made on the basis of the actual quantity executed after completion of the work.
- 2) Materials specification to be strictly as per items and approved materials only. A copy of approved materials to be obtained by the contractor from the Engineer-in-Charge before commencement of the work.
- 3) Prior to starting of work contractor to discuss with the Engineer-in-Charge and sample materials are to be approved before start of the work at site.
- 4) The colour scheme has been finalized and the Contractor to collect the same from the Engineer-in-Charge before procurement of the materials from the market.
- 5) The successful Contractor should be responsible to make the area/duct/walls water tight without any extra charges.

Signature of the Contractor