

BOQ OF INTERIOR & FURNISHING WORKS BRANCH AND ATM AT RK ASHRAM MARG METRO STATION, NEW DELHI					
S.No.	Particulars	Unit	Qty	Rates (Rs.)	Amount (Rs.)
<b>1.0</b>	<b>PARTITIONS &amp; DOORS</b>				
	Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall be considered. The rate to include provision of extra frame work as necessary for skirting and making openings for glazing & door etc.,cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions.				
<b>a</b>	Providing & fixing <b>Solid Full Height Partition</b> with 50/45x50/45 mm GI sections of India Gypsum @ 600 mm c/c in both directions, (vertical member to be in one piece) and horizontal direction fixed to floor & ceiling by means of <b>raw</b> plugs/dash fastners on both ways, 8 mm thk. commercial ply to be fixed on both sides till roof height.including provision of grooves as per instructions.Partition to have 100 mm high metallic decorative texture laminate band at skirting on both sides of partition, Item includes melamine polish on the wood surfaces and finishing of grooves with polish etc. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect / Bank's Engineer.				
<b>i)</b>	One side gypsum & one side laminate over 8mm th.comm. Ply.(in <b>UPS &amp; Server</b> )	Sq.Mt.	23		
<b>ii)</b>	Both side gypsum (in <b>Record Room</b> )	Sq.Mt.	11		
<b>b</b>	Providing & fixing <b>Partly Glazed Full Height Partition</b> with 50/45x50/45 mm GI sections (1 mm thk.) of India Gypsum @ 600 mm c/c in both directions, (vertical member to be in one piece) and horizontal direction fixed to floor & ceiling by means of <b>rawl</b> plugs/dash fastners on both ways, 8mm thk. commercial ply to be fixed on both sides till roof height.including provision of grooves as per instructions and 1.0mm thick decorative texture laminate fixed on both sides till false ceiling. Partition to have 100 mm high metallic decorative texture laminate band at skirting on both sides of partition, Item includes melamine polish on the wood surfaces and finishing of grooves with polish etc. 8mm thk. toughened glass to be fix with wooden moulding as per design. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect / Bank's Engineer. (in <b>Br.Mgr. &amp; Server</b> )	Sqmt.	15		
<b>c</b>	Providing & fixing 12mm toughend <b>Fixed Glass Partition</b> fixed with S.S. clamps on sides and top & S.S. 'U'-channel in the ground as per detail drgs. and complete to the satisfaction of Architect/ Bank's Engineer. (in <b>Main Ent. &amp; ATM</b> )	Sq.Mt.	9		
<b>d</b>	Providing and fixing front <b>Frameless Patch Fitting Door</b> with 12mm thick toughened glass with frame less glass fittings joining 2 glass & double action floor springs (Hettich/Dorma/Godrej) as per design. The item includes providing and fixing S.S. handle not less than 600mm long on both side of glass, locks and fittings (Haffle/ Hettich/ Ozone) as per the manufacturer's specifications etc. complete to the satisfaction of Architect/ Bank's Engineer.(in <b>BM+Main Ent.+ATM &amp; entry to strong room</b> )	Sq.Mt.	10		
<b>e</b>	Providing & fixing <b>Low Height Partition</b> with same specifications as item no. 1(a) above but with 12mm toughened glass above 3' 0" fixed as per design/details, height of partition to be 1350mm, item is with 38x95mm teak wood moulding on top and side edges of partition complete with DUCO paint/melamine polish including proper base etc. complete to the satisfaction of the Architect / Bank's Engineer.	Sq.Mt.	15		

S.No.	Particulars	Unit	Qty	Rates (Rs.)	Amount (Rs.)
f	Providing & fixing <b>Glazed Door</b> with 75x50 mm teak wood frame (chaukhat). The door shutter to be made from 125x40mm teak wood side & top members along with 200x40mm teak wood bottom member. Item includes fixing 12mm glass fixed with teak wood beading 14x12mm. The door is to be complete with mortice door lock & SS handle , S.S stopper, 4 No.s 125mm S.S. hinges (Hettich/ Dorma/ Ozone) etc. All wood surfaces to be malamine polished complete to the satisfaction of Architect / Bank's Engineer. in <b>(System room/Pantry/Corridor area)</b>	Sq.Mt.	6		
g	Providing & fixing 35mm <b>Water Proof Flush Doors</b> with 1.0mm thk. decorative texture laminate on both sides as per design. The item includes providing and fixing chaukhat made from 100mmx50mm teak wood members. The Doors to have all hardware fittings such as 4 No.s 125mm SS hinges, SS handles, 150mm SS tower bolts,7 lever mortice locks with SS handles (Dorma/ Hettich/ Godrej ) etc. complete to the satisfaction of Architects/ Bank's Engineer. <b>(Safe/Record room)</b>	Sq.Mt.	4		
h	Providing & fixing <b>Door Closers</b> (Hettich/ Haffe/ Dorma/ Godrej) including cutting and fixing, covering plate and all associated hardware etc. complete to the satisfaction of Architect/Bank's Engineer.in <b>(System room/Record/Safe rrom/Pantry/Corridor area)</b>	Nos.	5		
<b>SUB TOTAL : I : PARTITIONS AND DOORS</b>					
<b>2.0 PANELLING</b>					
<b>Measurement of height to be taken from finished floor level to level of false ceiling</b>					
a	Providing & fixing <b>Panelling (Laminate)</b> with frame work with 45 x 25 mm GI sections (India Gypsum or equivalent) @ 600 mm c/c in both directions, finished with 8mm thk. commercial ply. The ply to be covered with 1.0mm thk. decorative texture laminate in two or more colour. Paneling to have 50x35mm teak wood moulding on edges. Panelling to have 100 mm high teak wood DUCO painted Blue/Teak/Metallic band at skirting including moulding and provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.	Sq.Mt.	55		
b	P/f of 12mm thk lacquered glass fixing on MDF with adhesive as per design & pattern approved by Architect / Bank's Engineer. <b>(Column in banking hall area )</b>	Sq.Mt.	7.5		
c	Providing and fixing 12mm thk. <b>Toughened Float Glass</b> in front portion of Cash Cabin with SS metal clamps including cutouts for passing currency and communication as per details. The edges of the glass to be polished etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	4		
<b>SUB TOTAL : II : PANELLING</b>					
<b>3.0 FALSE CEILING</b>					
	Item includes providing False Ceiling in plane, curve shape and design . Suspending system and frame work shall match layout of A.C. ducts / grills, electrical / fire protection wiring / fixtures, return air grills etc. Rate to include provision of extra frame work, necessary scaffolding needed due to layout of other utilities refered above and fixtures etc.(Measurement shall be taken of the horizontal base area only nothing extra for cove design and verticle sections)				

S.No.	Particulars	Unit	Qty	Rates (Rs.)	Amount (Rs.)
a	Providing and fixing <b>Gypsum Board False Ceiling</b> with INDIA GYPSUM ULTRA gypsoc main ceiling sections at 1200 c/c and cross members at 450 c/c of INDIAN GYPSUM. The grid work to be suspended from ceiling with hangers at every 1200 c/c in both directions. The Frame work to be as per manufacturer's specifications. 12.5 mm thk. GYPBOARD to be screwd to the frame. The board to be finished with filling the tapered edges of the board with jointing compound and finishing with paper tape of INDIA GYPSUM. The ceiling to be finished with a top coat of two or more coats of acrylic emulsion paint as per manufacturer's specification along with provision of all necessary cut outs for electrical / air conditioning grills and necessary frame work including cove and curve designs etc. complete to the satisfaction of Architect/ Bank's Engineer.	Sq.Mt.	136		
b	Providing and fixing False Ceiling with <b>Mineral Fibre Acoustic Ceiling</b> tiles of Armstrong/ USG/ Boral or equivalent with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 15mm wide <b>Silhouette</b> type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Ceiling tiles of <b>Dune Premier</b> of size 600 x 600 x 15 mm (thk.) to be placed in the grid. Rate to include making necessary cut-outs or openings for light fixtures, air conditioners and other utilities etc. complete to the satisfaction of Architect/ Bank's	Sq.Mt.	32		
<b>SUB TOTAL : III : FALSE CEILING</b>					
<b>4.0 COUNTER/ TABLES/ WORKSTATIONS</b>					
	All Tables/ Counters/Work Stations/Running Counter to have 19mm thk. BWR ply top front, rear and sides and 1.0 mm thk. laminate (Decorative/Texture/Metallic) finish on all exposed surfaces along with 0.8 mm thk. white laminate on inside surface of shelves & shutters & rear drawer units to be made from 12 mm thk. BWR ply with 19mm thk. BWR ply FASCIA with 1.0 mm thk. decorative texture laminate finish (as per individual item).The drawers to run on telescopic drawer channels of Hettich make. Drawer units shall have two smaller and one bigger drawer and auto locking arrangement (Godrej). Footrest 75x50mm made of 2nd class teakwood member to be fixed in each table. The rate shall include providing all hardware such as drawer channels, S.S. handles, cable manager (Hettich/ Dorma/Haffele) etc. complete. The item also includes a tray for keyboard fabricated out of 12mm BWR ply finished with 1.0mm th.laminate runing on telescopic channel of Hettich, finshed with decorative texture laminate on top and rounded front of size 560x450mm, readymade CPU trolley with castors etc. complete to the satisfaction of Architect/ Bank's Engineer.				
a	Providing and placing <b>Table</b> made of 12mm thk. BWR ply finished with approved 12mm thk. corian solid acrylic surface on table and sides made with 19mm thk. commercial ply finished with 1.0mm thk. high gloss decorative laminate. Modesty panel to be made of 12mm thk. frosted toughened glass. Table top edges to be approx. 25mm thk. with corian finish as per design & details. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above etc. complete as per design/ drawing. The table size shall be 1980x838x750(H)mm.				
i	<b>Size (6'-6"x2'-9"x2'-6") FOR BM TABLE</b>	Nos.	1		
ii	<b>Size (5'-6"x2'-9"x2'-6") FOR OFF. TABLE</b>	Nos.	2		
iii	<b>Size (4'-0"x2'-0"x2'-6") FOR GRAHAK MITRA TABLE</b>	Nos.	1		

S.No.	Particulars	Unit	Qty	Rates (Rs.)	Amount (Rs.)
d	Providing and fixing <b>Side Storage Tables</b> made of 18 mm thk. exterior grade MDF board having 450mm wide top provided with 12 mm thk. high density acrylic (Corian/ LG/ Marino) and sides finished with 1mm thk. decorative laminate. The side table to have 2 drawers on top with shuttered storage below. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto hinges, S.S. handles (Hettich/ Dorma/Hafele) and locks (Godrej) etc. complete as per design/drawing to the entire satisfaction of Architect/Bank's Engineer.				
i	Size (3'-6"X1'-4"X2'-6") FOR BM CABIN	Nos.	1		
ii	Size (3'-6"X1'-4"X2'-6") FOR COUNTER and OFFICER	Nos.	6		
e	Providing & fixing <b>Running Counter/ Table</b> for fabricated with 19 mm thk. BWR ply top with 1.0mm thk. decorative texture laminate finish. Table supported on drawer unit and other side with gable end finished with laminate from outside and 0.8mm thk. white laminate from inside. Counter to have one drawer unit per occupant (approx. 1200mm running length per occupant) with specifications for drawer units etc. as per main specifications mentioned above etc. complete as per design/drawing to the entire satisfaction of Architect/Bank's Engineer. The width of running counter/ table to be 600 mm.( in server room)	R.Mt.	1.5		
f	Providing and placing in position <b>Banking Counters</b> in straight/curved shapes 750 mm high made of 18 mm thk. exterior grade MDF board duly rounded with 6mm thk. flexi ply covering in 750mm wide working top, finished with 12 mm thk. high density acrylic (Corian/ LG/ Marino) in curved shape and rest of the structure made from 19mm thk. BWR ply finished with 1.0 mm thk. decorative textured high gloss laminate in shade as per SBI standards. Rest of the specifications for drawer units etc. shall be as per main specifications mentioned above but with divisions for currency as per Bank's instructions. The drawer units shall be provided with autolocking system (Godrej) for drawers etc. complete as per design/ drawing. Item also includes providing & fixing 380mm deep <b>transaction counter in counter</b> fabricated out of 19 thk. BWR ply finished with 1.0mm thick decorative textured laminate upto 1167 mm height as per arch. drawing. The rate shall include cutting, making view panel opening (1'-0" x 8"), making good the surface & edge polish and providing 12mm thick toughened glass in the opening (view panel) of size 1'-0" x 8"with sillicon adhesive etc. complete to the entire satisfaction of Architect/Bank's Engineer.	R.Mt.	6		
g	<b>WRITING COUNTER</b>				
	Providing and fixing 450mm wide Writing Counter fabricated out of one numbers,12mm thick toughened etched plate glass with bevelled edge over 19mm Italian Composite Marble of rate not less then 250/ sqft. fixed over 19mm thk.Comm. board both 150mm a part,fixed with Stainless Steel studs over 19mm thk. Granite Stone in semi circular shape both horizontally as per architectural drawing fixed with SS Pipe Section, 304 grade 16/18 gangs as per Arch. Drg. & with SS Brackets of required size with col. & Boxing complete as per Arch. Dwg. complete to the satisfaction of Architect / Bank's Engineer.	Rmt.	1.5		
<b>SUB TOTAL : IV : COUNTER/TABLES/WORKSTATIONS</b>					

S.No.	Particulars	Unit	Qty	Rates (Rs.)	Amount (Rs.)
<b>5.0</b>	<b>STORAGE CUPBOARDS</b>				
<b>a</b>	Providing & fixing <b>Full/Low Height Storage</b> Cupboard 450mm deep & Ht. 750 - 900mm with frame, all sides, shelves to be made with 19 mm thk. BWR ply and 6mm thk. BWR ply fixed at the back. The shutters to be made with 19mm thk. BWR ply. Shutters, top and sides all exposed surface to be finished with 1.0 mm thk. decorative texture laminate on all exposed surfaces. All edges to have 19mm thk. T.W. edging as per details, all shutters to to be made overlapping the frame and edges of shutters to have 19mm thk. T.W. edging as per details including S.S. 6" long handles, magnetic catchers, self closing hinges, locks (Godrej/ Hettich/Haffele) etc. The item includes polishing the wood surfaces & grooves with melamine polish and all inside surfaces to have 0.8 mm thk white laminate finish etc. complete to the satisfaction of Architect / Bank's Engineer. Only front elevation will be considered for area calculation.	Sq.Mt.	14		
<b>b</b>	Providing and fixing <b>Over Head Storage</b> made of FIRESAFE IS: 5509 plywood sheet inside laminate finish with required 19mm thick aluminium profile shutters with back painted glass, required soft closing hinges (Hettich/ Haffle/ Dorma) & glass shelves. Item to be inclusive of all accessories, storage shelves, lift up sutters, design grooves, moulded edges, aluminum profile, soft close hinges etc. complete. Inner side of the storage to have 1mm thick laminate finish etc. complete to the satisfaction of Architect/ Bank's Engineer. <b>(in pantry)</b>	Sq.Mt.	1.5		
<b>c</b>	Providing and fixing <b>Storage under Platform</b> made of 18mm thk. FIRESAFE IS: 5509 plywood sheet finish with 1mm thick high glossed laminate sheet on outer face and 1mm thick white laminate sheets on inner face of the shutter; edge to be covered with aluminum profile section as per selection, shutters to have soft close hinges (Hettich/ Dorma/Haffele) with teak wood frame below platform. Item to be inclusive of 19mm thick interal horizontal laminated shelves, joining cleats, accessories, ss hardware, soft close drawer with ss basket, aluminum profile handles etc. complete. In side of storage to be finished with 1mm thick laminate etc. complete to the satisfaction of Architect/Bank's Engineer.(Measurement will be counted from front shutter's height & width, no extra measurement and payment will be given for ss basket & shelves). <b>(in pantry)</b>	Sq.Mt.	1.5		
<b>d</b>	Providing and fixing <b>Louvered Shutter Cabinet</b> for main electrical panel board, fabricated out of 19mm thick commercial board finished with 1mm thick Laminate of approved make shade and texture, louvers fabricated out of teak wood duly polished with melamine spray and all other specifications as per item no. 5 etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	6		
<b>SUB TOTAL : V : STORAGE CUPBOARDS</b>					
<b>6.0</b>	<b>MISCELLANEOUS</b>				
<b>a</b>	Providing and fixing <b>Box Notice Board</b> with 19mm thk. BWR ply with frame & sides finished with 1.0 mm thk. decorative texture laminate. Box to have 75x35mm teak wood shutters with 6mm thk. clear float glass. The back to have 6mm thk. BWR ply and 12mm thk. soft ply covered with cloth of approved shade and fabric. The item includes polishing the wood surfaces with melamine polish etc. complete to the satisfaction of Architect/Bank's Engineer. Size :- of the Box Notice Board shall be 1200x600x150(D)mm.	Nos.	1		

S.No.	Particulars	Unit	Qty	Rates (Rs.)	Amount (Rs.)
b	Providing and fixing <b>Pin-up Board</b> with 12mm thk.MDF board with cloth of approved shade and fabric on top. MDF board to be fixed with teak wood moulding of 19x25mm size with melamine polish etc.complete to the satisfaction of Architect/Bank's Engineers.	Sq.Mt.	2		
c	Providing and fixing <b>Bank Logo</b> with acrylic sheet and S.S.304 grade 16 gauge base.Logo to be provided with LED lights(Phillips/Havells/Wipro)as per Bank's instructions.The logo to be fixed on wall/panelling /partition as per details and instructions etc.complete to the satisfaction of Architects/Bank's Engineers. Size of Bank Logo shall be 600x600mm	Nos.	1		
d	Providing and fixing <b>Digital Glass Film Birla (3M)</b> for etching as per design in all shapes including curve shapes etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	11		
e	Providing and fixing <b>Roller Blinds</b> (Vista Levelor/ MAC/ DACK) of approved shade, texture and fabric including all associated accessories etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	1.2		
f	Providing & applying the walls, ceiling and elsewhere with <b>Plastic Emulsion Paint</b> (roller finish) after preparing the base by removing existing paint/ finish and applying 2-3 coats of birla white putty for making the surface plane & smooth and then applying 2 or more coats of plastic emulsion paint with final coat done with rollers as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.	Sq.Mt.	110		
g	P/F Wall Paper of basic rate Rs.80/- per sqft.with adhesive over P/A 6mm thick POP base.	Sq.Mt.	25		
h	Providing and fixing in position <b>Aluminium Composite Paneling (ACP)</b> for Cladding with framing of aluminium tube section of min. 50mmx25mm and 20 gauge at a spacing of 600mm center to center both ways. ACP to be of approved shade in 600mm wide panels or distributed equally. ACP sheets to be fixed to the frame with 3M make adhesive along with mirror screws. Joints to be finished with silicon based sealant. ACP sheets (Alubond/ Eurobond/ Fujibond/ Alcobond) to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the highest position etc. complete as per instructions of Architect/Bank's Engineer. Item includes scaffolding as may be required etc. complete as per site conditions.				
i)	Inside ATM	Sq.Mt.	27		
ii)	Outside Area	Sq.Mt.	35		
I	P/F Box 6" deep fabricated out of 19mm th. Comm. Board finished with 1mm th.laminate on all exposed surfaces inclusive of P/F 100mm decorative metallic Laminate.skirting as per arch. Drg.				
	In Curve/ Straight	Sq.Mt.	5		
<b>SUB TOTAL : VI : MISCELLANEOUS</b>					
<b>Total</b>					

**Note: The rates quoted includes all other taxes , duties , loading , unloading , transportation, other expenses etc to site only GST will be paid Extra**