NAME OF WORK : INTERIOR WORKS OF SBI BRANCH AT KUTCHERY DEHRADUN

S. NO.	BRIEF DESCRIPTION OF ITEM	QTY.	UNIT	RATE in figure & words (Rs.)	AMOUNT (Rs.)
1	**PARTITIONS/PANELLING:** Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall be considered. The rate to include provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings etc, making provision for laying conduit. All wood to be applied with 2 coats of fire retardant paint of VIPER make and 1 coat of wood preservative with anti-termite properties.				
a) i)	Providing & fixing **Wall Paneling** over GI framework of member/ sections size 50mmx35mm placed at the spacing of 600 mm centre to centre both ways fixed on wall and covered with 6.00 mm commercial ply **with 1 mm thick lamination** of approved make, shade, texture including 2-3 bends and skirting with different shades of 1.00 mm thick metallic laminate duly fixed with adhesive & horizontal grooves in desired pattern, finishing of grooves with polish in desired shade, polishing of exposed wood, etc. complete. The rate should be inclusive of necessary cut out/panel for electrical/fire/telephone wiring etc. as required. Top of paneling and exposed edges of wood etc. to be provided with 2nd class teak wood and beadings of size 40 mm X 12mm in desired pattern etc. complete with spirit polishing in desired shade etc. complete.	210	Sq.Mt.		

b-i	Providing & fixing **Full Height Partition** work consisting of 1st class kail wood frame work of wood size 50 mm x 50 mm placed at 600 center to center both ways with 6 mm thick commercial ply finished with 1 mm thick laminate of approved make, shade and texture fitted to wooden frames on both sides including 2-3 bends and skirting with different shades of 1.00 mm thick metallic laminate & horizontal grooves in desired pattern. Skirting to have an additional member of kailwood of size 50 mm X 50 mm. Partitions from 900 mm to 2100 mm height shall be glazed with 6.00 mm thick etched glass fitted with 2nd class C.P. teak wood beadings of size 75 X 12 mm in desired pattern, polishing with spirit polish at required places. Item includes provision of 4 mm grooving in desired pattern, finishing of grooves with polishing in desired shade with TW scantling etc. complete including necessary melamine polish in approved shade. Rates to include for providing and fixing of 35 mm thick flush doors covered with 1.00 mm thick laminate on both sides, 4 nos. brass butt hinges (heavy) on each door, all brass hardware, 6 levers Godrej make mortise lock with decorative handles, door stoppers, 5 mm. thick etched glass (for door) in 2nd class teak wood frame work (chaukhat) of size 75 X 40 mm etc. complete along with melamine polish in desired shade including providing and applying fire retardant VIPER paint over wooden frame work etc. complete. **Note:** The cost of doors with necessary hardware locks etc. complete to be included in rates of this item.	60	Sq.Mt.		
b-ii	Providing and fixing **Low Height Partition** (up to 1500 mm) consisting of first class kailwood frame work of wood size 50 mm X 50 mm, except in skirting member which shall have 2 nos. 50 mm X 50 mm members at required spacing but not exceeding 600 mm center to center in either direction, 6 mm commercial ply finished with 1 mm thick laminate of approved make, shade and texture on both sides complete with 4.00 mm wide grooves vertically & horizontally in desired pattern/ curve inclusive of providing and fixing 10 mm thick etched glass as per approved design having curved top shape in low height partitions as per requirement, 2nd class C.P. teak wood moulding (65 X31 mm) on free end/ top of low height partition, 2nd class teak wood beading(12 X 12mm). Rate to include providing 2-3 bends and skirting with different shades of 1.00 mm thick metallic laminate including providing and applying fire retardant VIPER paint and wood preservative with anti-termite properties over wooden frame work/surfaces and polishing wherever required etc. complete. **Note:** Measurement for one face of partition will be made for the purpose of payment.	50	Sq.Mt.		
2	**<u>FALSE CEILING</u>:** Suspending system and frame work shall match layout of A.C. ducts/grills, electrical/fire protection wiring/fixtures,		.		

	return air grills etc. Rate to include provision of extra frame work needed due to layout and fixtures etc referred above. Rates to include necessary scaffolding item includes design work cutting and bending in curved shapes as per requirements for providing false ceiling.				
	Providing & fixing **ARMSTRONG False Ceiling** with 600 mm X 600 mm tiles as per manufacturer's specifications duly fixed with screws & GI framework suspended from RCC roof/ ceiling (at height of less than 3.60 M) in combination with gypsum board false ceiling in required design & pattern and at different levels. Item includes providing extra support for fixing light fixture.	280	SqMt.		
3	**<u>COUNTERS WITH CORIAN TOP:</u>** Providing and fixing 750 mm deep **Customer Counters** fabricated out of 19 mm thick commercial board finished with 1.0 mm thick laminate of approved make, shade and texture on all exposed surfaces including front of drawers, sides etc. and with all exposed internal surfaces, leg space, CPU space & key board drawer area to be finished with 1.0 mm thick laminate except top and front fascia (part) of the counter which shall be finished with corian of approved make, shade and texture ***(cost of corian only shall be paid extra under respective item)***. On top of the counter 12 mm thick toughened & etched glass (acid wash & sand blasted) of 21" vertical and 15" horizontal fixed with teak wood beading duly polished.**(*cost of glass only shall be paid extra under the respective item*)** with provision for placing/fixing Godrej D-Tel Security & temper proof drawers and CPU trolly (to be paid separately) & finishing of **all internal surfaces (vertical & horizontal) with 0.8 mm thick laminate as per approved sample**, steem beech wood beeding (12 X 12mm), 100 mm wide skirting with 2 nos. 19 X 19 mm steem beech wood moulding, necessary hardware, Hettich make telescopic sliding channel, including providing and fixing 150 mm wide decorative ornamental column with grooves, beading, polishing of wood surface in melamine spray finish complete with making good all the surfaces, proving and fixing stainless steel cable manager in corian inclusive of cost of cutting hole in corian etc. complete.	6	R.Mt.		

3-a	**Supplying & placing in position Drawer Unit to be "Security & temper proof drawers (Name : D-TEL, DEPOSITORY SAFE SECURING YOUR DAILY EARNINGS), Godrej make, with following specifications:- Anti-fishing mechanism, snap shut mechanism, multi-purpose application, re-inforced security and heigh precision locks external dimension 691H X 460W X 460D mm and internal 345HX455Wx395D mm, weight approx. 33 kg."** The net cost will be exclusive of conventional wooden drawer units being used as of now. Each drawer unit shall be install at every 1.5 M length of the SW Counters.	4	Each		

3-b	Supplying and placing in position readymade MS CPU stand (Godrej make)	4	Each		
3c)	**SIDE CABINETS FOR COUNTERS:** Providing & placing in position **Side Cabinets** having side partition, top, drawers, shelves & shutter fabricated out of 19mm thick commercial board with 6mm thick commercial ply wood backing, all exposed surfaces, sides & front finished with 1mm thick laminate of approved make, shade and texture with shelves, drawers, shutter, 100mm wide decorative metallic skirting (as per approved sample) including providing and fixing necessary hardware, hinges, locking arrangement with Hettich make locks, Hettich make telescopic steel channel runners, Hettich make handles as per approved sample, **finishing of all internal surfaces vertical & horizontal with 0.8 mm thick laminate as per approved sample** & providing polish on exposed wood surface with spirit polish etc. complete . 750x450x750mm (2'6"x1'6"x2'6").	4	Each		
4	**TABLES:** Providing and fixing in position **Tables** fabricated out of 19mm thick commercial board with all exposed surfaces inclusive of leg space area & CPU area finished with				

	1mm thick laminate of approved make, shade and texture & table top finished with 1.0mm thick laminate of approved make, shade and texture with 31x31mm steem beech wood moulding complete inclusive of providing and fixing with drawers, shelves, shutter & 100mm wide skirting of metallic decorative laminate metallic in modesty panel as per approved sample 12x12mm steem beech beading including necessary hardware, Hettich make locks, locking arrangement, Hettich make telescopic steel channel runner for drawers, providing and fixing key board drawer, Hettich make handles (as approved sample) & polishing the exposed steem beech wood surface with melamine spray finish etc. complete along with **finishing of all internal surfaces (vertical & horizontal) with 0.8 mm thick laminate as per approved sample.** Rate to also include for providing and fixing SS cable manager, cutting & making hole and making good the surface etc. complete.				
	i)Table size 6'-0"x3'-0"x2' -6" for BM.	1	Each		
	ii)Table size 5'-0"x2'-6"x2' -6" for other Officers.	4	Each		
	iii) Asstt. Tables 4' x 2' x 2'-6"	3	Each		
4a)	**<u>SIDE CABINET FOR TABLES:</u>** Providing & placing in position **Side Cabinets** having side partition drawers, shelves & shutter fabricated out of 19mm thick commercial board with 6mm thick commercial ply wood backing, all exposed surfaces, sides & front finished with 1mm thick laminate of approved make, shade and texture complete with shelves, drawers, shutter, 100mm wide decorative metallic skirting (as per approved sample) including providing and fixing necessary hardware, hinges, locking arrangement with Hettich make locks, Hettich make telescopic steel channel runners, Hettich make handles as per approved sample, **finishing of all internal surfaces vertical & horizontal with 0.8 mm thick laminate as per approved sample** & providing polish on exposed wood surface with melamine spray etc. complete .				
	I)1050x450x750mm (3'6"x1'6"x2'6") for BM.	1	Each		
	II)900x450x750mm (3'0"x1'6"x2'6") for other Officers.	4	Each		
5	Providing and fixing 12mm thick clear **Toughened Glass** in front of public counters, cash counters & elsewhere held together with SS clamps & SS studs as per approved sample including providing and fixing steam beach beadings (18x18mm), steam beach moulding (62x31mm) along with polish & melamine spray finish etc. complete.	8	Sq. Mt.		

6	**STORAGE CUPBOARDS:** Providing and fixing in position wooden built-in **Storage Cabinets** (continuous divided vertically @ 3'0" (900 mm) center to center distance or as per site condition having sides, partitions, shelves & shutters fabricated out of 19 mm thick commercial board & 6.00 mm thick commercial ply on back, finished with 1.00 mm thick laminate of approved make, shade and texture on all exposed surfaces, top, skirting (in different shade), 6 X 19 mm thick CP teak wood beading on exposed edges of 19 mm thick board, complete with shelves, shutters including necessary hardware, self closing hinges, SS handles, magnetic catches, locking arrangement with Hettich make locks, 75 mm brass tower bolts, **finishing of all internal surfaces (vertical & horizontal) with 0.8 mm thick laminate as per approved sample,** melamine polish on wooden surfaces. **Note:** Only front elevation will be considered for area/ quantity calculation. I)Low Height (up to 1500 mm) Storage 450 mm deep. II)Overhead storage 450 mm deep	 20 4	 Sq.Mt. Sq. Mt.		
7	Providing and fixing ISI marked **Hydraulic Door Closers** of ISI mark along with all associated accessories etc. complete.	2	Each		
8	Providing and fixing **Voucher Tray** 1200x450x230 mm made out of 19 mm thick commercial board finished with 1 mm thick laminate of approved make, shade and texture on external exposed surface and 0.8 mm on internal surfaces both horizontal and vertical with writing top and racks for keeping vouchers as per Bank's design and duly fixed to wall/pillars or elsewhere as per the instructions of the Branch etc. complete.	1	No.		
9	Providing and fixing **Louvered Shutter Cabinet** for main panel fabricated out of 19 mm thick commercial board and finished with 1 mm thick laminate of approved make, shade and texture, louvers fabricated out of steam beech wood duly polished with melamine spray and all other specifications as per item no. 6 etc. complete.	3	Sq. Mt.		
10	Providing and fixing in position 600 mm deep Work Station / **Running Counter** in system room fabricated out of 19 mm thick commercial board finished with 1.00 mm thick laminate of approved make, shade and texture on all exposed surfaces including top, front of drawers, sides including providing sliding key board and drawers. The rate shall include providing and fixing 0.8 mm thick laminate on all internal surfaces of drawers and inner side of back ply, providing the sides and both sides of vertical, horizontal members with teal wood moulding, necessary hardware such as Hettich make	1.5	R.Mt.		

	locks, Hettich make telescopic sliding channels, Hettich make handles etc as per approved sample, SS cable manager etc. complete.				
11	Providing and fixing 12 mm thick **Toughened Glass Glazing** of approved make with all fittings including floor spring (in door), 2'-6" long SS handles (in door) along with all associated patch fittings of approved make including etching film (garware) along with blasted etching "State Bank of India" (in door/ elsewhere) etc. complete. i)Fixed Glass Glazing ii)Openable Glass Door	 8 4	 Sq. Mt. Sq. Mt.		
12	Providing and fixing in position **Flap Door** fabricated out of 19 mm thick commercial board, finished with 1.00 mm thick laminate of approved make, shade and texture on all exposed surfaces, top, skirting (in different shade), melamine polish on wooden surface on the backside of the door, provided with Godrej make heavy duty tower bolt from inside, hinges and all other necessary hardware etc. complete.	2	Sq. Mt.		
13	Providing & fixing on wall notice board of size 3' X 2' with side, top & bottom 3" X 3/4" teak wood, back celotex board with green / blue cloth. Top shutter with plain 4 mm thick glass, handle lock hinges, etc. complete duly polished.	1	Each		
14	Providing and fixing in position 12mm thick **Corian** of approved make, shade and texture duly fixed with adhesive wherever required in desired pattern and shape/ moulding etc. complete.	12	Sq.Mt.		
15	Providing and laying digital series and double charged glossy **Vitrified Floor Tiles** 600 mm X 600 mm (thickness as per manufacturer of approved make) of approved make, shade, finish (matching with existing flooring) with water absorption less than 0.08% and conforming to IS: 15622 laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigment etc. complete. For flooring and skirting (**Make:** Kajaria/ Johnson/ NITCO/ Somany).	280	Sq. Mt.		
16	Providing & fixing anti-skid ceramic coloured pavement tiles 300 X 300 X10 mm thick laid over 20 mm cement mortar 1: 4 (1 cement : 4 coarse sand) including dismantling of existing tile/floor of staircase and disposal of malba. Tile to be of Johnson/NITCO/Somany (sample to be got approved from the Bank) (actual size of risers, treads, landing, etc. of staircase shall be measured for payment purpose)	20	SqM		
17	Providing and fixing **Partition** for UPS/BATTERY/SERVOR made up of Aluminium Composite Panel (ACP) sheets with framing of aluminium tube sections of min. 2" x 1"	20	Sq. Mt.		

	and 20 gauge at a spacing of 2' center to center both ways. ACP to be in 2' width panels or distributed equally. ACP sheets to be fixed to both side of the frame with 3M make adhesive along with mirror screws. Joints to be finished with silicon based sealant. ACP sheets to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item also includes providing a door of size 3' x 7' for the system room, if required, with same specifications as specified above along with Godrej make heavy duty lock, 3 numbers 3" SS hinges, handles etc. complete. (**Make:** Alubond/ Eurobond/ Fujibond/ Alcobond).				
18	Supplying Dining table made of teak wood legs 75 mm X 75 mm and frame 100 mm x 25 mm . Top to be made of 25 mm thick commercial board with 1 mm thick laminate and teak wood beading Size of the top 1500 mm x 900 mm	1	Each		
19	Supplying cushioned Dining chairs made of teak wood legs and frame 50 mm thick high density cushions covered with tapestry costing Rs. 300/- per metre	6	Each		
20	Dismantling existing counters, partition, panelling, flooring,etc. as per the schedule of works. Disposal of malba away from Bank's premises and stacking of serviceable material at site.	1	Job		
21	Salvage value of old counters, partition, panelling, false ceiling, aluminium partition, tables, etc. (Minimum Rs. 30000.00)	1	Job		
	GRAND TOTAL*				

*GST extra as applicable.

SIGNATURE OF CONTRACTOR
WITH TUBBER SEAL