



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B: FINANCIAL BID

TENDER ID: MUM201911019
DATE : 20.11.2019

TENDER FOR:

CIVIL WORK OF PACHPAOLI BRANCH

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

| S.NO. | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|---------------|---|-----------------|-------------|-------------|---------------|
| S. No. | Particulars | Quantity | Unit | Rate | Amount |
| 1 | Providing and applying acrylic emulsion paint of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete | 750 | sq m | | |
| 2 | Providing and Laying vitrified tiles of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.(for repair purpose) | 420 | sq m | | |
| 3 | Constructing 9"thk. Brick masonry wall Providing & Constructing 6" thick brick wall masonry in cement Mortar (1:4) including (1:2:4) R.C.C.Patti of size 11cm X 15cm at bottom & 2 Nos. M.S. bars at to properly bend & bound at ends along with form work,scaffolding,racking out joint, both side neeru plaster finish, clean / level the surface, curing carting away debris out of compound, cleaning the site etc. complete as per instructions of Architect. RCC lintels of 100 mm thickness to be provided at each interval of 2.1 m during brickwork. | 5 | Cu Mtr | | |
| 4 | Providing general cement plaster 12 mm in cement mortar (1:4) in all positions including curring, scaffolding, cleaning, carting away debris out of the compound, cleaning etc. complete as per the instructions of the architect. | 150 | Sq mt | | |
| 5 | Providing and laying Cast in situ/Ready Mix cementPlain Cement Concrete in M-10 of trap/ granite/quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand | 1 | Cu mt | | |
| 6 | Providing and fixing in position reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams and columns, canopies, staircases, newels, chajjas, lintels, pardis, coping, fins, arches etc. as per detailed design and drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed. (use TMT steel only.) | 0.3 | M.T. | | |
| 7 | Providing & fixing Pantry Platform 750 mm wide out of 20 mm thk. Black granite supported over 12 mm thk. cement board including double moulding on the edges to granite, SS Nirali Sink (550 x 450), with 25 x 50 mm size Aluminium pipes TW inserted for framing below counter, including water supply CPVC pipes & bib-cocks, etc. complete. (Item includes dismantling of existing platform). | 0 | RMT | | |

| S.NO. | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|---|-----|--------|------|--------|
| 8 | Providing and fixing heavy duty inter locking concrete coloured paving blocks of 60 mm thickness of having a strength of 300 kg/sq cm of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc complete. | 0 | Sq MTR | | |
| 9 | Providing and fixing granite stone to treads and risers of staircase and entrance including all necessary material and labour. | 3 | Sq MTR | | |
| 10 | Providing and fixing panelling on E lobby, External walls and for External Rolling Shutters boxing. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 50mmx25mmx1.2mm as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete. | 5 | Sqm | | |
| 11 | Providing and fixing white vitreous china Orissa pan (Indian WC), with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid | 1 | NO | | |
| 12 | Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat | 2 | NO | | |
| 13 | Providing and fixing pedestal wash basin with C.I. brackets, 15 mm C.P.brass pillar taps,32 mm C.P. brass waste coupling of standard pattern, including painting of fittings and brackets, with cutting and making good the walls wherever required | 2 | NO | | |
| 14 | Providing and fixing white vitreous china flat back or wall corner type lipped front Urinal of 430x260x350mm and 340x410x265mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 liter white P.V.C. automatic flushing cistern | 2 | NO | | |
| 15 | Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 a) 15 mm nominal bore | 10 | NO | | |

| S.NO. | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|--|-----|------|------|--------|
| 16 | Providing & fixing PVC liquid soap holder of approved design and colour with screw | 4 | NO | | |
| 17 | Providing and fixing in position C.P. brass Taps & fittings with approved make & design etc. complete. (Parryware/ Hindware/ Cera make.) | | | | |
| A | 15 mm dia. Angular stop cock | 10 | NO | | |
| B | 15 mm dia. Bibcock. | 5 | NO | | |
| C | 15 mm dia. Pillar cock. (Minimum 150 mm high) | 2 | NO | | |
| 18 | Providing and fixing 10cm SWR Nahani Trap with S.S. jali 'including SWR bend and piece of pipe up to the outside face of the wall complete. | 4 | NO | | |
| 19 | Providing and fixing following dia. unplasticised SWR soil/vent / waste pipes with stand working pressure of 4 kg/cm ² solid waste pipes conforming to IS:13592 and IS:4985 including jointing with seal ring conforming to IS :5282 leaving 10mm gap for thermal expansion with necessary fixtures' and fittings such as bends, tee, single junction, double junction, slotted vent offsets, cowl with cap on walls or in the ground including fixing the pipe on walls by means of nails & clamps driven through huge in wood holder/ battens fixed with concrete blocks and supported on gr. floor by C. C. 1:2:4 30 X 30 cm size etc. complete. | | | | |
| A | 110 mm dia | 5 | RMT | | |
| B | 75 mm dia | 10 | RMT | | |
| 20 | Providing and fixing 40 mm dia. PVC soil/vent / waste pipes with necessary fixtures' and fittings such as bends, tee, single junction, double junction on walls or in the ground including fixing the pipe on walls by means of nails & clamps driven through huge in wood holder/ battens fixed with concrete blocks and supported on gr. floor by C. C. 1:2:4 30 X 30 cm size etc. complete | 28 | RMT | | |

| S.NO. | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|---|-----|--------|------|--------|
| 21 | <p>Providing and applying fibre reinforced elastomeric liquid water-proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof slab in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge. For horizontal surface one coat @1.85 kg per sqm. Single component UV resistant flexible acrylic coating, vapour permeable membrane(1.0 mm thick) & eco-friendly. Application with brush. Curing must be done by only placing a wet hessian at least upto 72 hrs after drying, and thereafter by proper curing with water(Make-Perma- Eazee Coat/ Choksey-Acrylic colour membrane/ROFF-Hyguard EX)</p> | 100 | SQ MTR | | |
| 22 | <p>Providing and applying water proofing treatment to vertical surface of brick and R.C.C. wall, elevated and overhead R.C.C./ brick water tanks and sumpwell etc. in all directions by using standard acrylic copolymer coating of Roff Hyguard, Monopol 456, Dr. Fixit Pidilite 2K or equivalent in two coats including cleaning the surface by wire brush, washing and drying i, and as directed by Engineer in charge etc. complete</p> | 100 | SQ MTR | | |
| 23 | <p>Erecting, scaffolding, preparing the surface for Synthetic enamel paint two or more coats by rubbing the surface by sand paper of different grade, removing all dirt, smoke, grease, loose particals etc. if any, from the existing surface cleaning the surface thoroughly an removing all dirt from the surface, applying one coat of metal primer etc. complete</p> | 50 | SQ MTR | | |
| 24 | <p>Removing existing and Providing and laying Ceramic glazed floor tiles(Antiskid) of any size (9-10mm thickness) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 sand) including pointing the joints with white cement and matching pigment, curing etc., complete.(Basic rate of Tile Rs. 650/Sq.m.)</p> | 35 | SQ MTR | | |

| S.NO. | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|---|-----|--------|------|--------|
| 25 | Removing existing and Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (6-7mm thickness) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Architect in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete (Basic rate of Tile Rs. 550/Sq.m.) | 80 | SQ MTR | | |
| 26 | Providing & fixing 20 mm thk. & 1.52m x 0.60m size Black Granite Partitions both side polished, between urinals with full round moulding as per drawing. Item includes removing existing partitions with finishing etc. complete | 1 | SQ MTR | | |
| 27 | Providing and fixing M.S Rolling Shutter-hand operated with central locking system conforming to IS:6248, machine rolled 80mm wide laths 1.25mm thick, inter-locked together throughout its length & joined together at end with end locks, including all necessary clips, stoppers welded at required positions with a coat of metal primer & 03 coats of oil paint of specified colour with finishing etc. complete. | 5 | SQ MTR | | |
| 28 | Providing & fixing in position MS Collapsible gates for Bank entrance & exit and painting the new gates with one coat of steel primer and two coats of Synthetic Enamel paint complete | 5 | SQ MTR | | |
| 29 | Providing & fixing Pantry Platform 750 mm wide out of 20 mm thk. Black granite supported over 12 mm thk. cement board including double moulding on the edges to granite, SS Nirali Sink (550 x 450), with 25 x 50 mm size Aluminium pipes TW inserted for framing below counter, including water supply CPVC pipes & bib-cocks, etc. complete. (Item includes dismantling of existing platform). | 2 | RMT | | |

| S.NO. | PARTICULARS | QTY | UNIT | RATE | AMOUNT |
|-------|-------------|-----|------|------|--------|
|-------|-------------|-----|------|------|--------|

| | | | | | |
|--|-----------------------------------|--|--|-----|--|
| | S U M M A R Y : | | | | |
| | Total of civil Work | | | Rs. | |
| | Less discount (if any) | | | Rs. | |
| | Total cost of work Tendered | | | Rs. | |
| | Add SGST @ 9% | | | Rs. | |
| | Add CGST @ 9% | | | Rs. | |
| | FINAL AMOUNT INCLUDING GST | | | Rs. | |

Total Amount
Rupees in words: _____

Signature & Seal of Contractor

Date: _____