

BOQ FOR PROPOSED INTERIOR FURNISHING WORK FOR RAISEN BRANCH

S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
	INTERIOR WORK'S				
	Partitions :				
	Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works				
1	Full Height Partly Glazed Wooden Partitions :				
	Providing and fixing full height partly wooden, partly glazed partitions- specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways 8 mm thk. MR plywood Termite & Borer proof from both the sides 1.0mm thick approved shades of laminate 5 mm thick	96.00	SQM		
2	Full Height Solid Partition				
	Providing & fixing at site Solid partition with 50 x 50 x 1.6 mm Aluminum box frame with spacing at 600- 900c/c horizontally & vertically, to be sandwiched with 8.0mm MR ply from both the sides and finished with 1.0mm thick laminated finish on both the sides, The cost shall include all labor, materials, strictly as	28.00	SQM		
3	Full Height Cement Board Double Skin Partition with				
	Providing and Fixing full height cement board double skin partition made out of 65X65X3 mm thick aluminium section and 10 mm thick cement board of Bison or equivalent make. Alum. section to be fixed at maximum 600 mm centre to centre for verticle members and at 0', 900 mm, 2100 mm and ceiling levels for horizontal member fixed with wooden screws, with Painting	15.00	SQM		
4	Flush Door / Partly Glazed Door with Frame				
	Providing, making & Fixing of partly Glass/ Flush door at site,-32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) The cost shall include Frame of 2nd class BTC/ Teak wood Frame of 100mm x 50 mm, Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm	22.00	SQM		
5	Low Height partitions With / Without Glass :				

	Providing and fixing Half Height (approx-1200 mm ht.) partitions. Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways(Horizontal/Vertical) 8 mm thk. MR plywood Termite & Borer Proof from both the sides 1.0mm thick approved shades of laminate, 12.00 mm thick float glass Etching as per approved design wicket gate wherever required with Godrej Night latch Note -Including all fittings,material, SS hinges, SS tower bolts screw, labour etc. Complete. (Making provision	43.00	sqm		
6	ALUMINIUM DOOR WITH FRAME FOR UPS &				
	Providing and fixing at site door to be made up approved shade of powder coated aluminum sections (heavy duty) as top & bottom sections with 6.0mm thick plain FLOAT glass in between, the glass panel shall have round polished edges. The external frame of the door shall be of size 100 x 50 x 2.0mm powder coated aluminum Box section section to be fixed in walls / as per site with anchor fasteners and heavy duty mechanical screws. The door shutter shall be in aluminum sections 85.0 x 44.5 x 2.0mm for top, and sides and 114.3x 44.5x 3.0mm in bottom rail, inclusive of with standard aluminum clips to be made strictly as per the drawing. and pivot arrangement with SS handles, all necessary fittings	4.20	SQM		
7	Toughened Glass Dividers For Single Window				
	Providing, making and fixing Toughened Glass :- a. 12mm thick toughened clear float glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all	12.00	sqm		
8	WICKET GATE				
	Providing and fixing at site wicket gate in the existing partition to be made up well seasoned hard wood/ 32mm flush door with 8.0 mm commercial ply, to be laminated on both faces with 1.0 mm thick laminate of approved shade, The cost of the gate shall include SS hinges, door closer , tower bolt, locking arrangement etc.	2.00	sqm		
9	VERTICAL BLINDS				
	Providing & installing Vertical Blinds of Trac / Vista or equivalent, 100 mm wide, in two colours, of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. All metal parts shall be corrosion resistant and rotating parts shall be self lubricating. The fixing of the top rail	21.00	sqm		
10	MAIN ENTRANCE DOOR WITH 12.0MM TOUGHNED GLASS & Patch Fittings				

	Providing and fixing at site Main entrance/ other doors "fully glazed" of 12.0mm toughened glass to be fixed with patch fittings including locks, with 600mm SS brush finished "D" Type door handle. The cost shall include all the fittings, Door handles, locks all materials, transportation fixing , all labour, contingencies etc complete but excluding cost of Floor Spring.	6.00	sqm		
11	FLOOR SPRING				
	Providing and fixing at site heavy duty Hydraulic floor spring for 12.0mm thick toughened glass door with patch fitting of Godrej/ Doorma Make only, to be fixed at site, inclusive of all labour, materials,	3.00	NOS		
12	Panelling Works (Walls , Columns, etc):				
	Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co- ordinate with electrical & AC contractor for				
13	Wall/Column Panelling				
	Providing, making and fixing single skin paneling (Using 6 mm thick MR plywood), plain and/or curved in profile, on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 – 0.45 mt. ht., as required, made out of 25 x 25 x 1.0 mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top	115	sqm		
	MDF Work:				
14	6 mm :Providing and fixing 6 mm Thick Plain MDF sheet in required design/pattern/ shape/size, etc. for application of texture paint/finishes. MDF shall be fitted over plywood structures, single skin panelling or double skin ply partition and cost shall be calculated for all these application. It shall be provided & fixed in major areas, bands and /or geometrical patterns and edges flat/ bevelled/ rounded off as per requirements upon approval from the Bank's engineer. MDF shall be of reputed makes like Century/ Greenply etc. and cost shall include all recommended adhesives, nailing, screwing, mitring, edge finishing etc. complete as per the	40	SQM		
15	FALSE CEILING (GYPSUM)				

	Providing and fixing gypsum false ceiling. in 12.5mm thick Gypboard (POP) plain false ceiling with corner POP molding & GI suspended from RCC slab/ Beam as approved by Bank/ Architect including G.I. Parameter Channels of size 0.55 mm thick having one flange of 20mm and another flange of 30mm and web of 27mm along with parameter of ceiling,screw fixed, to the brick wall / partition with the help of nylon sleeves and screws at 600mm C/C. The suspended G.I. Intermediate channels of size 45 x 0.9 mm thick with two flanges of 15mm each from the soffit at 1200mm C/C with GI cleats and steel expansion	182.00	sqm		
	51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with help of connecting clips and in direction perpendicular to intermediate channel at 457 mm C/C. 12.5mm Tapered edge Gypboard channel at 457mm C/C in both the directions screwed fixed to the ceiling section with 25mm dry wall screws at 230mm C/C screw, fixing is done mechanically with drilling machine and suitable attachment. Finally the boards are to be jointed and finished with jointing compound, paper tape and two coats of top Coat, suitable for Gypboard (As recommended practice of India Gyp.) For light fittings incutouts etc are to be made with a frame of parameter channels of size 20 x 27 x 30 x 0.5mm thick supported suitably. Angle beads, edge beads, control joints as required to be provided. The quoted rates to include all the above				
16	Cove in ceiling :				
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector	98.00	RM		
17	FALSE CEILING (ARMSTRONG)				
	Providing and fixing of false ceiling at all heights of 600mmx600mmx12mm Armstrong mineral fiber ceiling tiles of type IBIZA RH-90 laid on Armstrong prelude XL exposed grid systems with 9mm wide T Section flanges colour white. The frame work comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit approved hangers at 1200mm maximum centers. Hangers (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. flush fitting 1200mm along cross tees (with double stitching) to be interlocked between main runners at 600mm c/ c to form 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mmx600mm modules to be formed by fittings	178.00	sqm		
18	Water proof Exterior grad Grid Tile Ceiling :				

	Providing and fixing Water proofing Exterior Grade 600x600x 10-12 mm Grid Tiles including all framing work for tiles fixing for external side corridor side including all material, laboue etc complete	30.00	SQM		
19	COMPUTER COUNTER				
	Providing & fixing at site 2'-0" wide computer platform in server room to be made in 18 mm thick Commercial Ply to be supported with 18 mm Commercial Ply verticals AT 4' C/c. The computer platform shall have sliding keyboard at every 4'-0" c/c and shall have single drawer at every 4'-0" c/c. All the exposed surfaces 1.0mm thick laminated finish, and all the inner surfaces to have 0.8mm thick laminated finish. All exposed edges shall have 18 mm teak wood	2.50	RM		
20	DOOR CLOSERS				
	Providing & Fixing Hydraulic Door Closers, godrej or EQ Make to Door Shutter with Frames using necessary Screws, Nuts & Bolts etc. complete.	12.00	NOS		
21	ALUMINIUM CLADDING				
	Providing & Fixing at site 3.0mm thick Aluminum External cladding to be fixed at the site over Aluminum tubular pipes placed between 600 x 750mm in both the directions with two colours, as per the design, all the joints shall be filled by exterior grade of Silicon sealant, the cost shall include all materials, labour	20.00	Sqm		
22	WINDOW CLOSING				
	Closing the Existing window with 18 mm ply with framing etc complete including all material , labour etc complete	18.00	Sqm		
23	DISMANTELLING WORK				
a	Dismantling of existing wiremesh partitions/m.s. Grill/ false ceiling and stored the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges	1	JOB		
b	Dismantling of cash, clerical counters, tables, side units etc. and shifted the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete.	1	JOB		

c	Dismantling of old Alluminium window/Glass/ wooden partitions+windows/ brick partition wall/flooring/dado tiles / water pipes and shifting to a suitable place as per the instruction of the branch including shifting charges within the branch premises etc. The cost shall include removal/ dismantling etc. of existing wall tiles, dressing/ chiselling/ finishing/ replastering etc. for levelling or surface preparation purposes to achieve smooth, leveled surface suitable for tiling. Disposal of dismantled/ chiseled tiles and all related debris shall be borne by the contractor outside compound as per Municipal norms. The cost shall also include safely chiselling out remains of tiles from the wall surface without damaging existing pipelines, conduits, cables, wires, switchboards or any such item concealed inside the wall below the tiles., safe handling and removal of debris to a safe distance as directed by the engineer-in-charge.The work shall be done with utmost care to avoid any structural or physical damage to the existing electrical wiring, plumbing works, doors, ventilators, exhaust fans etc. complete	1	JOB		
	Safe Dismantling of Old Plumbing works including (a) safe disconnecting and removal of wash basins, taps, mixers, shower heads, hand showers, geysers, angle cocks, flexible connectors, western seats, flush tanks, and all such exposed plumbing fittings, mirrors, holders etc. (b) removal intact or in broken condition of indian seats/orissa pans , removal of concealed valves, gully and/or nahani traps, pipelines, mixers, diverters or all such concealed items causing hindrance to the new works on walls and/or floors (c) removal of all filling material, old waterproofing, including chiselling of extraneous materials, coba fillings etc so as to achieve the face of concrete slab of toilets suitable for reworking and waterproofing as required including minor repairing works like plaster etc if required, including safe	1	JOB		
24	BLOW PLATFORM COVER FOR PANTRY				
	Providing and fixing at site front shutter cover in 25.0mm thick Commercial block board with 1.0mm thick laminated finish on external surfaces and 0.8mm thick laminated finish on inside surfaces, the shutters to be fixed to main frame by heavy duty SS Hinges, the cost shall include all handles, magnetic	5.2	SQM		
B- FURNITURES WORK					

a.	Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. On the left side platform at bottom for CPU. The bottom compartment made up of 18mm thick. MR plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished. One M S powder coated keyboard tray with mouse tray as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufacturers specification to be				
	Tables :-				
	Providing and supplying table detailed below : 1.-18 mm thick MR Plywood 2.- 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved made 3.- TW half round beading of sect 20 x 12 mm duly polished 4.- Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer. 5.-Drawer made of 18 mm thk. MR Ply wood for the front and rear 12 mm MR Plywood for sides and 6mm thk MR ply for the bottom sliding & teak wood beading of sect. 20 x 6 mm 6- EBCO Sliding Telescopic Rail +M S powder coated keyboard tray with mouse tray. Note: all fittings, fixtures, locking				
1	Branch Manager Table :	1	NOS		
	same as above but providing and supplying Executives Branch Manager of size -1.80 m x 0.90 m x 0.75 m ht.				
2	Officer / Relationship Manager/ Auditor Tables :	10	NOS		
	same as item above but providing and supplying Officer / Relationship Manager/ Auditor Tables of size 1.65 - 1.50 m x 0.75 m x 0.75 m ht.				
3	GRAHAK MITRA+GUARD	2	No.		
	same as item above but providing and supplying Grahak Mitra table- Size 1650mm x 800mm - 900mm x 750mm				
4	SINGLE WINDOW TRANSACTION COUNTER				
	Single Window Operator Counters : same as above item & Following specifications and per dimensions specified.:- a. Size- 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement. b. 18 mm thick MR Plywood c. 1 mm thick laminate d. The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood e. Finished with 1 mm thick Plain or Textured I aminate Hidden areas like inside of	9.00	RM		
5	Corian Marble Surfaces on Furniture / Partitions :				

	Supplying, Fabrication and Installation of Dupont/Corian of thickness as specified below, applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate, in plain or curved profile. To minimize material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note: Corian Sheet use in				
	12 mm thick	16.00	SQM		
6	Wall Mounted Writing desk :				
	Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 18 mm thk. MR plywood and 12 mm thick glass top, and sides and edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed . The cost shall be completed with lippings, mouldings, fittings,and accessories etc as per	1	NOS		
7	Storages / Credenza :				
	Officer Storage/Side Credenza/Back Credenza :				
	Providing, making and placing in position Side/Back Credenza storage:- Size 375mm depth, height of 750 to 900 mm 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete. 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. 4- All drawers shall be fitted with telescopic channels and locking arrangement laminated with 1 mm thick plain external surfaces and 0.8 mm thick white lamination on internal surfaces Note- SS Hinge, SS handles, magnetic catches, Credra or ebee lock &	24	Sqm		
8	Digital Printed 3M or equivalent Backlit Glowsign for interior and exterior signages to be fitted over as per the pattern / designs wherever required and cut and fitted in place as per the manufacturer's instructions and to achieve patterns / designs	2	Sqm		
9	Numbering of Desks : .				

	Providing & fixing in position at all levels, Numerical Numbers on vinyl stickers / 3M or equivalent - front/ back side pasting on glass/ lamination, , with numerals on it from 1 to 20 in circular form,of diameter 100 mm or as directed. The colorful decals (SBI Blue & white) shall stick on the inside of the glass. The adhesive is on the front of the label. Graphics, however, are read from the outside. For pasting on laminate surface, it shall	20	Nos.		
10	Drop & Complaint Box :				
	Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.	0	Nos.		
11	Providing and fixing of green channel box on the column made out of 18 mm thick commercial block board and green coloured 1mm thick laminate as per design and as directed by the Engineer Incharge.	1	Nos.		
12	Pin-up boards :				
	Providing and fixing Pin-up boards of 12mm thk. pin board covered with plain matt/cotton fabric as per approval, the fabric stuck with rubber based adhesive to the board as instructed. Cost shall include all tw lippings, base preparation required and joints on fabric shall not	2	Sqm		
13	NOTICE BOARD :	1	Nos.		
	Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the				
14	Planters :				
	P & F in position planters of size 15"x15"x15"made out of 18mm MR plywood or 1 ½ " x1 ½"wooden frame with laminate & duly polished. on all exposed surface including making GI housing for plants made of superior quality Galvanized Sheets18 Gauge with rounded top edges the top and all sides/ bottom to be water tight The job shall include all material, labour, wastages etc.	0	Nos.		
ESTIMATES FOR CIVIL WORKS					
1	Plastic Emulsion Paint :				

	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris. Then first coat of primer to be applied. After this necessary leveling shall be done with putty and second primer coat shall be applied. The plastic emulsion paint of approved shade and make shall be applied in minimum 2 coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the	205	SQM		
2	Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, Walls :				
	Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls, etc. Removing, scrapping & cleaning the existing enamel paint on doors, windows, grills, metallic surfaces, etc. paint by scrapping, sand papering and scrubbing. Then first coat of primer to be applied. After this necessary leveling shall be done with putty & second primer coat shall be applied. The enamel paint of approved shade shall be applied in minimum 3coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the SBIIMS. (The grills, metallic surfaces, etc. shall be finished with	70.0	SQM		
3	OIL BOND DISTEMPER				
	Two or more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials, labour etc complete.	750.0	Sqm		
4	TEXTURED PAINT				
	Applying approved shade, pattern and surface textured paint over the wall, to give an even shade/ pattern, including all materials, labour etc complete, over the existing POP punning wall surface	15.0	sqm		
5	"WEATHER COAT EXTERIOR EMULSION PAINT Providing and applying two coats and final coat of weather proof exterior emulsion paint (Asian / Berger or equivalent) 7 years warranty of premium quality of approved make & manufacturer of required shade after thoroughly brushing the surface free from mortar dropping and other foreign matter, including two coats of primer and two coats of putty(JK, ASIAN or	50.0	SQM		
6	WHITE WASH				

	Two or more coats of white wash with brush over the existing ceiling, after scrapping the existing finish. to give a neat smooth finish including all materials,	420	Sqm		
7	FLOORING DOUBLY CHARGED VITRIFIED TILES				
	Providing and fixing mirror polished Full body doubly charged vitrified tile flooring Premium quality, RAK, Kajaria, Jhonson, make with pattern of different color as per the given design, 600 X600 x 9.0MM tiles to be fixed at site at Floor and in skirting including leveling of the base below (if required) with 1:4 cement mortar, Including filling of the joints between two tiles with matching shade of "Tile joint filler", including	220	SQM		
8	Removing of existing Vitrified tiles floor &, throwing away all the waste materials, away from the existing site including transporting, labour etc complete.	220	sqm		
9	Providing and fixing stainless steel sink 1 number Nirali Make or equivalent as per approval of size approx. 18inch X 24 inch or as available per approval in platform complete including all required cutting, filling, preparation for installation, connecting	1.00	NOS.		
10	Providing and fixing at site Stainless steel railing in stair with circular posts, and as per design including all materials, labour etc Complete	7.00	RM		
11	Providing & constructing Zade Black Granite platform for pantry and wash basin counters complete as per specifications with 18-24 mm kota stone stand and kota stone or MS angle/T section supports as required and as instructed, including base stone in kota stone and fixing of 15-18 mm thick mirror polished, machine cut jet black granite with simple full round edge moulding and facia for pantry counter and double thick edges with full round moulded edges and of required size. The granite full round moulding shall be fixed with araldite adhesive to the counter top. The cost shall be inclusive of cutting for sink, basin, taps etc. as and when required	3.00	SQM		
	DISMANTLING WORK				
12	Dismantling of existing wall (8"/4"), RCC Stair waist slab, Chajja etc repairing of wall , plaster etc complete, throwing away all the waste materials, away from the existing site including ,transporting the same if required all labour etc complete. All the debris, waste material to be thrown on the nearby municipal	2	CUM		
13	Dismantling of existing Railing of stair case throwing away all the waste materials, away from the existing site including ,transporting the same if required all labour etc complete. All the debris, waste material to be thrown on the nearby as per instruction.	1	JOB		
	BRICK WORK 4"				

14	Erecting of 100mm thick brick work in 1:4 cement mortar with 2 nd class brick including all materials, staging, curing	5	SQM		
	BRICK WORK 8"				
15	Erecting of 200mm thick brick work in 1:5 cement mortar with 2 nd class brick including all materials, staging, curing	2	CUM		
16	12 /15 mm 1:5 cement plaster on New/existing brick wall including necessary staging all materials, labour etc complete	50	SQM		
17	CHANNEL GATE				
18	CEILING COVERING WORK				
	Cover Ceiling with M.S Angle frame ISA 50x50x5 mm with spacing at 600- 600c/c horizontally & vertically, to be fixed 8.0mm Commercial ply with both side painting. The cost shall include all labor, materials, strictly as per the given design & drawing	10	SQM		
19	Providing & fixing Zade Black Granite Staircase Treads, sill, flooring, etc. complete as per specifications with 15-18 mm thick mirror polished, machine cut zade black granite with double thick full round moulded edges and of required size. The granite treads shall be fitted with full round moulding shall be fixed with cement grout on treads and the double thick moulded edge shall be joined with araldite adhesive to the tread. The cost shall be inclusive of cutting, moulding, transportation, edge polishing, etc. complete and also providing two parallel grooves in the	10	SQM		
20	Paver Block Works :				
	Providing and laying factory made coloured chamfered edge interlocking Cement Concrete paver blocks (min. 60 mm thk) of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand, compacting and proper embedding/laying of interlocking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in common areas such as lawn etc. complete	36.00	SQM		
21	TOILET WORK				
	WALL TILES				
a	Providing & Fixing at site 1st quality 6.0mm thick Glazed ceramic colored tiles of size 12" x 18" to be fixed on walls of toilet with 1:3 cement mortar after removing of existing finish & chipping of old plaster below the existing tiles the cost shall include all materials,	20	SQM		
	FLOOR TILES				

b	Providing & Fixing at site colored 16" x 16" x 8.0mm anti skid ceramic floor tiles to be fixed over the floor surface after removing of existing floor in 1:3 cement mortar including all labour, materials, etc	20	SQM		
e	EUROPEAN WC : Providing and fixing white vitrous pedestal type EWC of Hindware / Parryware make having P / S trap connection including 10 litre capacity PVC ISI approved make low height cistern tank. The rate should include all fittings jointing material, labour and making connection with the existing line complete.	1	NOS		
h	Providing & Fixing at site Light Colored Wash basin of Standard size (450 x 350) including pedestal and heavy duty pillar cock Quarter Turn of Parko, Plumber, Jacquar make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all	1	Nos.		
i	Providing & fixing at site 20mm CPVC pipe of 2.0mm wall thickness Class to be fixed in walls including all accessories after making Necessary chases in the existing Brick Work, fixing of pipe and making chases good including all accessories labour, materials,	20	M		
j	Providing & Fixing at site heavy duty Quarter turn foam flow Bib cocks, with ceramic disc angle cock & other taps of Parko, Plumber, jacquar make as per the site requirement etc complete.	4	Nos.		
k	Providing and fixing at site 5.0mm mirror to be fixed at site with 12.0mm BWP ply backing and to 25 x 50mm teak wood frame duly painted to match the tile color including all materials, labour etc complete.	3	Nos		
o	Providing and fixing at site towel ring Stainless Steel heavy duty to be fixed at site with metallic Anchor	3	Nos		
p	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials,	4	Nos		
22	CHANNEL GATE REPAIRING WORK				
	Repairing of Existing Channle gate with proper Alignment of channel gate, welding,complete with bolts, nuts, locking arrangement, stoppers, handles,and proper rolled on pully at site including	1	JOB		
23	ALUMINIUM WINDOW :				
	Providing and fixing composite windows with upper and lower portion of 500 mm (height) fixed and middle portion of about 1200 mm to be sliding with 2/3 track using standard approved section and 4mm float glass, to be provided with rubber gaskets, locks, handles, silicon sealants on all edges, Complete as per design and direction of Engineer – in charge. Net sliding shutter	26	SQM		

24	Dismantling of existing plaster, floor , wall tiles of the toilets and toilet seats, throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	10	sqm		
D Part D : Bought-Out Items (Sofa/ Chairs) :					
1	High back, revolving executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej Bravo/Featherite/ Wipro/ make or equivalent as approved for BM.	1	Nos.		
2	Medium back, revolving executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej Bravo/Featherite/ Wipro/ Methodex make or equivalent as approved for officers viz. Sales Manager, Service Manager, Discussion room, SWO counters, Visitor Chairs for BM cabin, etc.	4	Nos.		
Plus GST as applicable		TOTAL			
Amount in words.....					
		Signature of the Vendor			