BILLS OF QUANTITIES FOR PROVIDING, FABRICATING & ERRECTING MS DISPLAY WALL FOR SBI AT AMC BUS STAND BARRICADING, OPP. SBI LHO, LAL DARWAJA, AHMEDABAD.

BILLS OF QUANTITIES (Not to be Filled by the Bidder)

Sr.No	p. Description	Quantity	Unit
lote	: Rate should be inclusive of material, labour, tools, machinary, scaffolding, final dis ,cleaning cutting wastage etc. all taxes, transportation, VAT ,Excise, Octroi etc. No paid Extra as per applicable norms, Contractor will be fully responsible for Water site for execution	ote: GST	will be
1	 PROVIDING,FABRICATING & ERRECTING MS DISPLAY WALL as follows. Providing, Fabrication and Errecting Display wall made of 50mmx50mmx2.60mm thick MS Hollow Section framing 1200x600mm grid and P& fixing 16 Gauge GI sheet welded with frame work in proper workmanship to provide smooth surface for writing or fixing Bank advertisement (Display) Verticale members at 4'-0" distance shall embeded in ground and bracing shall embeded in ground of every 8'-0" distance in concerate pocket of M20 Concerate size 200 dia x 600mm Deep.Pocket to be created by core cutting in road, MS bracing with 8mm thick MS plate with 12mm dia J bolts 450mm long on pocket All MS Hollow pipe section for vertical and horizontal section in between properly weld to steel section complate as directed including painted with two or more coat synthetic enamel paint over a coat of primer etc. complete as directed. Contractor shall errect to make a stable display board in line and level and ansure that it withstands wind pressure and small impact. Display shall have expansion joint at every 60'-0" Rft Rate including M20 Concrete embanding 150mm Dia x 600 mm Depth by Core cutting in Road etc complete as directed by Architect / Consultant / Engineer - In - Charge All complete as per detail drawing, as specified and as directed by Architect / Consultant / Engineer - In - Charge. MS Section of Jindal make or Equivelent make Display wall for Measurement GI Sheet Length and height front side shall be measured and paid 	2,400	SQ.FT
2	Removing verycarefully the existing GI sheet with frame and cutting verticale MS support etc complete including stacking debris and reusable material within AMC Bus stand site area as directed including carting away debris all levels. Height up to 10'-" to 12'-0" [Contractor must visit site to assess work involved befor quoting.]	1	JOB

1

Vijay Sahijwani and Associate:Architect