

**PART – B (PRICE BID)**

**TENDER DOCUMENTS**

FOR

**AIR CONDITIONING WORK**

of

**GACL RANOLI BRANCH, VADODARA.**

for

**State Bank of India**

**TENDER ISSUED TO :**

---

---

---

---

**ARCHITECT**

**:** Ar. *MAYUR SHAH*  
*803, TOP FLOOR,*  
*CENTER POINT,*  
*ALKAPURI,*  
*VADODARA-390007.*  
*(M.) 9377213854*  
*Email - msa.baroda@gmail.com*

## INDEX

Tender documents are in two parts (Volumes) i.e. Part – A and Part – B

### PART – B (PRICE BID)

<b>Sr. No.</b>	<b>Description</b>	<b>Page No.</b>
1	<i>Cover page</i>	1
2	<i>Index</i>	2
3	<i>Bill of Quantities ( 2 nos )</i>	3 - 4

**BOQ : Interior Decoration and Furnishing work : AIR CONDITIONING WORK  
of SBI GACL RANOLI BRANCH, VADODARA.**

Sr. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Supplying & providing of <b>Hi-wall Inverter Split Type AC</b> with high wall mounted indoor and out door unit. having <b>eco friendly</b> refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have <b>copper condensor Unit</b> , Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries/ Toshiba/ Trane/ Voltas/ Panasonic. <b>[Mini 3 Star rating as per BEE Guide Line 2019]</b>				
1.1	Inverter Hi-wall Split AC of 2.00 TR	3	NO		
1.2	Inverter Hi-wall Split AC of 1.00 TR	1	NO		
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	4	NO		
3	Referigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit beyong 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make ( copper pipe concealed in inside wall)	30.49	RMT		
4	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	60.98	RMT		
5	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of Split A/C. ( Ready made)	4	NO		

6	Removing and Reinstallation charges for existing 1.00 TR High wall mounted split A/C at new location including connection servicing & gas filling complete as directed. [Entire new copper piping and drain shall be paid as per item No 3 & 4.] Shifting Existing Premises including indoor and outdoor with MS stand etc complete as directed.	2	NO		
	<b>GRAND TOTAL</b>				

**Note:**

- [1] Rate quoted shall includes all Taxes such as Sales Tax, VAT, Excise, Octroi, , etc. including transportation charges. **Excluding GST[GST will be Paid Extra as per Applicable Norms]**
- [2] 1 Years of M/C warranty with 6 free services and 5 years warranty for compressor shall be provided by the supplier.
- [3] The Standard installation charges for the high wall split A.C shall include 5 meter Each of Refrigerant pipe, Electrical Wiring [Copper Pipe and Electric cable total **length for all new AC machines shall be measured and standard Length for all the new** AC machines shall be deducted and difference shall be paid]
- [4] All Civil work such as Masonary works like breaking away and making good of walls,floors slab etc. Required to be executed in the A.C system installation is the part of the scope of project. ( Rate quoted shall included in Low side work items )
- [5] The Entire Job Shall be Excuted in Total Co. Ordination with the Other Agencies Working on this Project more particulary with the False Ceiling and Electrical work.