

PRICE BID FOR PROVIDING PLYWOOD WITH LAMINATE CHANGE FO MAKING UNIFORM LAYOUT FOR KATTOOR (8627) BRANCH.					
SI	Description of work	Quantity	Unit	Rate	Amount
1	Providing and fixing 6 mm marine flexy plywood and mica of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	8	Sq.M		-
2	Providing and fixing 1 mm mica of approved make to the existing tables, side tables, partitions, storage wherever necessary as per direction of engineer- in charge	30	Sq m		
3	Counter Top:- Providing, fitting and fixing the counters with 18mm thick plywood of approved shade and make finished with 1mm thick flexi mica with good surface finishing and edge . The fixing is to be done on exposed surface of counters, tables or any other surface as directed and should be as per the satisfaction of engineer in charge. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with specifications. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. The area of the surface work shall be measured for finished work.	12	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beadings etc, existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete	180	Sq.M		

5	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	5.00	Sq.M		
6	Providing and fixing front Modesty with 6mm thick Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	6.00	Sq M		
7	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	180.00	Sq m		
8	Painting with synthetic enamel paint 2 coats over priming coat to wood work and iron work after cleaning surface.	35.00	Sq.M		
9	Providing new PVC telescopic key boad tray with channel, if necessary.	10.00	Nos.		
10	Removing the existing drawer channel and fixing new telescopic channel of approved make	15.00	set		
11	Providing and fixing Godrej auto lock	10.00	Nos.		
12	Providing and Fixing 100 mm wide Vertical Blinds of Vista Levton or approved equivalent make and colour.	25.00	Sq.m		
13	Providing and fixing 4"handle of approved make as per direction of engineer- in charge	10.00	Nos.		
14	Providing and ifxing Door Stopper of approved make as per direction of engineer- in charge	4.00	Nos.		
15	Providing and fixing Door hinges of approved make of approved make as per direction of engineer- in charge	6.00	Sq m		
16	Providing and fixing Drawer locks of approved make as per direction of engineer- in charge	20.00	Nos.		
17	Providing and dfixing Night Latch of approved make as per direction of engineer- in charge	5.00	Nos		

18	Removing the waste material from the bank by the contractor including transportation, loading and unloading etc	LS			
	<b>Total Amt excluding GST</b>				





[illegible]

[illegible]

[illegible]


