

PRICE BID

BRANCH : RAHIKA (New premises)

UNDER RBO : Madhubani

Sl. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1.	<u>LOW HEIGHT SINGLE WINDOW COUNTER</u> Making of SWO counters of size 5ft x 2.50 ft by making use of existing workstations of (5' x2.50 ft) and side table.Making the front portion curved as per standard design of SWO counters. Making necessary changes in drawer unit of table including shifting it from left to right ,making provision for d – tel. Including necessary repair and finishing with 6 mm ply of Century/Green/Mayur and 1 mm laminate of white/blue colour wherever required with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I. .	No.	4.0		
2.	<u>FULL HEIGHT PARTITIONS PARTLY PANELED AND PARTLLY GLAZED:</u> Providing and fixing double skin partly paneled & partly glazed full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gamhar, Malaysian Sal wood / hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to false ceiling (if provided) fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick BWP grade plywood and 1.0 mm thick (Greenlam / century or equivalent) blue / white high gloss laminate with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 8.0 mm clear float toughen glass of approved make as above at item-1 of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame and with teak wood beading as per detail design, which is to be of 1 st quality teakwood (all visible wood to be of 1 st quality teakwood) and shall be polished and protected with melamine polish. The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fasteners so as to form a stable system / partition all complete work with provision for wring to be done by other agencies all complete work as per direction.	Sq.m	17.50		

3.	Making and fixing of full height/low height partition by making use of existing full height/low height partition(already made in blue /white laminate) as per drawing including repairing cutting/adding in size with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glossy blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required. Including cutting the glass in required size etc. & disposal of un serviceable materials to complete job as per direction of E/I	Sq.m	65.16		
4.	<u>HYDRAULIC DOOR CLOSER</u> Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn, Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	Nos.	4.00		
5.	<u>12 MM THICK TOUGHENED GLASS DOOR ETC</u> Providing and fixing / fitting 12 mm thick toughened glass of approved make with all necessary hardware accessories etc including cost of labours and materials etc as pe the direction.	Sq.m	13.38		
6.	Providing D-Tel depository cabinet of Godrej make in counters of size-691mm x 460mm x 460mm of weight 33.00 kg of automatic locking including of cost of labors & materials etc. to complete job as per specification & direction of E/I.	Nos.	4.00		
7.	<u>WORK STATIONS / TABLES</u> Fixing of existing work stations(already made up in blue/white laminate) along with side units as per drawing with necessary repair ,changing position of drawer units if needed. Repairing with 6 mm ply and 1 mm laminate of glossy white/blue colour wherever needed.	Nos.	4 no.		
8.	<u>FOOT REST:</u> Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings top clad with rubber mat. All inner portions shall have a coat of mat finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. Materials shall be above at item –10.	Nos.	8.00		
9.	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make of Du-Point only on table top, table front, & designer beads SBI facia, back black color & rounding of edges to complete in all respect, as per site condition and instruction of R.M/C.M (CS & CM)/ with rounding of edges etc to complete job. (Counters, B.M's table and S.M's table tops with fronts).	Sq.m	21.50		
10.	Refixing of existing low height caninets(already made in blue/white laminate) of different sizes as per the direction , including repairing and cutting into size as per drawing with 6 mm thick ply board of Century/Green or	Sq.m	6.50		

	equivalent make & 1mm thick high glossive blue / white laminate of Century / Greenlam or equivalent make wherever required .				
11.	<p><u>FALSE CEILING.(GYPSUM TILE)</u></p> <p>Providing and fixing of Gypsum tile of approx. size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Armstrong's Prelude XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be interlocked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-ordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.</p>	Sq.m	160.50		
12	<p>Providing and fixing in position Seamless Gypsum Board Plain False Ceiling in one or more levels as directed including vertical surfaces between different levels.</p> <p>The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards of approved make, duly finished with recommended filters, tapes, etc. to have a seamless flush look.</p> <p>The ceiling system is to be fixed to a concealed GI framework(Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways.</p> <p>The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners.</p> <p>The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc.</p> <p>The work includes applying two coats of approved putty & primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion</p>	Sqm	45.74		

	<p>paint on the surface.</p> <p>Provisions for openable type lids for facilitating arrangements for rolling shutters are to be made as required.</p> <p>Lids shall be made out of 9 mm thick BWR plywood duly painted to match the ceiling surface and provided with 2 No. 75 mm SS butt hinges & 1 No. 100 mm SS tower bolt along the surface.</p> <p>The work is to be completed with all materials, accessories. Labour, tools & tackles and in strict conformity with manufacturers specifications & recommendations.</p> <p>Rate is to include the cost of making openings for ceiling mounted electrical & air-conditioning accessories.</p> <p>All materials should be approved by Bank.</p> <p>Plan area is to be measured for finished work.</p>				
13	<p>Providing and fixing Ceiling Highlighter panel over transaction area as per design.</p> <p>The Ceiling Highlighter Panel is a recessed continuous strip with blue high gloss polyurethane coating on its surface and is provided to accentuate the Bank's blue color.</p> <p>The panel shall be made with 12.5 mm thick plain Gypsum board of approved make duly finished with recommended fillers, tapes etc to have a seamless flush look.</p> <p>A cut-out 600 mm wide with desired length is to be made on the false ceiling as directed with GI intermediate channels, ceiling sections, ceiling suspension angles etc. fitted to it as required.</p> <p>The cut-out is to be surrounded by 25 mm wide plain Gypsum sections fixed above & around its periphery by GI screws.</p> <p>The panel board is then to be placed on the Gypsum sections surrounding the cut-out and shall be fixed on it by 25 mm long GI drywall screws at 250 mm intervals along the perimeter.</p> <p>The panel board shall have a projection of at least 25 mm beyond the perimeter of the cut-out.</p> <p>The panel board is to be finished with blue paint and high gloss polyurethane coating of approved shade & make on its surface.</p> <p>Provisions are to be made for fixing LED strips.</p> <p>The work is to be completed with all materials, accessories, labor, tools & tackles and in strict conformity with manufacturers specifications & recommendations.</p> <p>All materials should be approved by Bank.</p> <p>Visible plan area is to be measured for finished work.</p>	Sqm	6.0		
14.	<p>Providing and fixing wall & Column Paneling as per drawing & design :</p> <p>The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically.</p>				

	<p>The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity.</p> <p>The framework is to be covered by 9 mm thick BWP plywood on exposed side with suitable fixtures.</p> <p>The surface is to be finished with 1 mm thick high gloss laminate of approved shade & make.</p> <p>Provisions are to be made for fixing LED strips.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc.</p> <p>Executed elevation area is to be measured for finished</p>				
(a)	Interior Columns in Banking Hall	Sqm	34.17		
(b)	With 12 mm thick MDF board fixed on frame finishing paneling surface with high gloss PU paint/1 mm thick high gloss laminate-In the wall back side of SWO Counters.	Sqm	120.16		
15.	<p>Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design :</p> <p>The film are to be pasted on main glass door & other glasses as directed, cut & fixed as per design including the Bank's logo.</p> <p>Supporting cash memo/bills are to be produced for payment of this item including certificate from the dealer certifying use of the product.</p> <p>Executed area of the film pasted on glasses shall be measured for finished work.</p>	Sqm	8.00		
16.	<p>Providing and fixing writing Desks as specified below :</p> <p>Providing and fixing Column-mounted Circular Writing Desk as per design.</p> <p>The Desk is to be fixed to the column along the perimeter through peripheral 19 mm thick BWP block boards with angled MS plate support as required.</p> <p>The Desk shall have two parts viz. head and stand. The Head, circular in plan, is to have an average 450 mm projection around the column periphery for facilitating writing. The Stand, conical in shape on elevation, is to be fixed to the column with a projection of 200 mm at the junction with head, and 50 mm at the floor-column junction all around. The head is to be provided with two circular disks made out of 19 mm thick BWP block board.</p> <p>The disks are to be fixed to the column keeping one on top & the other at bottom, 200 mm apart to have pigeon hole-shaped cells. Dividers, made out of 12 mm thick BWP block board sections, shall be provided to pigeon hole cells, 200 mm wide at the openings for keeping vouchers, slips etc. Each of the disks shall have an octagonal shaped hole in the centre around the column. The stand is to be made with an inner wooden framework of 50 mm x 37.5 mm well seasoned Malaysian sal wood sections to have a conical shape as per design.</p> <p>The framework shall be covered with 12 mm thick flexi-ply</p>	No.	1.00		

	<p>all around.</p> <p>The work is to be finished with 1mm thick high gloss laminate on the surface. The desk is to be fixed properly on the column by angled M.S plates as required with GI screws. The plates shall be welded firmly with rawl plug in RCC along the vertical surfaces.</p> <p>The inner surfaces are to be finished with French polish.</p> <p>The work is to be completed with necessary lipping & polishing to exposed block board edges. A Glazing on the work top is to be done by fixing of 12 mm thick transparent toughened glass on it with SS stud fittings.</p> <p>All edges of the glass are to be finished with mirror polishing. The work top shall be at a height of 1.0 m from FFL. The work is to include all necessary materials, accessories, labour, tools & tackles. This item may be done only if the breadth to width ratio of the column is between 1.0 and 1.2.</p> <p>Payment shall be made for finished work.</p>				
17.	<p>Providing, fitting and fixing Drop Boxes as per drawings :</p> <p>The box shall have an approximate size of 400 mm width, 200 mm depth and 450 mm height.</p> <p>One drop-slit, 200 mm long & 5 mm wide with edges smoothed properly, is to be provided on the top of the box. The box shall be provided with a small lockable door with 2 no. 75 mm SS butt hinges and a small SS hasp bolt. The item is to be made out of 12 mm thick BWR block board to a pigeon hole shape. The work is to be finished with 1mm thick high gloss laminate of approved shade. The inner surfaces are to be finished with French polish.</p> <p>The work is to be completed with necessary lipping & polishing to exposed surfaces.</p> <p>The box shall be fixed to a wall or column in the hall at a height of 1.2 m from FFL or as directed.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles.</p> <p>Payment shall be made for finished work.</p> <p>Boxes of the following categories are to be provided -</p>				
(a)	Suggestion Box	No.	1.00		
(b)	Cheque Drop box	No.	1.00		
©	Voucher Rack	No.	1.00		
18.	S/F/F Godrej mortise locks/ Night latches including cost of labor & materials etc. to complete job.	Nos.	5.00		
19.	<p><u>ROLLER BLINDS</u> :</p> <p>Providing & fixing of roller blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows & opening of B.M's chamber. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in-charge /Bank.</p>	Sq.m	10.50		

20	Providing and fixing of branding film on glazed partition of BM cabin	Sqm	20.81		
21	Labour charges for fixing of existing 12 mm toughened glass for BM's cabin with necessary fittings etc. all complete.	Sqm	20.81		
22	Providing and fixing of 12 mm toughened glass on SWO counters with necessary fittings etc. all complete	Sqm	2.50		
23	Fixing of existing mineral fibre false ceiling using existing tiles and frame structure labour charges only	Sqm	60 sqm		
24	ACP COVER FOR ROLLING SHUTTER: Providing and fixing of ACP cover for rolling shutter set within inner wooden cover frame work of 50mmx50mm well seasoned Malasian sal wood sections placed at suitable spacing not exceeding 600 mm c/c .The frame work shall be covered with 12 mm thick BWR plywood. The work is to be finished with 3mm thick exterior grade Aluminium Composite Panel (ACP) cladding.of approved make and shade with grooves duly treated with silicon sealant.	SQM	16.50		
Total					

**PRICE TO BE QUOTED EXCLUSIVE OF GST
GST WILL BE PAID BY BANK SEPARATELY**