

BOQ OF INTERIOR FURNISHING WORKS OF SAIMS BRANCH & ON SITE A.T.M. ROOM AT AUROBINDO COLLEGE, INDORE REGION, RBO-1

| S.No. | Description of Item | Qty | Unit | Rate | Amount |
|----------|---|-------|------|------|--------|
| A | Part A : Interior Works : | | | | |
| | Mode of Measurements : Area of exposed and finished surfaces will be measured. | | | | |
| 1 | False Ceilings : | | | | |
| 1.1 | Gypsum Board False Ceiling : | 96.00 | Sqm | 0 | 0 |
| | Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm & a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres. ... | | | | |
| 1.2 | Cove in ceiling : | 74.00 | Rmt | 0 | 0 |
| | Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc. | | | | |
| 1.3 | Mineral Fibre Grid Tile Ceiling : | 77.00 | Sqm | 0 | 0 |
| | Mineral Fibre Acoustic Ceiling Tiles: Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, Gyproc or equivalent make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mmx 600mmx 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. ... BLACK T JUNCTION | | | | |
| 2 | Partitions : | | | | |
| 2.1 | Full Height Partly Glazed Partly Wooden Double Skin Plywood Partitions : | 34.00 | Sqm | 0 | 0 |

| | | | | | |
|-----|---|--------|-----|---|---|
| | Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/ Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including antitermite treat-ment to all wooden members wherever used. The partition to be sandwiched with 8 mm HDF Board / MR plywood from both the sides and finished with 1.0mm thick approved shades of laminated finish & match the panelling pattern. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals.The cost shall include all labor, materials, strictly as per the given design & drawing etc. | | | | |
| 2.2 | Low Height partitions With / Without Glass : | 26.00 | Sqm | 0 | 0 |
| | Providing and fixing full height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite to all wooden members wherever used. The partitions to be sandwiched with 8.0mm HDF Board / MR plywood from both the sides & finished with 1.0mm thick approved shades of laminat. finish & match the panelling pattern. The borders/edges to be lained finish. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete. One additional section 50 x 50mm shall be placed at 700 mm level from floor to fix the table. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite. | | | | |
| 2.3 | Full Height Laminated Double Skin Plywood Partitions Wth Both Sides Laminations : | 9.00 | Sqm | 0 | 0 |
| 3.1 | Wall/Column Panelling - Type I : | 154.00 | Sqm | 0 | 0 |
| | Providing, making & fixing single skin paneling (type I using 6 mm thick MR plywood) on walls, front facia, boxing for rolling shutter, and/or columns & /or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 mt. ht., as required, made out of 50 x 25 x 1.0 mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 8 mm thick MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as. | | | | |
| 3.2 | Wall/Column Panelling - Type II : single skin panelling | 8.00 | Sqm | 0 | 0 |

| | | | | | |
|-----|---|-------|-----|---|---|
| | Providing and fixing single skin panelling (type-II) on walls , front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises as required with ply frame work for levelling and 18 mm thick MR ply of approved ISI grade, and/or limited use of 6mm Flexible ply for panelling of circular columns etc. including fixing as per pattern and style as directed, with salwood frame of size 38 | | | | |
| 3.3 | Cabinet for Electric Panel : | 4.00 | Sqm | 0 | 0 |
| | Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk MR grade plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved made and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots (approx. 10 mm wide) to be cut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet). | | | | |
| 3.4 | ACP Panelling Works : | 46.00 | Sqm | 0 | 0 |
| | ACP Panelling in ATM room & exteriors and Shutter boxing with trap door : Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, (OR Aluminium tubular section of same sectional dimensions if required) of good quality, fixed/fabricated @ 600 mm c/c or less as per site requirement or members recommended by the manufacturer and in accordance with the specifications and recommendations of the manufacturer. The structure shall be fitted in place on walls/ beams/columns/ceilings/ MS fabricated structures etc. as instructed using recommended fixing method, with 3M or equivalent adhesive and with mirror screws, joints to be finished with silicon based sealant, etc. complete. ..contd.. | | | | |
| 3.5 | 12 mm Additional Plywood framing/ Boxing : | 6.00 | Sqm | 0 | 0 |
| | Providing and fixing additional ply framing/boxing in 12 mm commercial ply (and/or 8mm commercial ply if required) for fixing of softboards/whiteboards etc. on wall surfaces or existing single /double skin partitions or boxing on walls/columns including levelling on walls, and in double thickness for small partitions on tables, etc. The framing shall be finished with 1mm thick plain or Textured Laminates (on one exposed surface) of approved shades including inlay etc if required and as directed along back credenza as required as per fixing pattern to achieve overall flush appearance. The framing shall include the provision of switchboard, lan cabling, telephone wiring etc. The cost shall also include providing and applying polish/paint, etc. | | | | |
| 4 | MDF Work: | | | | |

| | | | | | |
|-----|--|-------|-----|---|---|
| 4.1 | 6 mm :Providing and fixing 6 mm Thick Plain MDF sheet in required design/pattern/ shape/size, etc. for application of texture paint/ finishes. MDF shall be fitted over plywood structures, single skin panelling or double skin ply partition and cost shall be calculated for all these application. It shall be provided & fixed in major areas, bands and /or geometrical patterns and edges flat/ bevelled/ rounded off as per requirements upon approval from the Bank's engineer. MDF shall be of reputed makes like Century/ Greenply etc. and cost shall include all recommended adhesives, nailing, screwing, mitring, edge finishing etc. complete, as and in the manner required for proper and seamless fitting. | 7.00 | Sqm | 0 | 0 |
| 4.2 | 3 mm : same as item no. 4.1 but 3 mm thick for groove depth for BM Cabin. (Groove to be shaded with off-white colour). | 24.00 | Sqm | 0 | 0 |
| 4.4 | Full (Through) and Half Cut CNC/ machine cutting of 12 mm thick MDF so as to achieve desired design pattern/ oval/circular/geometrical, etc. through holes in MDF sheets & half cut lines, grooves, logos etc., simple oval/ circular plates and simple circular Bank logos as per the designs so as to achieve precise, neat, perfectly finished circular niches/ plates/ Logos in MDF to the satisfaction of the Bank/SBIIMS. Full surface of the MDF shall be measured and the superscribed square or rectangle shall be measured for the bank logo cutting.The above shall be provided & fixed on ply frame works, panelling/partions/ modesty panels/ columns and including backlight (if required), colouring, etc. complete so as to achieve smooth, buffed & joint free surface as directed by the Bank / SBIIMS. | 0.00 | Sqm | 0 | 0 |
| 5 | Main Door – Toughned Glass : | | | | |
| 5.1 | Providing, making and fixing 12mm thk single/double shutter tough-ned glass doors, at entrance, etc. (each door shutter counted individually) of size 2.10 m ht x (0.75 m - 1 m wide) (approx. as per site requi-rement) as demarcated, swing type door openable both sides made out of 12 mm thk. clear toughened float glass, edge polished, fixed in wooden top and bottom rails of approved colour and finish, fixed on Everite/ozone/ Hardwyn/ Dorma or equivalent floor springs set, upper patch, lower patch, lock key plate, provision of locking system, etc. as per approval. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of appoved make & design on both sides. Including providing "PUSH" * "PULL" sticker lables of approved design & make. The rate to include all materials, labour, transport, taxes, delivered and placed in position at site of work. Each door shall be treated individually with complete set of accessories to be provided on each door. | 6.00 | Sqm | 0 | 0 |
| 5.2 | Partly Glazed Door : (Partly Glazed Door on Floor Spring) | 3.00 | Sqm | 0 | 0 |
| 5.3 | Flush Door : | 12.00 | Sqm | 0 | 0 |

| | | | | | |
|----------|--|------|------|---|------|
| | Providing and fixing single shutter flush doors of approx size 2.10 m x 0.75 - 0.9 m as instructed, hinged type door openable one side as instructed, made up of superior quality waterproof flush door partially glazed (cost of glass included). The door shall be flush door of approx. 32-38 mm thickness, both sides 1 mm thk laminate as per design. Cost shall be inclusive of beadings, all accessories like SS hinges, medium quality mortise handles/locks, baby latches, stopper, etc. Fittings shall be in SS finish as per approval, the cost shall include p/f of door closers of reputed brand as per approval with all doors. | | | | |
| 5.4 | Aluminium Frame Glass Door for UPS / Server Room : | 1.00 | Sqm | 0 | 0 |
| | Providing and fixing at site door to be made up approved shade of powder coated aluminum sections (heavy duty) as top & bottom sections with 6.0mm thick plain FLOAT glass in between, the glass panel shall have round polished edges. The external frame of the door shall be of size 100 x 50 x 2.0mm powder coated aluminum Box section section to be fixed in walls / as per site with anchor fasteners and heavy duty mechanical screws. The door shutter shall be in aluminum sections 85.0 x 44.5 x 2.0mm for top, and sides and 114.3x 44.5x 3.0mm in bottom rail, inclusive of with standard aluminum clips to be made strictly as per the drawing. and pivot arrangement ,with SS handles, all necessary fittings, all labour, materials, etc complete. (to be fixed in sever & UPS room) | | | | |
| 6 | Sub Total : Part A (Interior Works) | | | | 0.00 |
| B | Part B : Furnishing Works : | | | | |
| 7 | Furnitures : | | | | |
| 7.2 | Tables : | | | | |
| 7.2.1 | Providing and supplying Officer's table and other tables as detailed below : | | | | |
| a | The table shall be of size of 1500 x 750 x 750 mm height, with edges been double thick having one side drawer Unit, 350 mm wide (clear internal size) one M S powder coated keyboard tray with mouse tray (<i>measured separately</i>) as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufactures specification. | | | | |
| 7.2.2 | Executives Branch Manager Table : | 1 | Nos. | 0 | 0 |
| | ... same as item no. 6.2.1 but providing and supplying Executives Branch Manager of minimum size 2.1 m x 0.90 m x 0.75 m ht. | | | | |
| 7.2.3 | Officer / Relationship Manager/ Auditor Tables : | 1 | Nos. | 0 | 0 |
| | ... same as item no. 6.2.1 but providing and supplying Officer / Relationship Manager/ Auditor Tables of minimum size 1.65 -1.50 m x 0.75 m x 0.75 m ht. | | | | |
| 7.2.4 | Assistant Tables : | 1 | Nos. | 0 | 0 |
| | ... same as item no. 6.2.1 but providing and supplying Assistant Table of minimum size 1.5-1.35 m x 0.75 m x 0.75 m ht. | | | | |
| 7.2.5 | Single Window Operator Counters : | 5.00 | Rmt | 0 | 0 |

| | | | | | |
|-------|--|-------|-----|---|---|
| | The overall size of each Single Window Counter to be 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement. | | | | |
| | | | | | |
| 7.2.6 | Grahak Mitra Table : | 1 | No. | 0 | 0 |
| | ... same as item no. 6.2.1 but providing, making and placing in position arch shape 1650mm long Grahak Mitra Table of approximate size 1650mm x 800mm - 900mm x 750mm with the following specifications and per dimensions specified. Grahak mitra table with transaction top of 370mm wide and height 150 mm made out of 12mm glass with blue laquered to be fixed with SS studs.. Exposed faces would be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shades.". The table shall have provision only for concealed LED strip lighting (cove type). | | | | |
| | | | | | |
| 7.2.8 | Wall Mounted Writing desk : | 2.00 | Sqm | 0 | 0 |
| | Providing & fixing half round / rectangular customer voucher holders writing counter of width 750-1200 mm and depth 300 - 450 mm fixed to be wall or partition or around the column (on two sides), at a height of 1050-1200mm made of 18 mm thk. MR plywood and 12 mm thick toughened glass top, and sides & edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed. The portion below the pigeon hole box to be provided as a cupboard unit, shall be with openable shutter & adjustable shelf all along the full width of the desk. The cost shall be completed with lippings, mouldings, fittings, and accessories etc as per specification. as per the instruction given by the Bank Engineer. (Measurement vertical area = length x height). | | | | |
| | | | | | |
| 7.3 | Storages / Credenza : | | | | |
| 7.3.1 | Officer Storage/Side Credenza : | 9.00 | Sqm | 0 | 0 |
| | Providing, making and placing in position low height storage cabinets as storage & or runners from 350mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and in 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete. | | | | |
| | | | | | |
| 7.3.2 | Back Credenza / Runner : | 6.00 | Sqm | 0 | 0 |
| | ... same as item no. 6.3.1 but providing and supplying Back Credenza/Runner, low height storage cabinets as storage and/or runners, in 18 mm MR grade plywood in verticals at sides, 900 mm c/c so as to form storage units attached together, each of width 900 mm. (Measurement area = Length x Height). | | | | |
| | | | | | |
| 7.3.3 | Full Height Storage Unit : | 18.00 | Sqm | 0 | 0 |
| a | Providing, making and placing in position 350 mm - 450 mm deep full ht. storage units of reqd. length with overall ht 2100 mm approx with 5 equal compartment, to be constructed in 18mm thk MR grade plywood with TW lipping at edges. | | | | |
| | | | | | |
| 7.4 | Corian Marble Surfaces on Furniture / Partitions : | | | | |

| | | | | | |
|-------|--|-------|-----|---|---|
| 7.4.1 | Supplying, Fabrication & Installation of Dupont/Corian quartz of 12mm thk. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. To minimis material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure & Diamond Blue, preferably on BM's table, SWO counter, as directed. | 10.00 | Sqm | 0 | 0 |
| 7.4.2 | Deduction for lamination work wherever Corian is been used (area same as Corian). | -10 | Sqm | 0 | 0 |
| 8 | Glass Works : | | | | |
| 8.1 | Toughened Glass Dividers For Single Window Counters and Front Partition Glazing / ATM : | 21.00 | Sqm | 0 | 0 |
| | Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1450mm x 400mm - 100mm in tapered shape. Also to provide toughned glass iat the entrance as partiton in Branch & at ATM. All the edges of the glass to be polished for a smooth finish and the glass is to be embedded in half partitions/ floor/ wall and fixed with " D " brackets/ SS fittings as required. The glass bottom to be min. 75 mm above tile surface at SWO and at floor level at partition. Etching of glass with film to be done as directed (measured separately). The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. | | | | |
| 8.2 | Partition Glass / Glass on Transaction side of Single Window Operator Counters : 12 mm glass work : | 5.00 | Sqm | 0 | 0 |
| | Providing, making and fixing in position 12mm thick clear float glass in the front side, vertically of height 400 mm and to place & fix another float glass of 12 mm thickness with round edged to be placed horizontally (of width 400 mm) above the vertical glass of length, equal to the length of the counter. | | | | |
| 8.3 | 12 mm Glass Work : | 6.00 | Sqm | 0 | 0 |
| | .. Same as item no. 7.5 but of 12 mm thickness. Also providing, making and fixing in position 12mm thick clear float glass on top of tables with tapered, rounded & polished edges, etc. complete. | | | | |
| 8.4 | Etching Glass with Film : | 19.00 | Sqm | 0 | 0 |

| | | | | | |
|--------|--|------|------|---|---|
| | Providing & Fixing Birla 3M /Lunar make frosted film fixed on the glass after cleaning and wiping glass surfaces free of any dust or foreign bodies and then fixed plain approved pattern / design film on the glass as per detail drawing inclusive of making necessary cutouts, carting away unserviceable materials out of compound, cleaning the site etc. complete as per the site requirements and the instructions of the Architect. (Basic Cost Of Film not less then Rs.800/- Per smt) . (Measurement area = Length X Height). | | | | |
| 8.3 | Laquered Glass : | 5.00 | Sqm | 0 | 0 |
| | Providing and Fixing of Laquered 8mm Thick Extra Clear Float Glass of reputed brands like Modi, Saint Gobain, ASahi etc. on Table sides/ Panellings/Table Tops etc as instructed. The laquering shall be done on 12mm Thick EXTRA CLEAR Float Glass with best quality Imported Laquer and Hardner as per the manufacturer's specifications so as to achieve even, scratch free finish of colour as specified or as approved. The Glass Shall be edge polished on all sides before laquering and shall be handled carefully to avoid scratches/chips/jagged edges etc. and shall be fitted in place using a layer of NON-TOXIC SILICON adhesive and/or SS Stud head Caps. The rate shall be inclusive of all procurement, labour for laquering, labour for fixing, transportation, edge polishing etc. complete to the satisfaction of the Bank/SBIIMS. | | | | |
| 9 | Hardwares : | | | | |
| 9.1 | Providing and fixing Doorset / Sterling / Ozone or as approved heavy duty floor spring , upper patch, bottom patch, etc. complete. | 1 | Nos. | 0 | 0 |
| 9.2 | Providing and fixing lock keeper plate, euro profile cylinder EPC), etc. complete. | 0 | Nos. | 0 | 0 |
| 9.3 | Providing and fixing night latch with three keys at doors, etc. | 2 | Nos. | 0 | 0 |
| 9.4 | Providing and fixing two lever mortise lock of Godrej Make with brass handle | 2 | Nos. | 0 | 0 |
| 9.5 | Providing and fixing Door closers on doors of make Everite/Ozone/ Hardwyn/ Dorma or equivalent upon approval including all packing, levelling, etc. as required. | 2 | Nos. | 0 | 0 |
| 9.6 | Providing and fixing floor mounting 6 lever lock for main entrance door | 1 | Nos. | 0 | 0 |
| 9.7 | Providing and fixing SS AL-drop 300 mm long along with through nut & bolt fittings, etc. complete. | 0 | Nos. | 0 | 0 |
| 10 | Misc. Works : | | | | |
| 10.2 | Pin-up boards : | 2.00 | Sqm | 0 | 0 |
| | Providing and fixing Pin-up boards of 12mm thk. pin board covered with plain matt/cotton fabric as per approval, the fabric stuck with rubber based adhesive to the board as instructed. Cost shall include all tw lippings, base preparation required and joints on fabric shall not be approved. | | | | |
| 10.2.1 | NOTICE BOARD : | 2 | Nos. | 0 | 0 |

| | | | | | |
|-----------|--|-------|------|---|----------|
| | Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x 1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete. | | | | |
| 10.3 | Rollar Blinds : | 10.00 | Sqm | 0 | 0 |
| | Providing & installing Rollar Blinds of Trac / Vista or equivalent, 100 mm wide, in two colours, of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. | | | | |
| 10.7 | Numbering of Desks : | 0 | Nos. | 0 | 0 |
| | Providing & fixing in position at all levels, Numerical Numbers on vinyl stickers/ 3M or equivalent - front/ back side pasting on glass/ lamination, with numerals on it from 1 to 20 in circular form, of diameter 100 mm or as directed. The colorful decals (SBI Blue & white) shall stick on the inside of the glass. The adhesive is on the front of the label. Graphics, however, are read from the outside. For pasting on laminate surface, it shall be normal sticking sticker. | | | | |
| 10.8 | Drop & Complaint Box : | 0 | Nos. | 0 | 0 |
| | Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete. | | | | |
| 10.9 | Wall Paper : | 10 | Sqm | 0 | 0 |
| | Wall paper -Wallcoverings to be made from vinyl (PVF), coated with plastic; to be colourfast and washable with dust repellent property. Application of wall paper as per approved sample. Rate to include surface preparation abd application as per manufacturers standards. (Basic Rate Rs.90/- sqft) | | | | |
| 10.1 | Providing & fixing of green channel box on the column made out of 18 mm thick commercial block board and green coloured 1mm thick laminate as per design & as directed by the Engineer. | 0 | Nos. | 0 | 0 |
| 10.11 | Providing and fixing self-adhesive Sparkle Series of 3M make designer frosted film/and / or One-way Vision Film/ flex paintings to 12 mm glass partitions / doors as per approved pattern and design complete as directed at site. | 0 | Sqm | 0 | 0 |
| 11 | Sub Total : Part B (Furnishing Works) | | | | 0 |
| C | Part C : Civil Renovation Works : | | | | |
| 12 | Painting Works : | | | | |

| | | | | | |
|----------|--|------|-----|---|---|
| 12.1 | Rates to include cost of all materials, labour, curing, tools & machinery, transportation, scaffolding, ladders and all incidental and operational charges, at all heights, etc., complete and as directed by SBIIMS. All glasses, surfaces to be cleaned of the paint marks/drops due to work/splashes. | | | | |
| 12.2 | Plastic Emulsion Paint : | 50 | Sqm | 0 | 0 |
| | Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/ distem-per/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris. | | | | |
| 12.3 | Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, Walls : | 60 | Sqm | 0 | 0 |
| | Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls, etc. Removing, scrapping & cleaning the existing enamel paint on doors, windows, grills, metallic surfaces, etc. paint by scrapping, sand papering and scrubbing. Then first coat of primer to be applied. After this necessary leveling shall be done with putty & second primer coat shall be applied. | | | | |
| 12.5 | OIL BOND DISTEMPER : | 0 | Sqm | 0 | 0 |
| | Two ore more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials. etc. | | | | |
| 24.4 | Dual Tone Texturised Paint : | 6.00 | Sqm | 0 | 0 |
| | Providing & applying approved make dual tone texturised paint (Royale Play or equivalent) in two or more shades, in metallic, stucco, etc. material and of design, decorative paint effects as instructed on the new surface or after removing existing finishes, plaster & apply texturised paint as per the Manufacture's Specifi-cation including leveling the existing surface with plaster of paris, cracks filled with Chemicals/M-Seal material, etc. and including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the SBIIMS, etc. complete as per the site. | | | | |
| 13 | Sub Total : Part C (Civil renovation Works) | | | | 0 |
| | | | | | |
| D | Part D : BOUGHT OUT ITEMS: | | | | |
| 14 | Sofa set : (Leatherite Finish) | | | | |

| | | | | | |
|---------------|--|--------------------------------------|------|---|----------|
| | Providing, making and fixing in position sofa set with/without side arms made for best quality badam/hillock wood frame-work & legs fitted with rubber nylon shoes fixing with 8mm thick commercial ply back side. Providing 150 mm thick high density (min40) foam rubber of approved quality to seat of zigzag spring of approved quality over 12 mm thick phenol form aldehyde bonded approved quality commercial ply and 50 mm thick foam rubber of approved quality, density mini. 32 to back covered with upholstery of latherite, rate not less than Rs. 450/- per mt. finish of approved quality materials including polish finish complete of approved quality and make selected by the Engineer in Incharge. Rate inclusive of cost of material, transportation, loading/ unloading, labour tools & tackles up to any lead and lift etc. | 3 | Nos. | 0 | 0 |
| | | | | | |
| 15 | High back, revolving executive chair with cushioned seat & back & molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej Bravo//Featherite Click/Featherlite Astro/Featherlite Contact Project/ Wipro/ Methodex make or equivalent as approved for BM. | 1 | Nos. | 0 | 0 |
| | | | | | |
| 16 | Medium back, revolving executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej Bravo//Featherite Click/Featherlite Astro /Featherlite Contact Project/ Wipro/ Methodex make or equivalent as approved for officers viz. Sales Manager, Service Manager, Discussion room, SWO counters, Visitor Chairs for BM cabin, etc. | 6 | Nos. | 0 | 0 |
| | | | | | |
| 17 | Medium back fixed type chairs with cushioned seat and back & molded PVC hand rest Godrej, S-frame type, as per quality & design approved, of makes viz. Godrej Bravo//Featherite Clicl/Featherlite Astro/Featherlite Contact Project/ Wipro/ Methodex make or equivalent as approved for visitors, lunch room, etc. | 5 | Nos. | 0 | 0 |
| | | | | | |
| 18 | PVC lightweight chairs with chrome plated legs of colour and shade as per approval of Nilkamal, Supreme, Blowplast, Featherlite or equivalent make (similar to Nilkamal Novella 07 Blue Chair). | 2 | Nos. | 0 | 0 |
| | | | | | |
| 19 | Sub Total : Part D (Bought Out Items) | | | | 0 |
| | | | | | |
| | Sub Total : Part A (Interior Works) | | | | 0.00 |
| | Sub Total : Part B (Furnishing Works) | | | | 0.00 |
| | Sub Total : Part C (Civil renovation Works) | | | | 0.00 |
| | Sub Total : Part D (Bought Out Items) | | | | 0.00 |
| | Total : Part (A + B + C + D) = | | | | 0 |
| | | | | | |
| RUPEES | | | | | |
| | | | | | |
| | | Seal & Sign of Contractor | | | |