

**PRICE BID : INTERIOR DECORATION AND FURNISHING WORK OF
DANAPUR BRANCH(FIRST FLOOR)**

S.NO.	ITEM	PARTICULARS	QTY.	UNIT	RATE	AMOUNT
1	HYDRAULIC DOOR CLOSER	Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn, Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	3	NO.		
2	FULL HEIGHT PARTITIONS PARTLY PANELED AND PARTLLY GLAZED/SOLID PARTITION	Providing and fixing double skin partly paneled & partly glazed full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gamhar, Malaysian Sal wood / hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to false ceiling (if provided) fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick BWP grade plywood/ Exterior Grade MDF board of Green/Century or equivalent and 1.0 mm thick (Greenlam / century or equivalent) blue / white high gloss laminate with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 5.50 mm clear float toughen glass of approved make as above at item-1 of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame and with teak wood beading as per detail design, which is to be of 1st quality teakwood (all visible wood to be of 1st quality teakwood) and shall be polished and protected with melamine polish. The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fas-teners so as to form a stable system / partition all complete work with provision for wring to be done by other agencies all complete work as per specification	45.66	SQ. MTR.		
3	WORK STATIONS	Dismantling of existing work station tables etc and re-fixing the same as per the drawing including repairing with 6 mm thick ply board of Century / Green or equivalent make & 1mm thick high glosive blue / white laminate of Century/Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	4	No.		
4	PARTITION REPAIR	Repairing of full height partly paneled partly glazed / non-glazed / low height partitions etc as per the direction including finishing with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks, resizing of glass etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I	27.6	Sqm		

5	COLUMN PANELLING REPAIR	Repairing of wall / column paneling etc as per the direction , including finishing with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	6.69	Sqm		
6	WORK STATIONS / TABLES	<p>(a). Making and erecting Desk-top with provision of wore manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWP grade block board of Green / Century /Mayur or equivalent/ Exterior Grade MDF board of Green/Century or equivalent top laminated with 1.0 mm blue / white high gloss laminate of Green/ Marino / Century or equivalent. All edges shall be covered with teak wood lapping and front-edge shall be covered with half round molding. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. All wooden surfaces shall be well polished with melamine/sprit polish.</p> <p>(b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWP grade ply of Green/ Century or equivalent / Exterior Grade MDF board of Green/Century or equivalent front shall be clad with 1.0 mm thick high gloss blue /white laminate of Green lam / Century or equivalent side edges of drawers and cupboard shall molded in round shape with Gamhar wood. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per approved ma-terials Colour Laminate and specifications .</p> <p>(c). Providing and fixing key board tray (as per design and specification at 1- above) try and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers.</p>				
	I	'L' shaped 2400 mm x 900 mm x 750 mm (For R.M.)	0	NO.		
	II	4800 mm x 900 mm x 750 mm (For Meeting Hall)	0	NO.		
	III	L' shaped 1800 mm x 900 mm x 750 mm(For C.M)	1	NO.		
	IV	'L' shaped 1500 mm x 1650 mm x 750 mm	0	NO.		
	V	'L' shaped 1500 mm x 1500 mm x 750 mm	0	NO.		
		All complete work as per drawing, design. Speci-fication and direction of Engineer-in-charge /Bank.				
7	FOOT REST	Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings top clad with rubber mat. All inner portions shall have a coat of mat finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. Materials shall be above at item	5	NO.		

8	CORIAN LAMINATE	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make of Du-Point/Mairino on table top, table front, & designer beads SBI fa-cia, back black color & rounding of edges to complete in all respect, as per site condition with rounding of edges etc to complete job. (C.M's table table tops).	5.5	SQ. MTR.		
9	LOW TYPE STORAGE CABINET	Making and fixing low type storage cabinet with drawer and cupboard with shelf as per the drawing / design all made of 19 mm thick BWP block board of Green/Century /Mayur or equivalent/ Exterior Grade MDF board of Green/Century or equivalent top and front laminated with 1.0 mm thick blue / white high glosive laminate of Green/Marino /century or equivalent top edges shall have Gamhar wood moulding. Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per approved materials Colour laminate and specifications .	6.5	SQ. MTR.		
10	PANELING	Providing and fixing wall & Column Paneling as per drawing & design : The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically. The framework is to be fixed by means of Alumin-ium angles of appropriate size for proper fixity. The framework is to be covered by 6 mm thick BWP plywood /Exterior Grade MDF board of Green/Century or equivalent on exposed side with suitable fix-tures. The surface is to be finished with 1 mm thick high gloss laminate of approved shade & make. Provisions are to be made for fixing LED strips. The work is to include all necessary materials, ac-cessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed elevation area is to be measured for fin-ished				
	B	With 12 mm thick MDF board fixed on frame fin-ishing paneling surface with high gloss PU paint/1 mm thick high gloss laminate-In the wall.	57	SQ. MTR.		
11	SYNTHETIC ENAMEL PAINTING	Providing two or more coats painting with finest 1st quality synthetic enamel paint of Asian paints / ICI Dulux/ Berger Nerolac/ equivalent approved brand of specified colour to give an even after proper scrapping, sand-papering, etc. as per direc-tion of bank.	92.5	SQ. MTR.		
12	WALL PUTTY	Providing and applying wall putty of 2 mm aver-age thickness over plastered & white washed walls & ceiling to prepare the surface even and smooth compete as per direction of Bank.	155	SQ. MTR.		
13	PLASTIC EMULSION PAINT	Providing two or more coats of Plastic emulsion paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to	265	SQ. MTR.		
RS.			TOTAL			

NOTE:-

* ABOVE PRICE IS EXCLUDING GST.

* GST PAID EXTRA BY THE BANK AS PER RULE.

