

PRICE BID : INTERIOR&FURNISHING WORK OF BRAHMPUR BRANCH

BRANCH : BRAHMPUR Br.

UNDER RBO : RBO, ARA

Sl. No	Particulars of Items	Unit	Quantity	Rate (Rs.)	Amount
1.	<u>12 MM THICK TOUGHENED GLASS DOOR ETC</u> Providing and fixing / fitting mm thick toughened glass of approved make with all necessary hardware accessories etc including cost of labours and materials etc as per Corporate Centre, Mumbai approved materials Colour etc and specifications and the direction of E / I.	Sq.m	12.26		
2.	Providing D-Tel depository cabinet of Godrej make in counters of size-691mm x 460mm x 460mm of weight 33.00 kg of automatic locking including of cost of labors & materials etc. to complete job as per specification & direction of E/I.	Nos.	5.00		
3.	Supplying & fixing/fitting of corian laminate of 6mm thickness of approved make of Du-Point only on table top, table front, & designer beads SBI fascia, back black color & rounding of edges to complete in all respect, as per site condition and instruction with rounding of edges etc to complete job.	Sq.m	20.79		
4.	Providing and fixing ACP Cover for Rolling Shutter Box : The cover is to be set with an inner wooden framework of 50 mm x 50 mm well seasoned Malaysian sal wood sections, placed at suitable spacings not exceeding 600 mm c/c. The framework shall be covered by 12 mm thick BWR plywood. The work is to be finished with 3 mm thick exterior/interior grade Aluminium Composite Panel(ACP) cladding of approved shade & make with grooves duly treated with silicon sealant. The work is to include all necessary materials, accessories, labour, tools & tackles. Executed covered area shall be measured for finished work.	Sqm	4.07		

5.	S/F/F Godrej mortise locks/ Night latches including cost of labor & materials etc. to complete job.	Nos.	7.00		
6.	<u>ROLLER BLIND :</u> Providing and fixing roller blinds of (Mac/annums) of approved shade and pattern having handrail made of high strength aluminium alloyed wall thickness of 1.2mm thk. Handrail to have 25mm decorative insert. Control unit shall be of derlin. The runner also to be a derlin with anti friction adhesive. Spacers should be made of stainless steel. fabric should be polyester viscosted/ polyester yarn having protective coating with chemicals for stain resistance and soil repelancy. The rates shall include necessary scotch guard treatment on both sides. The overlapping should be uniform and adequate. Necessary operative arrangements , frames to be provided. The work to be completed	Sq.m	18.58		
7.	Dismantling of existing work station tables etc and re-fixing the same as per the drawing including repairing with 6 mm thick ply board of Century / Green or equivalent make & 1mm thick high glossive blue / white laminate of Century/Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Nos.	3.0		
8.	<u>SYNTHETIC ENAMEL PAINTING :</u> Providing two or more coats painting with finest 1st quality synthetic enamel paint of Asian paints / ICI Dulux/ Berger Nerolac/ equivalent approved brand of specified colour to give an even after proper scrapping, sand-papering, etc. as per direction of bank.	Sq.m	110.00		
9.	Dismantling of SWO counters etc and re-fixing the same as per the direction , including repairing with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glossive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	No's.	6.00		

10.	Dismantling of low storage cabinets of different sizes etc and re-fixing the same as per the direction , including repairing with 6 mm thick ply board of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks & 02 or more coats of paintings & beadings etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I	No's.	15.00		
11.	Repairing of full height partly paneled partly glazed / non-glazed / low height partitions etc as per the direction , including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks, resizing of glass etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Sq.m	105.00		
12.	Repairing of wall / column paneling etc as per the direction of R.M / CM (CS & CM), including with 6 mm thick ply board both sides of Century/Green or equivalent make & 1mm thick high glosive blue / white laminate of Century / Greenlam or equivalent make with change of Godrej multipurpose locks etc. wherever required & disposal of un serviceable materials to complete job as per direction of E/I.	Sq.m	25.76		
13.	<p>Providing and fixing wall & Column Paneling as per drawing & design :</p> <p>The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically.</p> <p>The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity.</p> <p>The framework is to be covered by 9 mm thick BWP plywood on exposed side with suitable fixtures.</p> <p>The surface is to be finished with 1 mm thick high gloss laminate of approved shade & make.</p> <p>Provisions are to be made for fixing LED strips.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles and also allow</p>				

	provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed elevation area is to be measured for finished				
(a)	Interior Columns in Banking Hall	Sqm	Nil		
(b)	With 12 mm thick MDF board fixed on frame finishing paneling surface with high gloss PU paint/1 mm thick high gloss laminate-In the wall back side of SWO Counters.	Sqm	108.90		
14	Providing and fixing of Gypsum tile false ceiling tile of size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Prelude XL Hot dipped galva-nized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independent-ly. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-ordinating with all trades and making any cut-outs required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	Sqm	236.52		

15.	<p>Providing and fixing in position Seamless Gypsum Board Plain False Ceiling in one or more levels as directed including vertical surfaces between different levels.</p> <p>The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards of approved make, duly finished with recommended filters, tapes, etc. to have a seamless flush look. The ceiling system is to be fixed to a concealed GI framework(Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways. The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners.</p> <p>The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc.</p> <p>The work includes applying two coats of approved putty & primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion paint on the surface.</p> <p>Provisions for openable type lids for facilitating arrangements for rolling shutters are to be made as required.</p> <p>Lids shall be made out of 9 mm thick BWR plywood duly painted to match the ceiling surface and provided with 2 No. 75 mm SS butt hinges & 1 No. 100 mm SS tower bolt along the surface. The work is to be completed with all materials, accessories. Labour, tools & tackles and in strict conformity with manufacturers specifications & recommendations.</p> <p>Rate is to include the cost of making openings for ceiling mounted electrical & air-conditioning accessories.</p> <p>All materials should be approved by Bank. Plan area is to be measured for finished wor</p>	Sqm	162.55		
16.	<p>Providing, laying and fixing vitrified flooring / skirting in specified area with vitrified tiles approx size 600mm x 600 mm X 8mm in light colours specified by the Bank as per approved shade and colour of standard make i.e. Naveen/ Johnson/Nitco/ Euro(Premium quality) only, laid over 20 mm thick cement mortar 1:4 or with the help of Pedilite or equivalent make pasting chemicals after required chipping and leveling the surface by 1:4 cement sand mortar if required all complete including cost of materials, labours etc.</p>	SQM	286.53		
17	<p>Providing and fixing double skin partly paneled & partly glazed full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gamhar, Malaysian Sal wood /</p>	Sqm	12.50		

	hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to false ceiling (if provided) fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick BWP grade plywood/ Exterior Grade MDF board of Green/Century or equivalent and 1.0 mm thick (Greenlam / century or equivalent) blue / white high gloss laminate with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 5.50 mm clear float toughen glass of approved make as above at item-1 of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame and with teak wood beading as per detail design, which is to be of 1st quality teakwood (all visible wood to be of 1st quality teakwood) and shall be polished and protected with melamine polish. The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fas-teners so as to form a stable system / partition all complete work with provision for wring to be done by other agencies all complete work as per specification				
18.	Dismantling of tile work in floor laid in cement mortar including disposing off the debries outside the premises in suitable dumping yard	Sqm	286.53		
	TOTAL				
	PRICES SHOULD BE QUOTED EXCLUSIVE OF GST.				

Place: -

Date:-