

**RENOVATION OF SERCHHIP BRANCH  
BOQ FOR AIR CONDITIONING INSTALLATION WORK**



Sl. No.	Description	Unit	Qty.	Rate (Rs.) (Exclusive of of	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin/LG/Godrej	No.	1		
3	"Supply of 2 TR Cassette Type Inverter AC, 3 STAR with Copper Condensor Coil and refrigerant (R32 or R 410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, Voltas/Blue Star/Carrier/Daikin /LG"	No.	6		
5	Installation charges of the 1.0/1.5 TR Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	1		
6	Installation charges of the 1.5/2.0 TR Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	6		
7	For 1.5/2.0 TR Copper Cassette type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	90		
8	For 1.0 TR/1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	10		
9	Supply and Installation of 4 KVA Stabilizer for 1.0 TR/1.5TR Split Acs	Nos.	1		
10	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	6		
11	Comprehensive Annual Maintenance Contract of above mentioned 1 No. of 1.0/1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	1		

12	Comprehensive Annual Maintenance Contract of above mentioned 6 Nos. of 1.5/2.0 TR Copper Cassette type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	1		
13	Supply and Installation of outdoor unit stand	Nos.	7		
<b>Grand Total</b>					

GST on work contract will be extra as applicable.