

**PRICE BID**

**Creation of Seating arrangement for staff at 5th Floor B- wing GITC Belapur for civil works**

Sr. No	Description	Qty	Unit	Rate	Amount
1	<b>Low height partition:</b> Providing and fixing low height partition of 3' 6" height having alluminium frame of 50X50mm Jindal or equivalent both ways at 2ft c/c covered with 6mm thick commercial ply confirming IS:303 MR grade ply of ecotech, Archid, Green or equivalent make finished with 1mm thick laminate including edges of approved colour and make on both sides rates are inclusive of finished with 3" TW bidding patti & polished as per instructions Complete the work as per site condition and instruction of Bank	60.00	RFT		
2	Providing and fixing in position running counter 600 mm Wide to be made out of 19 mm thick ply (confirming to IS 303) the vertical support at every 2'11" All the exposed surfaces of the counter shall have approved make/colour 1mm laminate with matching color and TW half round moulding will be finished with zink polish matching/approved colour as per existing laminate colour provided at so including one pedestal, the design and size of pedestal will be as per the site conditions if required as per site conditions the instruction of the Banks Engineer complete the work.rates are inclusive of necessary hardware, Keybord etc to complete the work.	35.00	RFT		
3	Providing and fixing in position running counter 600 mm Wide to be made out of 19 mm thick ply (confirming to IS 303) the vertical support at every 4'3" All the exposed surfaces of the counter shall have approved make/colour 1mm laminate with matching color and TW half round moulding will be finished with zink polish matching/approved colour as per existing laminate colour provided at so including one pedestal, the design and size of pedestal will be as per the site conditions if required as per site conditions the instruction of the Banks Engineer complete the work.rates are inclusive of necessary hardware, Keybord etc to complete the work.	170.00	RFT		
4	Providing and fixing toughened clear 8 mm thick glass partition of size 1'6" x 2' on running counters at specified/approved locations with 1.5" round moulding at corners, rates are inclusive all necessary hardware required for fixing/ embedding the glass in half partitions and fixed with " D " brackets/SS fittings etc. complete the work as per site conditions and instructions of the Bank.	22.00	Nos		
5	Providing and fixing double charged vitrified tiles of Kajaria, Johnson, etc. make (size 600mm x 600mm) flooring in cement sand mortar (1:4) bedding including removal of existing flooring, debris etc. from site as per directions of the Bank	100.00	Sft		
6	Providing & applying Birla putti	200.00	sft		
7	Providing & applying plastic paint	600.00	sft		
8	Carefully removing and shifting the existing storages, workstations etc. and storign the servicable material to Banks specified location	1	Lums um		
9	Necessary repairs and finishing to the existing panel (Panelling to the column up to 3'6" ht x 10') if required match the laminate with the surrounding area)	10	Nos		
Total					
18% GST Extra					