

PRICE BID FOR INTERIOR RENOVATION WORKS AT SBI RACPC - II, ERNAKULAM (AS PER UNIFORM LAYOUT) AND ENTRANCE LOBBY IN GROUND FLOOR OF BANK'S OWN BUILDING AT PANAMPILLY NAGAR, UNDER AO ERNAKULAM.					
Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
1	<p>LOW HEIGHT PARTITION FOR SINGLE WINDOW SYSTEM & COUNTERS :Providing and fixing of Low height partitions for Single window system of 1350 mm (or 1200 mm as directed) height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thickn of approved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided. (Partitions shall be of straight/ curved shape as shown in the drawing).</p>	146	Sq.M		
2	<p>Custom Made Full Height Solid Partition:Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beddings. Measurement for the partition area shall be considered from floor level to false ceiling level only. (Partitions shall be of straight/ curved shape as shown in the drawing)</p>	112	Sq.M		

3	Full height partly solid and partly Glazed partition :- Providing and fixing in position partly panelled and partly glazed partition as per specification in item no.(8) above but with 8 mm thick float glass with etching between 900 mm and 2100 mm level between the solid partition as per size required at site fixed with necessary SS D brackets. The edges of partition is to be finished with 1 mm thick laminate. Measurement for the partition area shall be consider from the floor level to false ceiling level only. (Partitions shall be of straight/ curved shape as shown in the drawing)	26	Sq.M		
4	Custom Made Full Height Solid Partition (Ply with laminate on one side & Cement board on other side) : Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on one side of the frame work from the floor level to false ceiling level finished with 1 mm laminate including necessary grooves and 10 mm thick Cement board on the other side of the frame work from the floor level to false ceiling level finished with two coats of plastic emulsion paint of approved make and shade over a coat of putty shall be provided. Measurement for the partition area shall be considered from floor level to false ceiling level only.	33	Sq.M		
5	Custom Made Full Height Cement Board Partition: Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 10 mm thick Cement board on the other side of the frame work from the floor level to false ceiling level finished with two coats of plastic emulsion paint of approved make and shade over a coat of putty and primer shall be provided. Measurement for the partition area shall be considered from floor level to false ceiling level only.	8	Sq.M		

6	Custom Made Full Height Solid Partition with Glass panelling: Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on one side including necessary grooves and steam beach beadings and 6mm thick lacquered blue colour glass (Planilaque Evolution) on the other side with necessary glass adhesive on the rear side of the glass and fixing in position. Measurement for the partition area shall be considered from floor level to false ceiling level only. (Partitions shall be of straight/ curved shape as shown in the drawing)	39	Sq.M		
7	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.	4	Sq.M		
8	Partly solid and partly glazed Teak wood Door with frame: Providing and fixing door shutter using 35mm teak wood planks with 12mm thick toughened glass of size as shown in the drawing. Necessary pivot, heavy duty Floor springs ,1 pair of stainless steel brush finished handle 60 cm (90 cm to the lobby door - 2 nos) to each shutter, lock of approved make etc to be fixed to the door. 5cm wide mirror strips are to be fixed on the wooden surface of the door as shown in the drawing . A teak wood frame of size 150x35mm is also to be provided for fixing the Door.	13	Sq.M		

9	Automatic Sliding Glass Door- size 300x240cm (sliding door 180x227cm and sliding length 380x227 cm): Supply and fixing of Automatic sliding glass door consisting of Dorma / GEZE / approved equivalent make automatic system for sliding the glass door, 2 Nos of 12 mm thick toughened glass for sliding door panels and 2 nos of 12 mm thick toughened glasses for fixed panels, all required patch fittings etc complete. Activators- Radar system 01 Nos Eagle 6 / EW Series on outside and 1 pair of infra red safety sensors to be mounted on either side of the opening, with 24 GHz, with Electro Magnetic Locking System, and 5 Position Program Switch .The system shall have Stabilised power supply of 230V+ 5%, 50Hz - AC. The rate includes cost of all materials, labour, transportation etc complete.	1	Nos		
10	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	10	Sq.M		
11	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma or equivalent make at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	114	Sq.M		

12	Gypsum Board False Ceiling Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete.	480	Sq.M		
13	GRID Ceiling:- with fissured mineral fibre board tile 600 x 600 x 12 mm thick (amstrong or approved equivalent) over the suspended grid system with hot dipped precoated GI angle sections 24 x 24 x 0.9 mm size on walls / partitions T Sections 24 x 38x 0.7 mm size in bottom directions to form 600 x 600 grid. Neceswsary cutouts for lighting fixtures, air conditioner, air conditionin grills etc to be provided.	10	Sq.M		
14	GRID Ceiling:- with accoustic mineral fibre board tile 600 x 600 x 12 mm thick (amstrong or approved equivalent) over the suspended grid system with hot dipped precoated GI angle sections 24 x 24 x 0.9 mm size on walls / partitions T Sections 24 x 38x 0.7 mm size in bottom directions to form 600 x 600 grid. Neceswsary cutouts for lighting fixtures, air conditioner, air conditionin grills etc to be provided.	10	Sq.M		
15	Multilevel (5 level) FALSE CEILING DESIGN WORK IN LOBBY GYPSUM BOARD: Provide and fix false ceiling design work in lobby area using 12.5 mm thick gypsum board of approved make for rafters with frame work, sufficient supporting systems in line and level. all fittings and fixtures etc complete including providing cutouts for light fittings,etc complete as per specifications. Finishing the surface with 2 coat putty , 2coat plastic emulsion paint of approved colour over primer, as directed by the Engineer-in-charge. Provision for fixing big sized chandelior (heavy duty hooks or the like) shall also be provided. Measurements shall be taken for the flat area only.	50	Sq.M		

16	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings/ handles/ locks etc. complete. Edges should be neatly finished using pvc edge band	10	Sq.M		
17	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	10	Sq.M		
18	Repairing of false ceiling such as closing of existing cuttings of light fittings/ ac with gypsum and finishing with 2 coats of paint over a coat of putty and providing cuttings for light fittings/ ac wherever required.				
a	cutting for light/ ac fitting	10	Nos.		
b	closing of existing cuttings of light/ ac fittings and finishing with 2 coats of paint over a coat of putty	10	Sq.M		
19	AGM Table Providing and fixing AGM table of size 2300 x 900 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip. 12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete. A superior grade writing board with transparent glass fibre having level adjusters and paper holder clips etc complete shall also be provided for placing on the table top.	1	No.		
20	Side Tables For AGM Providing and fixing side unit for AGM table to detail as per drg. of size 1200mm x 600 mm made of 18 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc., complete. 12 mm glass with polished edges to be provided for the table top. All external and internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.		

21	Providing and fixing Officer's table of size 2050 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above . 12 mm thick glass with polished edges to be provided on table top.	1	No.		
22	Providing and fixing Officer's table of size 1800 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above . 12 mm thick glass with polished edges to be provided on table top.	4	No.		
23	Providing and fixing Officer's table of size 1700 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above . 12 mm thick glass with polished edges to be provided on table top.	1	No.		
24	Providing and fixing Officer's table of size 1650 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above . 12 mm thick glass with polished edges to be provided on table top.	6	No.		
25	Providing and fixing Officer's table of size 1600 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above . 12 mm thick glass with polished edges to be provided on table top.	2	No.		
26	Providing and fixing Officer's table of size 1550 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above . 12 mm thick glass with polished edges to be provided on table top.	1	No.		
27	Providing and fixing Officer's table of size 1500 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above, but without writing table . 12 mm thick glass with polished edges to be provided on table top.	14	No.		
28	Providing and fixing Officer's table of size 1200 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above, but without writing table and CPU stand . 12 mm thick glass with polished edges to be provided on table top.	1	No.		
29	Providing and fixing Officer's table of size 1050 x 700 X 750 mm high to detail as shown in drg. as per specification in item no.19 above, but without writing table and CPU stand . 12 mm thick glass with polished edges to be provided on table top.	27	No.		
30	Providing and fixing Grahak Mitra table of size 1800 (mean length if curved) x 600 X 750 mm high to detail as shown in drg. As per Bank's standard design with raised writing board and Bank's emblem on front side (with provision for Concealed LED strip lighting, glass etc) and other specifications as per specification in item no.19 above, but without writing table. 12 mm thick glass with polished edges to be provided on table top.	2	No		

31	Lobby Table 4500x750x750mm: The size of Table is 426x80x75cm. The table is made out of 17 mm thick exterior grade both side prelaminated MDF board with exposed top edges lipped with 2mm thick PVC edge band . 6 mm thick white corian top is to be provided on table top and the edges to be rounded and polished. The shape of the corian top is shown in the drawing . For the curved shape of corian top 6 mm flexy plywood is to be used. The exposed front portion of the table is made of Aqua blue shade of saint gobain lacquered glass as per the drawing. Necessary grooves are to be provided. 2 sets of Drawers, 2 Nos of keyboard tray are made of 17 mm thick exterior grade both side prelaminated MDF board with exposed top edges lipped with 2mm thick PVC edge band as per the drawing. . Necessary fittings such as steel slides, lock (Godrej/equivalent) , handles etc. of approved make are to be provided. One Drawer set contains three numbers of drawers. Foot rest (2 nos) are made of 17 mm thick exterior grade both side prelaminated MDF board with PVC edge band knock down type bottom bush etc.30cm wide and 15cm height at one end and the other end is zero 60cm length fixed on the bottom side of the table etc. complete. Provision for cable manager is to be provided.2 Nos of good quality ready made adjustable metallic CPU Trolley with casters are also to be provided.	1	No		
32	Providing and fixing Rectangular shaped Discussion Table of size 125cm X 90 cm high with curved edges as shown in the drawing comprising of table top out of 19mm thick Plywood with 1mm thick laminate of approved color and brand with side edges with 3mm thick PVC edge band. The table shall have 2 sets of 3 curved Legs joined together with a rectangular centre pillar, both connected with intermediate vertical support along the longitudinal direction, all made up with plywood and laminate as mentioned above. Table shall have cable managers and slot for keeping Mobile/ tablet, pens, cards etc. Legs shall have good quality antislip rubber bushes.	3	Nos.		
33	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 120 x 45 cm as per specification in item no.20 above	10	No.		
34	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 100 x 45 cm as per specification in item no.20 above	1	No.		
35	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 90 x 45 cm as per specification in item no.20 above	18	Nos.		

36	Storage :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	35	Sq.M		
37	Storage :Providing and fixing full height storage to detail as shown in the drg. Size about 450mm wide, 240mm high with openable shutters in front approx 450 mm wide & 1200 mm high fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area. The unit shall be firmly fixed to the walls/ partitions to prevent overturning.	29	Sq.M		
38	Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate over Aluminium sections of size 50 x 25 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres (and at all vertical corners/ edges) and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position..	31	Sq.M		
39	Providing and fixing cladding around the columns to detail as per drawing comprising 18mm thick Plywood with necessary stiffner on both ways of required nos and finished with 1 mm thick laminate of approved colour and shade. The surface has also fixed with 8 mm thick Lacqured glass as per drawing. 8mm thick MDF board jally work (CNC cutting) of approved design / pattern finished with white colour high gloss duco paint fixed over the laminate finish surface.	48	Sq M		

40	COLUMN PANELLING IN LOBBY: The frame work of panelling should be of aluminium rectangular section of size 50 mm x 25 mm x 1.5 mm both horizontally and vertically at 60 cm c/c. which is covered with 6 mm thick flexy plywood finished with 6 mm thick white corian sheet (corrugated type pillar design to be made) of approved make as per the drawing. Skirting for a height of 10 cm should be provided. The rates including shuttering charges.	22	Sq M		
41	Glass panelling in lobby/ corridor area: The panelling should be firmly fixed on floor/ counter/ wall and made out of aluminium section of 63.5x38.1x1.2 mm thick of INDAL/JINDAL as internal frame structure placed horizontally & vertically in 60x60 cm interval as shown in the drawing which is covered with 9 mm thick marine grade plywood(IS 303). Then 6mm thick lacquered blue colour glass (Planilaque Evolution) shall be fixed over the plywood with necessary glass adhesive on the rear side of the glass and fixing in position as shown in the drawing.	56	Sq M		
42	Providing and fixing back drop on walls, made of 8mm thick acrylic sheet, over Plywood wall panelling finished with approved laminate. The matter shall be clear vinyl printing reverse type and the digital printing shall be done on rear side of Acrylic sheet. The matter contains "THE BANKER TO EVERY INDIAN" /LOGO/Bank's approved advertisement photo etc. The panel shall be fixed on the wall with suitable method with out bend and undulation complete.	22	Sq M		
43	Providing and Fixing 100 mm wide Vertical Blinds of Vista Levton or approved equivalent make and colour.	36	Sq.M		
44	Providing and Fixing Zebra Type Roller Blinds of Vista Levton or approved equivalent make and colour.	26	Sq.M		
45	Applying & Finishing existing exterior /interior wall area Acmatex brand texture coating (Latterite stone pattern and other design type) work with Asian Exterior primer coat and Asian apex exterior/Inerior emulsion 2 type colour 2 coats each covering and finally acmatex long last clear coat applying	21	Sq.M		
46	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including cleaning the surface.	200	Sq.M		
47	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shadeover a coat of putty including cleaning the surface.	120	Sq.M		
48	Painting the windows/ doors/ ventilators with two coats of synthetic enamel paint of approved make and shade including cleaning the surface.	80	Sq.M		

49	Providing & Fixing display shelf 30x50 cm using 18mm plywood with all exposed faces finished in 1mm laminate & inside faces finished with 6mm mirror/ 8mm glass. Cost includes all material, labour etc complete.	10	Nos		
50	Applying 2 coats of Asian floor guard paint on car porch floor	24	Sq.M		
51	Dismantling existing counters, cabins, partitions, false ceiling and the like and stacking the usable items as directed and disposal of debris away from site. The work includes rearranging the tables/ partitions for temporary functioning of the Branch.	1	LS		
52	Dismantling the existing tiled/ mosaic floor (in case the height of the tiled surface doesn't match with the existing tiled surface or due to some other reasons) as directed by the Engineer- in Charge and disposal of the debris away from site.	100	Sq.M		
53	Block work in CM 1: 6 with CC blocks of 40/30x20x15 cm for superstructure	5	CuM		
54	Plastering including patch plastering with cement mortar 1:5 (1cement 5 sand) 12mm thick, one coat floated hard and travelled smooth for the wall surfaces including all staging works, watering ,curing etc. complete.	40	Sq.M		
55	Reinforced Cement Concrete 1:2:4 for lintel including shuttering, curing, cost of reinforcement etc complete as directed	1	CuM		
56	Plain Cement Concrete 1:3:6 for Bath room flooring (50mm thick) over a layer of brick bat concrete and finishing the top surface ready for tiling work including shuttering, curing etc complete as directed	6	Sq.M		
57	Flooring with Italian marble finish vitrified tile slabs of superior quality and approved colour with 240x120cm or nearest size with basic price of Rs.2350/m2. over the existing floor using tile adhesive at the rate of 5 kg/m2 and fixing the tiles to correct line and levels after cleaning the surface including pointing the joints between the tiles. (The make of vitrified tiles is of Cera/Asian/ RAK bell dark colour and the tile adhesive of carafill/ cerafill/ Pedilite)	67	Sq.M		

58	Flooring with Italian marble finish vitrified tiles of superior quality and approved colour and 9 mm thick or as per manufacture's specifications, 80x80 cm or nearest size with basic price of Rs.1050/m ² and fixing the tiles to correct line and levels (The make of vitrified tiles is of Cera/Asian/ RAK/ bell. The work includes dismantling existing tile flooring and its underlayers including disposal of debris away from site and providing base course with CM 1:4 and jointing/ fixing the tiles with cement slurry and pointing the tiles with joint filler/ cement grout mixed with pigment of matching colour.	236	Sq.M		
59	Flooring:- Providing and fixing 60 x 60 cm vitrified ceramic tiles Johnson 'Marbonite' or equivalent approved for flooring and skirting. Tiles to be fixed to existing flooring using approved quality tile on tile adhesive. Basic price of tile to be taken as Rs.700/m ² ex showroom. (Tiles will be selected by the Bank)	219	Sq.M		
60	Supplying and Fixing granite slabs 18 mm thick with a base price of Rs 2200/m ² over a bed of CM 1:4, 20 mm thick and cement grouted and fixing the slab after removing the existing plaster/ tile etc including rounding and polishing the edge, grouting/ pointing etc complete. For steps/ design work in lobby	11	Sq.M		
61	Supplying and laying 1st quality glazed wall tiles of size 30x45cms of approved colour and brand with tile adhesives, make Kajaria/ RAK/johnson/ bell or equivalent. Height of toilet cladding 2.40 m	33	Sq.m		
62	Supplying and laying 1st quality antiskid floor tiles of size 30x30 cms of approved colour and brand with tile adhesives. Make Kajaria/ RAK/Johnson/ bell or equivalent	6	Sq.m		
63	Providing and fixing approved brand WPC door with frame of size about 90 x 210 cms or as per the existing door opening with all fittings. The work includes dismantling the existing door and frame (if any) and making good the walls etc complete.	16	Sq.M		
64	Providing and fixing steel door of size 90 x210 cms for ups/ Record/ cash rooms with necessary frame work and all other fixtures	5	sq.m		
65	Supplying and fixing wall mounted concealed type (basic price of tank and closet Rs. 20000/No) European W.C.pan parryware or equivalent make with Superior type CP flushing switch, flush valve P-trap, angle cock including all necessary fitting etc complete.	1	Nos.		

66	Providing and Laying of PVC pipes, Solvent pasted type joints inclusive of all necessary specials like bends, tees, offsets, junctions, pan connector etc., laid under floor / under ceiling / on walls with suitable clamps including making bores in masonry and rendering the bores in cement mortar after laying the pipes and specials curing etc., complete.				
a	25 mm PVC pipe (10Kg/ Cm2 grade, pasting type) for water lines	25	RM		
b	20 mm PVC pipe (10Kg/ Cm2 grade, pasting type) for water lines	30	RM		
c	50 mm 4 Kg/ cm2 grade pasting type PVC waste pipes	25	RM		
d	63 mm 4 Kg/ cm2 grade pasting type PVC waste pipes	25	RM		
e	100 mm 4 Kg/ cm2 grade pasting type PVC waste pipes	20	RM		
67	Supplying and fixing 55x40 cm half pedestal wash basin (parryware or equivalent make, basic price of wash basin Rs. 3500/No) rates including cost of pillar cock quarter turn, bottle trap are of cabtree or jaguar , waste coupling, waste pipe, brackets, PVC connection, angle cock with all necessary fittings etc. complete.	1	No		
68	Supplying and fixing urinals with sensor (parryware or equivalent make , basic price of urinal and sensor concealed type flushing valve Rs.12900/No) flushing etc such as flushing valve, C.P tube, sprader angle cock, urinals waste coupling etc complete	2	No		
69	Supply & Installation of Angle cock for water purifier or the like with PVC connection pipe with end nuts including the cost of material, labour etc complete.	4	No		
70	Coat Hook:- Supplying and installation of CP Coat hook (Jaquar) including all accessories required etc complete as per the instruction of Engineer in charge.	2	No		
71	Supplying and fixing CP Brass Two way Bib cock jaquar or crab tree (,basic price of Rs.1370/No)	2	No		
72	Supplying and fixing CP Brass Long Body Bib cock jaquar or crab tree (,basic price of Rs.1150/No)	5	No		
73	Supplying and fixing 24" towel rod (basic price of Rs.1250/No) of approved quality.	2	No		
74	Providing and fixing CP Brass health faucet with connection tube parryware make T9940A1 or equivalent	5	No		
75	Providing and fixing floor trap with SS gratings. Rate includes material cost and labour charges	2	Nos.		
76	Providing and fixing stainless steel sink with drain board of size about 36" x 18" including all connection/ fittings	1	No.		
77	Providing & fixing 750mm x 450 mm x4mm bevelled edge mirror of superior glass mounted on 6mm thick A.C.sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers.	1	No.		

78	Granite counter :- Providing & Fixing granite counter in MS Base framework with 18mm granite fixed to cement board fixed on framework , edge moulding etc complete.	7	RM		
79	Panelling with 3 mm thick aluminium composite panel of approved make and shade cut and bind using router machine and curved using rol over aluminium frame work with 50 x 25 x 1 mm sections as per site condition and instructions of Engineer-in-Charge	17	Sq.M		
80	Providing and fixing wall mounted writing desk of 1200 x 350 mm in 19 mm plywood with 1 mm laminate on all exposed surfaces. Top portion is to be provided with 12 mm clear glass with polished edges, with shelves to keep slip books including frosting of approved design and exposed edges to be fixed with TW beeding with melamine polish. A provision to be made for keeping Banks printed Broachers for public etc. complete.	1	No.		
	TOTAL (Excluding GST)				

GST at applicable rates will be extra