

BOQ FOR INTERIOR FURNITURE AND ALLIED CIVIL WORK AT					
SBI, WOKHA BRANCH NAGALAND					
SI.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
A. HNI CUSTOMER LOUNGE AND ABM CHAMBER					
1	<p>Supplying and installing Tables of Overall size - 1680 mm X 1830 mm x 750 mm including cost of side credenza (1230 mm x 450 mm x 750 mm) made up of 19mm thick block board of approved brand all around and finished with not less than 0.8 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of required size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type.Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy. Rate includes removal of existing furniture.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	Each	1		
2	<p>Fabricating and installing Grahak Mitra table of overall size - 1520mm x 600mm x 750 mm in straight or curved profile made up of 19mm thick block board of approved brand all around and finished with not less than 0.8 mm thick laminate of brand, colour and shade as approved by the Bank. The table cost to include three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide, foot rest & CPU stand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type. All exposed edges to have wooden lipping/bidding of requierd size, stained to match the desk and melamine finished. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on table and necessary cut-out to accommodate wires, edges to be m/c polished, with m.s. powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	Each	1		
3	<p>Low ht storage unit: Providing and fixing storage units of size 450 mm x 750 mm, made up of 19 mm thick block board of approved brand on top & vertical support and finished with not less than 0.8 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/bidding of requierd size, stained to match the desk and melamine finished. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, ,locks , handles etc. of Godrej or approved make. Rate includes removal of existing furniture.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	RM	3		
4	<p>Fabricating and fixing full height semi glazed/solid partition, made of 6 mm ply of approved brand in both side and to be finished with not less than 0.8 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) aluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping/bidding with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Rate shall includes etching of glass as requierd by bank. Rate includes removal of existing furniture.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	40		
5	<p>Providing and fixing Semi glazed/Solid doors shutter made up of 38 mm thick block board of approved brand and quality, finished both side with not less than 0.8 mm thick laminate of approved brand, colour and shade. Middle portion at 900 mm to 2100 mm height shall have 6 mm thick plain float glass (Make Saintgobin/Modigurd) fixed with 10 mm thick teak wood bidding duly polished N C lacquer as per design and direction by bank. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as requierd by bank. Rate includes removal of existing furniture.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply/Gattani/kitply or equivalent. Laminate Make: Greenlam/Centurylam/Merinolam/Archidlam or equivalent.</p>	SQM	6		

6	False ceiling : Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling tiles of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.	SQM	15		
6	Supply of one 3 seater sofa for HNI Customer seating all made with wooden frame, with high density foam of sleepwell/Featherlite, white Lining and Finished with cloth of approved shead of fabric as per the instructions of Bank. (3 seater sofa)	Each	1		
B. E-LOBEY AND ATM WORK					
1	Fabricating and fixing fully glazed partition , with 8 mm thick float glass fixed in between powder coated 50mm x 50mm size aluminium section framework in 600mm x 600mm c/c in horizontal and vertical direction. All exposed edge shall be covered with bidding. Payment will be made for the area upto false ceiling only.	SQM	10		
2	Providing and fixing glazed doors made of 8 mm thick float glass with frost film fixed in between top & bottom rail and side stile framework of powder coated aluminium section of size 125 mm x 50 mm. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring. S.S. finish handle of approved size and make to be provided. All complete including locks and necessary hardwares such as hinge, stopper, tower bolt etc. all exposed edge shall be covered with bidding as directed by EIC.	SQM	4		
3	Providing and fixing low height solid wooden partitions made of 8 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) aluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). All exposed edge shall be covered with teakwood lipping/bidding with polishing complete in all respect. Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Archidlam or equivalent	SQM	3		
4	Providing & fixing in position Aluminium Composite Panel (ACP) Panelling with framing of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.	SQM	50		
5	Shutter Boxing : Providing & fixing in position Aluminium Composite Panel (ACP) with with framing of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. ACP Trap door will be 12 mm ply finished with 3 mm thick ACP. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval.	SQM	20		
6	False ceiling : Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling tiles of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.	SQM	40		

C. CIVIL WORK FOR CONSTRUCTION OF TOILET AND TILING OF STAIRCASE AREA					
1	Brick work in Cement mortar 1:4 (1 cement : 4 coarse sand) with 1st class bricks including racking out joints and curing complete as directed in all levels. Half brick wall (112 mm).	SQM	30		
2	12 mm thick cement plaster in single coat on fair/rough side of brick/concrete walls for interior/exterior plastering in all levels finished even and smooth including curing complete as directed: In cement mortar 1:4 (1 cement : 4 fine sand)	SQM	60		
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	SQM	15		
4	Wash basin: Providing and fixing wash basin with CI bracked, 15 mm CP brass pillar top, waste cupling, 32 mm pvc waste pipe of standard pattern including painting of fittings and brackets, cutting and making the walls wherever required. White vitreous China wash basin 550 X 400 mm with 15 mm thick C.P. Brass pillar top complete in all sense. Hindware	Each	2		
5	Providing and fixing 600x450 mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	Nos	2		
6	Providing and fixing C.P. brass angular stop cock.	Nos	4		
7	Providing and fixing uplasticised PVC connection pipe with brass unions :	Nos	3		
8	Urinal: Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350, including drain pipes, painting of fittings and brackets, cutting and making good the walls and floors etc. wherever required : (make:Cera/Parryware).	Each	1		
9	Water Closet: (European type W.C.) Providing and fixing white vitreous china water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required. W.C. pan with ISI marked white solid plastic seat and lid. (WC make:Cera/Parryware/Hindware).	Each	2		
10	Providing and fixing 2 in 1 Bib cock of approved quality conforming to IS:8931	Nos	2		
11	Supplying, Fitting & fixing of health faucet of Prayag / Jaguare / or equivalent make with one metre long Tube, Hook & all fixtures.	Nos	2		
12	Providing and fixing UPVC/HPVC pipes complete with fittings and clamps, i/c cutting and making good the walls etc. Internal work - Exposed on wall 40 MM dia/ 25 mm dia/ 15 mm dia	RM	25		
13	Providing and fixing PVC (6kg) darinage pipes complete with fittings and clamps, bends etc complete as per direction of engineer in charge. 75 mm dia	RM	15		
14	Ceramic glazed wall tiles : Providing and fixing 300 x 300 mm size 8 mm thick 1st quality ceramic glazed wall tiles conforming to IS: 15622 of approved make, in all colours, shades approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) or 5 to 8 mm thick Balendura / Latticrate adhesive as advised and jointing with matching shade cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete including dismantling of existing tiles if any.. Make: Kajaria / Jhonshon/marbito	SQM	25		
15	Non skid Bathroom floor tiles : Providing and laying Ceramic non skid bathroom floor tiles of size 300 x 300 mm 8 mm thick of approved make and shade, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), or 5 to 8 mm thick Balendura / Latticrate adhesive, as advised including pointing the joints with white cement and matching pigments etc. complete including dismantling of existing tiles if any. Make: Kajaria / Jhonshon/Marbito	SQM	9		
16	Suply and fixing of Ppvc Bathroom door of standard size with frames fo superior quality brandcs.	Nos	2		
17	Applying & Finishing walls with 2 or more coats of emulsion paint of approved colour/shade on surfaces after preparation of base with sand papering, POP/Putty required over a coat of primer of approved brand. Make: Asian paint, Deulux	SQM	200		

18	Applying & Finishing walls with 2 or more coat of enamel paint of required shade on wooden and steel surface. Rate including cost of primer coat. Make: Asian paint, Deulux	SQM	90		
19	Floor tiles for staircase: Providing and laying Ceramic non skid floor tiles of size 300 x 300 mm 8 mm thick of approved make and shade, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), or 5 to 8 mm thick Balendura / Latticrate adhesive, as advised including pointing the joints with white cement and matching pigments etc. complete including dismantling of existing tiles if any. Make: Kajaria / Jhonshon/Marbito	SQM	105		
20	Supplying and fixing of one staircase made of MS section of appropriate size to climb upto 1.5 metere height and width 1.2 metre.	LS	1		
21	Dismantling of existing rcc ramp at enrty of Bank and make it stair.	LS	1		
Total					
NOTE :The estimated cost is exclusive of statutory taxes (GST)on work contract					