

BOQ FOR CIVIL WORK OF					
SBI, GUWAHATI MEDICAL COLLEGE BRANCH, GUWAHATI, ASSAM.					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
1	PROVIDING AND LAYING OF RCC IN 1:1.5:3 FOR CASTING SLAB AND WALLS WITH PROVISION OF REINFORCEMENT AS PER DESIGN (AS TOLD BY ENGINEER-IN - CHARGE). INCLUDING COST OF SHUTTERING, CENTERING AND FINISHING ETC. AND CURING COST. BUT EXCLUDING THE COST OF STEEL.	cum	33		
2	PROVIDING AND FIXING OF STEEL FOR MOULDING OF RCC . TO PREPARE AFTER SHUTTERING EXCLUDING COST OF SHUTTERING. INCLUDING COST OF STRAIGHTENING, CUTTING, BAR BENDING, PLACING IN POSITION, AND BINDING ALL COMPLETE.	KG	6150		
3	BRICKWORK IN RATIO 1:4 (1: CEMENT AND 4: COARSE SAND) INCLUDING MATERIAL COST. WITH FIRST CLASS BRICKS ONLY.	CUM	5.7		
4	PLASTERING IN 1:6 (1: CEMENT AND 6: COARSE SAND) 12MM THICK	SQM	80		
5	PROVIDING AND FIXING EUROPEAN WATER CLOSET ALONG WITH TRAP COMPLETE.	EACH	3		
6	PROVIDING AND FIXING URINAL ALONG WITH TRAP COMPLETE.	EACH	2		
7	PROVIDING AND FIXING WASH BASIN COMPLETE.	EACH	2		
8	Providing and Fixing UPVC/HPVC pipes complete with fittings and clamps cutting and making good the wall etc. Interior and Exposed wall. 25mm/15mm.	RM	40		
9	Supply and Fixing PVC soil pipes (1.8 m each) including current mortar chalk joints laid to the proper level excavating the foundation and filling dressing complete as directed.				
	PVC pipes (63 mm)	RM	20		
	PVC pipes (90 mm)	RM	20		
	PVC pipes (100 mm)	RM	20		
	100 mm Nahani Trap	Each	6		
	Total				
<b>NOTE :The estimated cost is exclusive of statutory taxes (GST)on work contract</b>					