

**PRICE BID - BHAUDAJI BRANCH**

**HIGH SIDE WORKS**

Sr.	DESCRIPTION	UNIT	QTY	Rate	Amount
1	Supply & installation of air conditioners comprising of outdoor unit with ROTARY/SCROLL & Inverter Compressor, isolating valve,copper condenser, evaporator, vibration isolators, thermostatic control, safety cut-outs, cordless remote control. Note: Split Air Conditioners unit should have 5 Star Rating in energy efficiency as per Bureau of Energy Efficiency (BEE) (WHEREVER APPLICABLE) Approved Makes: CARRIER, BLUE STAR, DAIKIN , HITACHI, VOLTAS (The rate should include necessary copper pipe, Electrical cabling & drain pipe upto 3 mtr each )				
a	1.0 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Nos	2		
b	1.5 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Nos	3		
c	2.0 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Nos	1		
d	2 TR Cassatte unit ( BEE rating - minimum three star and above)	Nos	4		
<b>Total High Side Cost (without GST) - A</b>					

**LOW SIDE WORKS**

Sr.	DESCRIPTION	UNIT	QTY	Rate	Amount
1	Installation, Testing & Commissioning of AC's including all required anchor fastner accessories & with One or more times pressure testing with nitrogen at 350 psig, leak testing, rectification, vaccummisation, gas charging, testing & commissioning and balancing of each unit to satisfy that there are no leakages & satisfactory operations,trenching as per requirements.				
a	2.0 TR Cassette	Nos	4		
b	1.0/1.5/2.0 TR Split AC	Nos	6		
2	<b>Supply, Installation &amp; testing &amp; Commsioning of Refrigerent copper pipe with 9 mm thick nitrile insulation including accessories etc (Only single distance will be measured between Indoor &amp; Outdoor Units)</b> <b>The piping shall be well supported at specific intervals with GI supports with insulated PUF saddles and installed on GI cable trays supported from wall / roof with anchor fasteners &amp; C type ms angle etc if required.</b> <b>(Rate 3 mtr pipe which will be free with unit)</b>				
a	1.0 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Rmt	40.00		
b	1.5 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Rmt	60.00		
c	2.0 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Rmt	20.00		
d	2 TR Cassatte unit ( BEE rating - minimum three star and above)	Rmt	80.00		

3	Supply and laying of Electrical cabling 3 x 2.5 sq.mm polycab make or equivalent (Only single distance will be considered)				
a	1.0 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Rmt	45.00		
b	1.5 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Rmt	70.00		
c	2.0 TR Hiwall split Invertor type( BEE rating - minimum four star and above)	Rmt	25.00		
d	2 TR Cassatte unit ( BEE rating - minimum three star and above)	Rmt	90.00		
4	Rigid PVC drain pipe with 6 mm Heatlon insulation complete with fittings, U traps etc. & as specified to the nearest toilet / drain point with all required. Multi-runs between Indoor & Outdoor units shall be considered as ONE length for the purpose of measurement.(Make: Finolex / Supreme / Prince)				
a	32 mm dia	Rmt	35		
b	20 mm dia	Rmt	30		
5	<b>M.S. Stand work</b>				
	Providing and fixing in position M.S. Stand work for keeping A.C. units, floor or wall mounted. MS sections strong enough to hold the weight of the AC unit, and should be painted with two or more coats of approved enamel paint on a coat of red oxide complete.				
a	1.0/1.5/2.0 TR Split AC	Nos	6		
b	2.0 TR Cassette	Nos	4		
6	Supply and filling of additional REFREGERENT GAS if required	Kg	10		
7	Charges for Core Cuttings & filling the same with cement and other accessories if required	Nos	2		
8	Supply & Installation of Digital/sequential Timer Switch alongwith suitable size enclosure box for ATM room (Schneider / Hager / Siemens / Legrand make as approved by client / consultant)	Nos	1		
<b>Total Low Side Cost (without GST) - B</b>					
TOTAL OF HIGH SIDE EXCLUDING GST - A					
TOTAL OF LOW SIDE EXCLUDING GST - B					
<b>TOTAL (A+B) EXCLUDING GST</b>					
LESS : DISCOUNT (IF ANY)					
<b>GRAND TOTAL (A+B) EXCLUDING GST</b>					
GST extra as applicable					
Date :	Seal & Signature of the contractor				
Place :					