

**Estimate for Civil & carpentry work 4th floor conference room SBI GITC CBD
Belapur**

• Rates are inclusive of material labour wastage, cutting transportation etc.

	DESCRIPTIONS	UNIT	QTY	RATE	AMOUNT
1	Carefully removing existing soft board panels and replacing it with the new ACP panels as per approved colours and make complete the work as per site conditions and instructions of the Bank.	SQFT	800		
2	Repairing the existing false ceiling wooden panels after replacement of AC unit, rates are inclusive of any cutting or carpentry assist require, finishing the same with melamine polish after completion of work complete the work as per site conditions and instructions of Bank.	SQFT	550		
3	Repairing of the Gypsum false ceiling work if required after completion of AC work finished with one or more coat of plastic paint complete the work as per site conditions and instructions of the Bank.	SQFT	150		
4	Providing and fixing in position 8 mm thick writing glass board as per instruction of the Bank.	SQFT	80		
5	Carefully removing existing veneer to column/ceiling complete the work as per site conditions and instructions of the Bank.	SQFT	300		
6	Supplying and fixing in position 2mm thk. Veneer to the column and ceiling if required of approved make and colour as per site conditions finished with melamine polish over it complete the work as per instructions of the Bank.	SQFT	500		
7	Polishing to the table and columns providing and applying melamine polish to the column, table etc	SQFT	500		
	* GST will be paid extra as applicable		TOTAL=		