

FINANCIAL BID OF CIVIL WORK FOR STATE BANK OF INDIA, BUILDING, FOCAL POINT, LUDHIANA.					D.A.C.
SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	EXTERIOR WEATHER PROOF EMULSION PAINT:-				
	Applying three or more coats of Exterior Weather Proof Emulsion Paint (Asian, Nerolac, Dulux) of approved shade including making of ground, rubbing, filling of putty base preparation etc. In case where the surface has been white/color washed, the old white/color wash shall be entirely removed and surface broomed/scrapped down before the newPaint is applied. Rates include cleaning of splashes, stains on floor, window panes etc and scaffolding, if required and for all heights.	20300	Sq.ft		
2	TOILET WALL & FLOOR TILE:-				
	Providing and laying Ceramic wall tiles 300mm x 450mm & Anti skid floor tiles 300mm x 300mm (Johnson, Kajaria, Nitco) 8mm of 1st quality conforming to IS:15622 of approved make in colours such as White, Ivory,Grey,Fume Red Brown. laid on 12 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) pointing the joints with white cement and matching pigment etc., including dismantling of existing floor & wall tiles if any & disposal of malba at appropriate place.				
	Ceramic Tiles For Wall : (12" x 18")	805	Sq.ft		
	Anti Skid Tiles For Floor : (24" x 24")	195	Sq.ft		
3	GRANITE :-				
	Providing and laying Black/Grey Granite stone flooring on steps as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Architect.	50	Sq.ft		
4	PLASTER & FINISHINGS :-				
	Repairs to plaster 1:4 (1 cement : 4 fine sand) of thickness 12 mm to 18 mm in patches of area 2.5 sq.meters including removing the old plaster wherever required and cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	3830	Sq.ft		
5	REINFORCED CEMENT CONCRETE WORK :-				

	Reinforced cement concrete work on floor (4" thick), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement : 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	80	Cu.ft.		
6	REINFORCEMENT :-				
	Providing, laying and binding in position 12mm and 16 mm bars as per drawing provided by the Architect for locker room.	355	Kg.		
7	COLLAPSIBLE/KANCHI GATE :-				
	Providing & fixing in position collapsible steel shutters with vertical channels 20x10x2 mm & braced with flat iron diagonals 20x5 mm size, with top & bottom rail of T-iron 40x40x6 mm, with 40mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer:-	80	Sq.ft		
8	ENAMEL PAINT:-				
	Applying 2 or more coats of enamel paint (Asian, Nerolac, Berger) on Collapsible m.s. kanchi gate & m.s.windows to give even & uniform surface. Rates include cleaning of metal rust.	3900	Sq.ft		
9	FLUSH DOOR (WOODEN) :-				
	Providing and fixing wooden Choukhat & Flush Doors made of Partal Wood inside & 1 mm laminate on both the surfaces , with necessary vertical or horizontle grooves 6mm thick, including steel handle, hinges & hudraulic door closer etc.complete in all respect,as/drgs provided by the Architect.including accesory. (Including the cost of removing the existing Window/Door)	6	No.		
10	M.S. WINDOW :-				
	Providing and fixing factory made ISI marked steel glazed doors, windows and ventilators in walls with 15x3mm lugs 10cm long embedded in cement concrete blocks 15 x 10x10cm of 1:3:6 (1 cement : 3 coarse sand: 6 graded stone aggregate 20 mm nominal size) or with sooden plugs and screws or raw plugs and screws or with fixing clips or with bolts and nuts as required, including fixing of float glass panes with glazing clips and special metal-sash putty of approved make, or metal beading with screws (only steel windows with lugs, glass panes cut to size and glazing clips or metal beading with screws, shall be supplied by department free of cost. (Including the cost of removing the existing Window panes)	195	Sq.ft		
11	5 MM GLASS WITH WINDOW & VENTILATOR				

	Providing and fixing 5 mm toughened glass in windows/Ventilators wherever required with silicon of appropriate company (Dow, Gorcci or its equivalent) Silicon is to be filled on all the 4 sides of window panes. including removal of existing glass & scaffolding complete in all respect.	280	Sq.ft		
12	EUROPEAN WATER CLOSET:-				
	Providing & fixing 1st quality vitreous china white colored Floor mounted European water closet (Hindware- Universal Cat 20012) with 10 ltr. Vitreous china white colored cistern (Hindware) with seat cover & lid, C.p bend, including connecting with existing C.I pipe with CI/PVC,pipe, cutting & making good floor/walls wherever required, complete in all respect. (Including the cost of removing the existing European Water Closet)	4	No.		
13	WASH BASIN:-				
	Providing & fixing 1st quality vitreous china white colored washbasin 56x41cm size (Hindware- Opal Cat no. 10082) size 67x51 cm, with pedestal (Hindware) , I no. C.P Pillar cock (Jaquar – Presmetic) , C.P waste , P.V.C drain pipe, fixing wash basin with M.S bracket, cutting & making good floor walls, wherever required, complete in all respect. (Including the cost of removing the existing Wash Basin)	4	No.		
14	URINAL & URINAL PARTITION :-				
	Providing & fixing 1st quality vitreous chine white colored urinal & urinal partition(Hindware – cat mo. 600002) with matching 5 litre vitreous china white colored auto cistern (Hindware) connecting C.P brass pipes/speaders, removing & stacking existing fixtures, cutting & making good floor/walls, wherever required, complete in all respect. (Including the cost of removing the existing Urinal & Urinal Partition)	2	No.		
15	Providing & fixing 15mm dia CP short body Bibcock (JAQUAR CONTINENTAL- Cat no. 037), with CP wall flange, complete.	12	Nos.		
16	Providing & fixing 15mm dia CP Angle valve (JAQUAR - Cat no. 053), with CP wall flange	12	Nos.		
17	Providing & fixing 15mm dia CP Water jet for WC with connecting CP pipe.	4	Nos.		
18	Providing & fixing CP jali (heavy duty) with CP outer ring.	4	Nos.		
19	Providing & fixing CP Towel rack heavy duty rod with wall hanging rail for towel.	4	Nos.		
20	Providing & fixing CP liquid soap container (JAQUAR make or its equivalent.)	4	Nos.		
21	Providing & fixing 15mm dia PVC pipe, medium class conforming to IS-1239 (JINDAL/ TATA), including necessary fittings like nipples, tee, socket, union (SNW/ UNIQUE make) etc., complete. Rates to include cutting/ chasing walls, floor, fixing pipe & making good the damages with cement mortar, complete in all respect.	50	R.ft		

22	Providing & fixing GI Reducer (SNW/ UNIQUE make) for floor drain, 75x50mm size ,including chasing walls, floor, fixing pipe & making good the damages with cement mortar, complete in all respect.	12	Nos.		
23	Providing & fixing 75/ 100mm Floor trap, complete in all respect.	11	Nos.		
24	Providing and laying in position 4" heavy duty Supreme/Finolex 6kg/cm ² pipe (DIPLAST- ISI marked), including excavating earth, dismantling cement concrete floor, laying pipe, including bend, collar etc., encasing pipe in concrete 1:2:4 (1 cement: 2 coarse sand: 4 coarse aggregate 20mm & down), connecting with existing pipe, including providing collar & jointing with adhesive, re-filling earth, repairing concrete flooring & disposal of malba from site, complete.	40	R.ft		
TOTAL CIVIL WORK					
Seal & Signature Of Vendor					