

BOQ FOR INTERIOR FURNISHING WORKS FOR SETUP OF SBI WEALTH HUB OF STATE BANK OF INDIA, AT ZILA PARISHAD BRANCH, UNDER RBO – 1, BATHINDA.

SI. No.	Description of Item	Qty.	Unit	Rates	Amount
	INTERIOR WORKS				
	PANELING/PARTITON				
	Note: (i) For the works of paneling, full height partitions and low height partitions measurement shall be done only for plain visible surface, no extra cost for extrusions or extra frame work required will be made. The work done above Ceiling, below floor finish level or not directly visible shall not be measured. Also, the works done behind table, side credenza, and low height storage not visible will not be measured. It is the responsibility of the vendor to co-ordinate with other vendors/ bank officials and state/ central departments as required. Vendor to arrange its own electricity supply/ water arrangement etc required for its working & operations. However, if available at site, vendor could use the same. The rates mentioned in the items to include all lead and transportation and no additional payment will be paid on account of lead and transportation charges. The vendor is required to dispose of all the rubbish/ unserviceable material to the nearest dumping ground & no additional payment will be made in this regard. The vendors are advised to visit the site and understand the requirements first, thereafter quote their rates. In case of technical query, the vendor may co-ordinate with the Technical official.				
	(ii) All ply to be sprayed with anti terminate and anti borer spray.				
1	12 MM THICK TOUGHENED GLASS PARTITIONS:	440	Sqft		
	Providing and fixing in position 12 mm clear float toughened Glass partition with patch fittings for the full height glass partitions as per the direction of the engineer-in-charge. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., then toughening the same. The cost to include all hardware (PATCH FITTINGS etc) required of approved equivalent make viz. single corner patch, top and bottom corner patch etc. or as per the direction of the engineer-in-charge, along with etching with sand blasting as per design and drawing. The maximum size of each glass shall be 1200mm to 2000mm x 2400mm to 2700mm or as per the site requirement. The rate is for a finished item of work etc. complete in all respects as directed. The cost to include the cost of beveling and smoothing of the exposed edges of the glass.				
2	12 MM THICK TOUGHENED GLASS DOORS:	73.5	Sqft		
	Providing and fixing in position 12mm clear float toughened glass (Makes-Modi / Asahi / Saint Gobain) for door. The work to include making necessary template for all the glasses and then cutting the clear float glass to correct size, making all the necessary holes, cuts etc., and then toughening the same. The cost to include all hardware required approved make its accessories, top pivot, center lock, 300mm glass door handles (Make Godrej/ SXL C series (Dorma)/ OPF series (Ozone) etc. as per design and drawing. The maximum size of each glass shall be as per the drawing or the direction of the Engineer-in-charge. The rate is for a finished item of work etc., complete as directed.				
3	FLOOR SPRING:	3	Nos.		
	Floor spring (Make Everite/ Dorma/ Godrej) heavy duty of approved make.				
4	TABLES WITHOUT SIDE CREDENZA (Finishing with 1 mm laminate)	4	Nos.		
	Changing of old laminate to new laminate of 1 mm of approved shade (White laminate) of the existing tables in the branch as approved by the Bank Officials of approved make (Sunmica/ Formica/ Merino) & desired design on all the outer visible surfaces of the table. Changing of the wooden lipping of the approved shade as directed by the Bank. The work to include all other necessary repairs/ works if any as directed by the Bank Officials.				
5	SIDE CREDENZA FINISHED WITH 1 mm LAMINATE	4	Nos.		
	Changing of old laminate to new laminate of 1 mm of approved shade (White laminate) of the existing side credenza in the branch as approved by the Bank Officials of approved make (Sunmica/ Formica/ Merino) & desired design on all the outer visible surfaces of the side credenza. Changing of the wooden lipping of the approved shade as directed by the Bank. The work to include all other necessary repairs/ works if any as directed by the Bank Officials.				

6	LOW HEIGHT STORAGE FINISHED WITH 1 mm LAMINATE (2'-6" height)	4	Nos.		
	Changing of old laminate to new laminate of 1 mm of approved shade (White laminate) of the existing low height storage in the branch as approved by the Bank Officials of approved make (Sunmica/ Formica/ Merino) & desired design on all the outer visible surfaces of the low height storage. Changing of the wooden lipping of the approved shade as directed by the Bank. The work to include all other necessary repairs/ works if any as directed by the Bank Officials.				
7	FROST FILM ON GLASS	440	Sqft		
	Providing and fixing at site, Frost Film on the glass after cleaning the glass to the entire satisfaction of the bank Officials/ Project Architect of approved design at the approved location. The vendor to get the location approved from the Engineer – In – Charge/ Project Architect before executing the item.				
8	FLUSH DOOR	1	Nos.		
	Changing of old laminate to new laminate of 1 mm of approved shade (White laminate) of the existing flush door and frame in the branch as approved by the Bank Officials of approved make (Sunmica/ Formica/ Merino) & desired design on all the outer visible surfaces of the flush door including frame. The work to include all other necessary repairs/ works if any as directed by the Bank Officials.				
9	WALL PANELLING FINISHING WITH 1 mm LAMINATE	485	Sqft		
	Providing and fixing of paneling on column/wall. Framing shall consist of Heavy duty Aluminum Box Sections 50mm x25 mm x1.5 mm wall thickness (Make Jindal/ Hindalco/ Indal) with maximum spacing @ 600mm c/c both ways horizontally and vertically on the column/wall. This framing would be covered by 8mm HDF Ply (Moisture content- < 8 % Water Absorption 5% after 2 Hours Soaking)(Make. GREENPLY/ Century / Duro) and finished with 1.0 mm thick Laminate (white laminate) (Make- Sunmica/ Green lam/ Century/ Merino) of desired shade design and gloss of approved makes. Wooden molding, lipping etc. shall be provided wherever required as per drawing in desired shade. The work shall also include the cost of making cutouts for the electrical switches, lights, switch boxes etc. and provision for laying conduit for electrical/ telephone/ Data cabling etc.				
10	ROLLER BLINDS	65	Sqft		
	Providing, Supplying & Installing Roller blinds of approved shade (White) and approved make at the desired location as approved by the Bank Officials. The item to include necessary fittings etc and installation of the same in all respects.				
11	LOW HEIGHT PARTITIONS BOTH SIDE (1 MM) LAMINATES	4	Nos.		
	Changing of old laminate to new laminate of 1 mm of approved shade (White laminate) of the existing low height partitions in the branch on both the sides with complete safety as approved by the Bank Officials of approved make (Sunmica/ Formica/ Merino) & desired design on all the outer visible surfaces of the low height partition. Changing of the wooden lipping of the approved shade as directed by the Bank. The work to include all other necessary repairs/ works if any as directed by the Bank Officials.				
12	DISMANTLING	1	Nos.		
	Dismantling of existing low height wall paneling including framing, low height glass partition, low height partition and any other dismantling in the branch as directed by the Bank Officials. The item to include disposing off the dismantled material to the nearest dumping ground.				
	Total value of works				

GST will be paid extra as applicable