

PRICE BID for INTERIOR DESIGN & FURNITURE WORKS FOR STATE BANK OF INDIA AT RBO PATNA CENTRAL

S No.	Particular of Items	Unit	Quantity	Rate	Amount
1	<u>LOW HEIGHT PARTITION</u>	Square meters	40.07		
	Providing and fixing low / half height partitions up to 4' 0" with double skin paneling up to 3'-0" and 12 mm thick toughened glass of approved make above frameless on the top and sides and sturdily fixed at the bottom on a polished teakwood frame all complete job with all other specifications and details to be as per the design i.e. shown in sides of low-height counters all complete work. All complete work as per and specifications and direction of Bank.				
2	<u>8 MM Thick glass with all necessary hardware,polish etc. all complete for table counters of approved make.</u>	Square meters	30.67		
3	<u>WORK STATIONS / TABLES</u>				
	(a). Making and erecting Desk-top with provision of wire manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWP grade block board of Green / Century /Mayur or equivalent top laminated with 1.0 mm blue / white high gloss laminate of Green/ Marino / Century or equivalent. All edges shall be covered with teak wood lapping and front-edge shall be covered with half round molding. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. All wooden surfaces shall be well polished with melamine/sprit polish.				
	(b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWP grade ply of Green/ Century or equivalent front shall be clad with 1.0 mm thick high gloss blue /white laminate of Green lam / Century or equivalent side edges of drawers and cupboard shall molded in round shape with Gamhar wood. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per specifications and direction of Engineer-in-charge /Bank.				
	(c). Providing and fixing key board tray (as per design and specification at 1- above) tray and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers.				
	<u>(i) L Shaped 1350 mm x 900 mm x 750 mm</u>	Nos.	23.00		
	<u>(ii) 'L' shaped 1500 mm x 1650 mm x 750 mm</u>	Nos.	3.00		
	All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.				
4	<u>FOOT REST:</u>	Nos.	26.00		
	Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings top clad with rubber mat. All inner portions shall have a coat of mat finish ena-mel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. Materials shall be above at item –10.				

5	<u>LOW TYPE STORAGE CABINET:</u>	Square meters	30.29		
	Making and fixing low type storage cabinet with drawer and cupboard with shelf as per the drawing / design all made of 19 mm thick BWP block board of Green/Century /Mayur or equivalent top and front laminated with 1.0 mm thick blue / white high glossy laminate of Green/Marino /century or equivalent top edges shall have Gamhar wood moulding. Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be mela-mine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per specifications and direction of Engineer-in-charge /Bank.				
6	<u>Providing and fixing self adhesive Sparkle series Frosted Film and/or one way vision film of 3 M make as per design :</u>	Square meters	18.22		
	The film are to pasted on main glass door & other glasses as directed, cut & fixed as per design including the Bank's logo. Supporting cash memo/bills are to be produced for payment of this item including certificate from the dealer certifying use of the product. Executed area of the film pasted on glasses shall be measured for finished work.				
7	<u>ROLLER BLINDS</u>	Square meters	23.42		
	Providing & fixing of roller blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows & opening of B.M's chamber. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in-charge /Bank.				
8	<u>PVC FLOORING</u>	Square meters	225.81		
	Providing and laying waterproof PVC laminate flooring (thickness of approx 1.5-2.0 mm) complete of approved make as directed by bank				
9	<u>BRICK WORK (for UPS Room)</u>	Cubic meters	6.50		
	Brick work with common burnt clay machine moulded modular bricks of class designation 12.5 in exposed brick work including making horizontal and vertical grooves 10 mm wide 12 mm deep complete in cement mortar 1:6 (1 cement : 6 coarse sand).				
10	<u>WALL PUTTY</u>	Square meters	30.96		
	Providing and applying wall putty of 2 mm average thickness over plastered & white washed walls & ceiling to prepare the surface even and smooth compete as per direction of Bank.				
11	<u>Providing two or more coats of Plastic emulsion paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job.</u>	Square meters	30.96		
12	<u>CEMENT PLASTER (IN FINE SAND)</u>	Square meters	30.96		
	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)				
13	<u>Dismatling work of work stations,partitions and stacking of the material within a lead upto 100 m as directed by bank</u>	Job	1.00		
	GRAND TOTAL				
	<u>Amount in Words: Rupees</u>				
	NOTE :- * PRICE INCLUDES TRANSPORTATION, LIFTING, FIXING CHARGES AND OTHER TAXES AS PER GOVERNMENT RULES * ALL OTHER TERMS AND CONDITIONS AS PER INDIAN STANDARDS/SPECIFICATIONS * ABOVE PRICE IS EXCLUDING GST * GST PAID EXTRA BY THE BANK AS PER RULE.				
					SIGNATURE (AUTHORIZED SIGNATORY)