

**PRICE BID**

**Name of the work: INTERIOR & FURNISHING WORKS AT SBI, GLOBAL NRI CENTRE, PATIALA**

S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
1	<b>FALSE CEILING -(MINERAL FIBRE TILE):</b>				
	Providing & fixing Armstrong false ceiling RH-99 with 600x600x16 mm Fine Fissured Beveled Tegular Edge false ceiling laid in Armstrong silhouette grid system. The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee( with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc. Rates include dismantling existing false ceiling and removal of malba from site, complete in all respect.	440.00	sq.m.		
	<i>MAKE: Armstrong, St. Gobain (India Gypsum)</i>				
2	<b>GYPBOARD FALSE CEILING:</b>				
	Providing and fixing suspended false ceiling including steps as per design with 12.5mm tapered edge Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level. The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MFS) and the outer edges to gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section (MFS of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together.	733.00	sq.m.		
3	<b>COVE IN CEILING:</b>				
	Providing and Fixing of Cove in Gypsum Board with specifications same as item No.2	96.00	mtr		

4	<b>EXTRA FOR PROVIDING VENEER WITH POLISH IN CEILING</b>				
	Providing and fixing 4mm thk. VENEER in ceiling over 12mm thk. commercial ply screwed (IN PLACE OF GYPBOARD) to GI ceiling sections work as item number 2 above. The work includes providing grooves as per pattern, spirit polished of approved shade on the veneer surface. Payment shall be made for the visible finished area. The work should be complete as per instructions of Architect or Engineer in charge.	98.00	sq.m.		
5	<b>WOODEN RAFTER (2"x3") SUSPENDED CEILING</b>				
	Providing and fixing wooden rafters made of Beech Wood of size 2"x3", suspended in false ceiling using suitable hangers/channels to provide suspended ceiling which is level & plumb. The rafters to be fixed at a regular spacing as per design / drawings & provided with spirit polish on all surfaces, complete in all respects. The length of rafters installed shall be measured for payment.	161.00	mtr		
6	<b>WALL PANELLING (VENEER WITH POLISH):</b>				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishings as per drawing and instructions.				
	All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza, storage etc.				
a)	Panelling with 4.0MM thick veneer with polish	192.00	sq.m.		
7	<b>ACOUSTICAL / FABRIC PANELLING</b>				
	Providing and fixing paneling over partition made out of 12MM thick ply panels (as per size given) with 40density foam 1" thick fixed & fabric fixed neatly & firmly over it. The fabric panel shall be fixed to partition/s using suitable hardware as per instructions of the Architect / Engineer in charge. The joints between the panels shall be provided with SS/Copper finished T-profiles, complete in all respects. All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly	25.00	sq.m.		

	designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza , storage etc.				
	Basic Cost of Fabric = Rs. 300/mtr				
8	<b>FULL HEIGHT PARTLY GLAZED WOODEN PARTITIONS &amp; DOORS</b>				
	Full Height partly Glazed (with etching) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides. Also 1-1/2" x5/8" teak wood beading shall be provided on both sides of 8mm thk. glass with etching work as per interior details where ever specified. The rate shall also include for providing grooves in laminate & wood.	153.00	sq.m.		
	Wherever applicable, the doors shall be a part of full height partitions & shall be provided with 35mm thick commercial block board, with laminate 1.0mm thick on both side, as per pattern & with groves as per design. 38mmx6mm thick teakwood lipping shall be provided all around the edges of the door & finished with spirit polish, complete in all respects. Basic hardware like mortice lock / dead lock / handles, hinges, door stopper shall be a part of the door & will not be paid extra,				
	<i>Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</i>				
9	<b>LOW HEIGHT WOODEN PARTITION WITH LAMINATE</b>				
	Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides. Also 3"x5/8" teak wood section shall be provided on the exposed edges of the partitions, including provideing grove for 12mm thick glass wherever specified. The rate shall also include for providing grooves in laminate & wood.	340.00	sq.m.		
	<i>Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</i>				

10	<b>STORAGE CABINETS</b>				
	Providing & fixing storage cabinets, 18" deep & height as specified, made out of 19mm thick commercial plywood, including the inner shelves & shutters. The visible external surface shall be provided with 1.0mm thick laminate of shade specified, whereas internal surface including both sides of shelves shall be provided with balancing laminate of 0.8mm thickness. All the exposed edges of shutters & shelves shall be provided with beechwood lipping 5mm thick with clear polish finish. The shelves shall be spaced at approx. 15" vertically/as per drawings. The cabinets shall be complete in all respects with handles, catchers, locks, tower bolt(inside) etc.				
	In low height / back storages, drawers shall be provide as per design, running on telescopic channels. Internal surfaces shall be provided with 0.8mm th. Balancing laminate., whereas the visible top shall be provided with 1.0mm thick laminate				
a)	FULL HEIGHT STORAGE	82.00	sq.m.		
b)	4'-6" HIGH STORAGE	67.00	sq.m.		
c)	3'-0" BACK STORAGE	36.00	sq.m.		
11	<b>TABLES &amp; WORKSTATIONS</b>				
	Providing & Fixing tables / workstations made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); with 40 mm X 6 mm thick beech wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer/ electrical cables at appropriate place will be made in the top surface of the table. Teak wood lipping will be provided on all the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 fixed on channels(EBCO/ HARRISON/ GODREJ). A full depth CPU shelf 15" wide shall be provided at one side of table underneath the working top, which will be made of 19mm thick commercial ply finished with laminate 1mm thk. 15" wide drawer cabinet with one lockable drawer running on side mounting drawer slides (channels)& one shutter below, made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood ( ISI marked-GREEN (Ecotech)/ CENTURY ( Sainik), bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Inside of drawers & Non-Visible/ inside surfaces i.e. inside / leg-space of table, inside of cupboard will have white coloured 1mm laminate. Teak wood edges / lipping / beading shall be Spirit polished.				

a)	AGM/DGM desk of size 8'x3'x2'-6" with side return of size 5'-6"x1'-9"x2'-3"	2.00	no.		
b)	Officer Table 6'-0"x2'-6"x2'-6"	6.00	no.		
c)	Workstation 5'-3"x2'-6"x2'-6"	63.00	no.		
d)	Running counter -2'-6"wide x 2'-6" high for dipatch & sorting area	10.50	mtr.		
e)	Meeting Room /VC table: 7'-0"x3'-6"x2'-6"	2.00	no.		
f)	Reception Table - Curved 6'-6" (av) x 2'-3" including a drawer cabinet with 3 no. drawers running on telescopic channels.	1.00	no.		
g)	Conference Table 15'-0" x 6'-0" x 2'-6"	1.00	no.		
h)	Dining Table : 4'-6"x2'-6"x2'-6" with SS pipe frame & laminated table top having 1.5" edges all around, provided with 40mmx6mm beechwood beading, with polish, complete in all respects.	5.00	no.		
i)	Running Counter - dining room: 1'-9" wide	3.00	mtr.		
12	<b>SIDE CREDENZA:</b>				
	Providing & fixing Side credenza 3'6" long & 15" deep, made of 19 mm thick commercial ply ( ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have two drawers on top, horizontally running on side mounting drawer slides (channels) of EBCO/ GODREJ make, & inner surfaces finished with 1mm thk. white/off white laminate. The remaining part of the credenza will have cupboard with shutters and one shelf, with handle /knob and magnetic catcher. All non visible/inside surfaces shall be finished with 1mm thk. white/off white laminate and teak wood edges/ lipping/ beading shall be Spirit polished with matching pigment.				
	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - (W X D X H)				
a)	SIZE: 3'-6" X 1'-6" X 2'-3"	20.00	sq.m.		
13	<b>3-DRAWER PEDESTAL FOR RUNNING COUNTERS</b>				
	Providing & fixing drawer pedestal of size: 16"x24"x28.5" (H), made of 19 mm thick commercial ply ( ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The pedestal will have 3 drawers orunning on side mounting drawer slides (channels) of EBCO/ GODREJ make, & inner surfaces finished with 1mm thk. white/off white laminate. All non visible/inside surfaces shall be finished with 1mm thk. white/off white laminate and teak wood edges/ lipping/ beading shall be Spirit polished with matching pigment. Locks shall be provided in all 3 drawers,	6.00	no.		

14	<b>12mm THICK FIXED TOUGHNED GLASS IN PARTITIONS</b>				
	Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors of 304 Grade / Wooden beading, fixed in position, with etching / filming, as per interior details/instruction of the Achitect/Engineer in charge.	30.00	sq.m.		
15	<b>12MM THICK TOUGHNED GLASS DOORS WITH PATCH FITTINGS &amp; ETCHING/LOGO:</b>				
	Providing & fixing frameless fully glazed 12 mm thk. toughend glass doors, single leaf glazed Toughned door of size approximately, 1200mm (to 750mm) X 2100 mm all sides edge grained, polished to be fixed on patch fittings. The glass door shall be provided with patch fittings such as PT 40, 10, US 10, PT 24, pull handle 450 x 38 and floor spring conforming to DIN EN 1154. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete	12.00	sq.m.		
	<i>NOTE: Rates include Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" SS door handle (both sides) etc. all complete.</i>				
16	<b>PIEGONHOLE CABINET (18'-0" X 4'-6" X 1'-0")</b>				
	Providing & fixing piegonhole cabinet with open compartments of overall size 18'-0" x 2'-6" x 1'-0" deep, fixed on partition / wall, made of 19mm thick commercial plywood. All visible surfaces to be provided with 1.0mm thick laminate (both sides of shelves & vertical dividers). The visible edges of ply shall be provided with 20x6mm beechwood beading with polish finish, comoplet in all respects.	4.20	sq.m.		
17	<b>WPC LOUVERS - PANELLING</b>				
	Providing & fixing interlocking WPC wall panel of 2700mmx160mmx240mm fixed to the wall & partition with suitable glue. Complete design -138 of EURO PARATIK or equivalent. Of LEBEN/MARIA DÉCOR	48.00	sq.m.		
18	<b>PLANTER BOX</b>				
	Supplying running Planter Box 2'-0" wide x 1'-9" high, made of 19mm comm. Ply with 1mm laminate and polished beech wood moulding 25x 8 mm on top & lining of aluminum sheet on the inner surfaces, complete in all respects	11.20	mtr.		
19	<b>WOODEN BOXING AT MAIN ENTRANCE</b>				
	Providing & fixing wooden boxing on wall/columns as per details, using 19mm thick commercial ply, with 1 mm thick laminate fixed as per pattern, complete in all respects.	14.00	sq.m.		

20	<b>WALL MOUNTED TV UNIT</b>				
	Providing & fixing Wall Mounted TV unit of size 6'x3'-6"x 1'-0" made out of 19mm thick commercial plywood. The unit shall have open shelf/box fo size 6'-0"x1'-0"x1'-0" at the bottom for keeping set top box / other gadgets. The TV units shall be made of 19mm thick commercial ply, with 1.0mm thick laminate on all visible surfaces. The edges of ply shall be provided with 40x6mm thick beechwood beading, with polished finish.	1.00	no.		
21	<b>LACQUERED GLASS PANNELLING:</b>				
	Providing & fixing 6mm lacquered glass (St. Gobain "Planileque" or equivalent), fixed to walls over a layer of 12mm thick commercial ply/mdf using clear silicone adhesive, complete in all respects	20.00	sq.m.		
22	<b>DOOR CLOSER:</b>				
	Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej / Dorma / Hardwyn make, to Doors complete in all respects.	5.00	no.		
23	<b>ROLLER BLINDS OF VISTA / MAC MAKE</b>				
	Providing and fixing Rolling Roman blinds made of fabric of approved design and shade, as approved by the Architect, including rolling channels and other fitting complete in all respect, as per manufacturer's specifications. Make : FARRARI/ VISTA/ MARVEL.	82.00	sq.m.		
23	<b>CARPET FLOORING IN CONFERENCE ROOM</b>				
	Supply & installation of 100% commercial grade nylon carpet tile of 500x500mm of solution dyed nylon 6 (AquafilEconyl) quality or equivalent, Machine Gauge 1/10" or more and having backing of glass fiber + PVC and made of basic fabric of Nonwoven Polyester , total height of 7 mm or more, smoke density( ASTM E 662) less than 450, anti static less than 1.0kv (JIS-L4406 STROLL 23 C. degree 25%R.H.), electrostatic propensity - maximum average 0.5kv (AATCC 134) Color fastness to light- rating 5.0= No change (AATCC 16) critical radiant flux - (ASTM E 648) Class 1 average CRF 0.48 / cm2 or higher certified It is absolutely mandatory that the manufacturer has valid certifications of CRI PLUS certified, GLP 8200, certified from Singapore Green Building Council, certified of Japanese industrial standard (JIS) Mark.	43.00	sq.m.		
	Make: Shade TC4301 of ECONYL (Fuji Series) by Japan Carpet Company or equivalent of Myfloor / Welspun / Modulus				
25	<b>BANK LOGO &amp; LETTERS</b>				
	Providing , making to shape and size ( as per the design provided) and fixing to position SBI bank logo made out of ACP sheet of bank	1.00	no.		

	blue color ( pre approved) fixed to position with aluminium framework with required screws, nuts bolts and hooks etc.				
a)	SBI logo 10" dia (SS FINISH) / English letters 10" high (SS FINISH)	4.00	no.		
b)	English letters 6" high (SS FINISH)	11.00	no.		
	TOTAL				
Amount in words:					

Signatures of the Contractor with Seal