

PRICE BID OF AIR CONDITIONING WORK FOR SBI MATAR BRANCH					
Sr.No.	Description	QTY	UNIT	RATE	AMOUNT
[I] MACHINE PART					
AC EQUIPMENT WITH - INVERTER COMPRESSOR					
1	Supply & providing of 4 way Inverter Cassette Type AC ceiling mounted cassette unit with indoor and out door having eco friendly refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have copper condensor Unit, Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries / Toshiba / Trane / Voltas /Bluestar.				
1.a	Inverter 4-way Cassette of 4.00 TR (BEE 3 Star rating)	2	NOS		
2	Supplying & providing of Hi-wall Inverter Split Type AC with high wall mounted indoor and out door unit. having eco friendly refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have copper condensor Unit, Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries/ Toshiba/ Trane/ Voltas/ Bluestar [Mini 3 Star rating as per BEE Guide Line 2022]				
2.a	Inverter Hi-wall Split AC of 2.00 TR	1	NOS		
2.b	Inverter Hi-wall Split AC of 1.50 TR	1	NOS		
TOTAL FOR PART- I					
[II] LOW SIDE WORK					
1	Installation of IDU & ODU of 4.00 TR / 3.00 TR / 2.00 TR ceiling mounted cassette unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	2	NOS		
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	2	NOS		
3	Removing and Reinstallation charges for existing 2.00 TR / 1.50 TR / 1.00 TR High wall mounted split A/C at new location including connection servicing & gas filling complete as directed.[Entire new copper piping and drain shall be paid as per item No 5] Shifting Existing Premises including indoor and outdoor etc complete as directed	2	NOS		
4	Refrigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 4 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make	15	RMT		
5	Refrigerant piping - insulated 0.80mm wall thicknees copper tube of Mandav/ Totalline make between indoor to out door unit beyong 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make (copper pipe concealed in inside wall)	10	RMT		
6	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	15	RMT		
7	Providing of Fabricate and Fixing M.S stand Plateform for keeping outdoor unit of Cassette /Split A/C. with M.S cage for locking of outdoor unit of Cassette/Split A/C. including painting [Drawing should be prepared by the vendor and approved by the Architects]	60	KG		
8	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of Split A/C. (Redy made)	4	NOS		
TOTAL FOR PART- II					
TOTAL (I + II) A					
[III] REMOVING AND BUY BACK					
	Cassatte AC 3 tr	3.00	nos		
	Split AC 1/1.5 tr	2.00	nos		
AMOUNT BUY BACK PART - III					
GRAND TOTAL (A - III)					