

B	C	D	E	F	G	
PART-2						
PRICE BID						
TENDER FOR AIR-CONDITIONING WORKS AT PROPOSED SBI SINAPALI ADB BRANCH						
Tender No. ZO/SAM/R-V/AC/2023-24/05						
Dated 15.12.2023						
2						
3	S. No	Item Description	Quantity	Unit	Rate	Amount
4					in (Rs.)	in (Rs.)
5	A	Hi-side: Supply of AC Machine				
6						
7	1	Supply of Ceiling suspended four-way Cassette type Split Air-conditioner unit of following capacity having one indoor unit, one outdoor unit with compressor with R410/R32 eco-friendly gas, Thermo sensor temperature control ,auto air swing ,multifunctional cordless remote having condensor coil copper only.				
8	b	3 TR Inverter Cassette type Split Air-conditioner, min. BEE 3 Star Rated	4	Nos		
9						
10	2	Supply of wall mount type Hi-wall Split Air-conditioner unit of following capacity one-way one indoor unit, one outdoor unit with single compressor with R410/R32 eco-friendly gas , Thermo sensor temperature control ,auto air swing ,multifunctional cordless remote having condensor coil copper only. cost include three meter copper pipe				
11	a	1.5 TR Inverter Hi-wall Split AC , min. BEE 5 Star rated	3	Nos		
12	b	1 TR Inverter Hi-wall Split AC , min. BEE 3 Star rated	2	Nos		
13	A	Total estimated price for supply of units				
14						
15						
16	B	Low Side: Installation, Testing and Commissioning & Related low side work	QTY.	UNIT	RATE	AMOUNT
17					in (Rs.)	in (Rs.)
18	1	Supply and fixing of Copper pipe (both liquid & suction) line duly insulated with Class "O" fire retardant 6 mm sleeve type elastomeric nitrile rubber insulation all complete as per standard specification and practice and instruction of Engineer-in charge as per site conditions, with proper saddling (S.S Saddle) on wall / terrace including making good the damages with cement mortar 1:2:4 on walls /floor with similar finish. Alu. foil membrane shall be applied to provide resistance against breakdown due to UV radiation for exposed portion of the rubber insulation with Nitrogen testing (totally sealed - in case of proposed machine). It shall be in total clamping manner above false ceiling & in total concealed manner below false ceiling level. From the structural ceiling it should hang or shall be fixed on wall / beam etc. with clamps & the distance between two clamp shall be less than 1 meter Copper line sizes for cassette type (Suction line & Liquid line - 5/8" & 3/8") (Liquid line & Suction line -3/4" & 3/8"), for cassette type A/C (Liquid line & Suction line -5/8" & 1/4")	85	RMT		
19	2	Supply , installation, Testing & Commissioning of suitable Refrigerant piping (both liquid & suction) with soft drawn copper pipe & duly insulated with required insulation with suitable size saddles on the surface of the wall or suspension hooks from the ceiling, as required at site for Split AC (Liquid line & Suction line -1/2" & 1/4")	40	RMT		

	B	C	D	E	F	G
20	3	(i)Laying of electrical Cabling from indoor to the outdoor unit; considering as per required at site	140	RMT		
21	a	2.5* 3 core/1.5* 4 /2.58 4 core				
22	4	Supply and fixing ISI mark UPVC pipe 25mm/32mm dia with elbow, tee socket for condensate water drainage line with 6 mm nitrle insulation for various units in clamping manner above false ceiling and in concealed manner below false ceiling. From structural ceiling it should hanged using self threaded rods or shall be fixed on wall /beam etc. with clamps & the distance between 2 clamps shall be less than 1 meter. It shall not be placed over the false ceiling nor it shall be fixed with false ceiling members. It shall be laid required gradient for easy disposal of the drain water & testing shall be done before filling the zaries. The drain line shall not be laid in the floor (except toilets & other utility areas where there are no electrical lines in the floor). It should be connected to nearest rain water pipeline or drain as per site conditions Make: Supreme/National/Prince or equivalent.	150	RMT		
23	5	Supply and fixing of M.S stand wall/ floor mounting brackets suitable for holding the outdoor units structure made of M.S angles for installation of outdoor unit with anti-vibration pad including grouting on wall /floor etc as may be required depending upon site condition and as per the instruction. Grouting to be done by cutting necessary holes and grouting with M-12 anchor fasteners/ cement concrete 1:2:4 and making good the damages with similar finish, two coats of synthetic enamel paint over a coat of metal primer.	4	NOS		
24	6	Providing & Fixing of sutable size powder coated Metal wall/floor mount Stand for outdoor Condensing unit for split AC.	5	NOS		
25	7	Standard Installation and testing of 3TR cassatte type machines including indoor & outdoor machine erection, first Oil & Gas charging, installation & commissioning Including top and plug, vacuumissing, nitrogen pressure testing (as applicable).	4	NOS		
26	8	Standard Installation and testing of 1.5 TR Hi-wall split ACs type machines including indoor & outdoor machine erection, first Oil & Gas charging, installation & commissioning Including top and plug, vacuumissing, nitrogen pressure testing (as applicable).	5	NOS		
27	9	Providing and fixing wall mounting 4KVA automatic stabliser of ELPOWER/Microtake make/V-Guard (Input Voltage- 130V-270V, Output Voltage-230V) including all labour and material for 1.5 TR AC	5	NOS		
28	B	Total Low side Price				
29						
30	C	TOTAL FOR SUPPLY, INSTALLATION AND COMMISSIONING (ITEM A + B)				
31						
32		Note : GST shall be extra as applicable.				
33						
34	D	Comprehensive Annual Maintenance Contarct (CAMC) after expiry of 1 year warrenty Period	Total Capacity	Unit	Rate/TR in Rs.	Amount in Rs.
35	a	2nd Year	18.5	TR		
36	b	3rd Year	18.5	TR		
37	c	4th Year	18.5	TR		
38	d	5th Year	18.5	TR		
39	D	Total AMC value in Rs. for 4 Years				

	B	C	D	E	F	G
40	E	TOTAL FOR SUPPLY, INSTALLATION , COMMISSIONING AND AMC (ITEM C + D) excluding GST				
41		Net Tender Amount in words : Rupees'				
42		TERMS & CONDITION:				
43	1	The quoted prices shall be firm and inclusive of all duties, transportation, handling, loading and unloading at site, road permit, etc and no extra will be permitted. Only GST will be paid extra on Hi-Side , Low Side and AMC as applicable.				
44	2	THE CONTRACTOR SHOULD DEPUTE ONE PERSON AT SITE FROM START OF WORK TO FINISH FOR GIVING TEMPORARY CONNECTIONS & ATTENDING PROBLEMS				
45	3	THE CONTRACTOR SHOULD WORK ACCORDING TO THE FINAL LAYOUT.				