

<b>SCHEDULE OF QUANTITIES</b>			
<b>AIR CONDITIONING WORKS</b>			
<b>AT NEW PREMISES OF Y. DONDA PETA BRANCH</b>			
S. No.	Description of item/ work	Quantity	Unit
<b>A</b>	<b>WALL SPLIT ACs :</b>		
1	Supply of <b>Inverter Model Hiwall split Air Conditioners</b> (minimum BEE 3 star rated Airconditioner) with Full Copper Condensor coils and Rotary type compressor sufficiently filled with Ozone friendly R32/ R410 Refrigerant Gas, with 3 mtrs of Copper piping (Covered with 9 mm thick closed cell nitrile rubber foam), Cordless remote & other fasteners etc.		
a	2.0 (1-Ph) TR (For Banking Hall)	3	Nos
b	1.5 (1-Ph) TR (For Branch Manager room)	1	Nos
c	1.0 (1-Ph) TR (For Cash Officer room & ATM)	4	Nos
2	Supply of <b>Voltage Stabilizers</b> for the above Airconditioner as per the following ratings.		
a	5 kVA	3	Nos.
b	4 kVA	1	Nos.
c	3 kVA	4	Nos.
3	<b>Installation, Testing &amp; Commissioning</b> of the following Air Conditioners along with the necessary accessories completely as per standards		
a	2.0 (1-Ph) TR (For Banking Hall)	3	Nos
b	1.5 (1-Ph) TR (For Branch Manager room)	1	Nos
c	1.0 (1-Ph) TR (For Cash Officer room & ATM)	4	Nos
4	Supply & fixing of <b>Support structure for outdoor units made of M S Metallic Structures</b> coated with non rustic paint as per the site conditions with necessary hardware and fasteners for the following AC units.		
a	2.0 (1-Ph) TR (For Banking Hall)	3	Nos
b	1.5 (1-Ph) TR (For Branch Manager room)	1	Nos
c	1.0 (1-Ph) TR (For Cash Officer room & ATM)	4	Nos
5	Supply, installation, testing and commissioning of Refrigerant <b>Piping (Liquid &amp; Suction Soft Drawn Copper refrigerant piping)</b> covered with Class-1, 9mm thk closed cell nitrile rubber foam wrapped with 0.5mm thick PVC Tape for above Airconditioners for interconnecting the indoor unit and OD Unit, to be suspended from the ceiling (where ever necessary) with proper supports, clamps and a piece of PVC pipe within the clamp to place the copper pipe.	48	Rmt
6	Supply and installation of <b>Electrical &amp; Control Cables</b> of suitable size (Only one length will be will be considered even for multiple lines).	63	Rmt

7	Supply & fixing of <b>Flexible PVC conduit</b> of 0.5 mm thick and suitable dia for the refrigerant piping running in Out door areas to wrap over the nitrile foam gasket of the Copper pipe exposed to weather.	36	Rmt
<b>B</b>	<b>OTHER WORKS :</b>		
8	Supply, installation, testing and commissioning of following size <b>UPVC Drain pipe covered with nitrile rubber foam</b> and PVC tape wrapped on it (for the length within the premises & not required in Out door area), with 'U' trap at the end.		
a	25mm dia, 2 mm thk	45	Rmt
b	20mm dia, 2 mm thk	27	Rmt
	<b>GRAND TOTAL (A+B):</b>		

**Note:**

1. GST as applicable shall be paid extra.
2. All materials shall be selected by the SBI officials or Engineer-in-charge before execution.
3. All the quantities are approx and executed as per site requirement.
4. The Bank reserves the right to select any of the brands indicated in the "List Makes" in case of delay in delivery of ordered 'make of item'.
5. The contractor cannot claim anything extra if the Bank changes the make but will accept approved make.
6. Bidder shall visit/ inspect the site before quote.

Rate (in Rs)	Amount (in Rs)
	0
	0
	0
	0
	0
	0
	0
	0
	0
	0
	0
	0
	0
	0

	0
	0
	0
	<b>0</b>

ecution.

: of Approved

thin the list of