

SCHEDULE OF QUANTITIES

AIR CONDITIONING WORKS

AT NEW PREMISES OF RAMBILLI BRANCH

S. No.	Description of item/ work	Quantity	Unit
A	WALL SPLIT ACs :		
1	Supply of Inverter Model Hiwall split Air Conditioners (minimum BEE 3 star rated Airconditioner) with Full Copper Condensor coils and Rotary type compressor sufficiently filled with Ozone friendly R32/ R410 Refrigerant Gas, with 3 mtrs of Copper piping (Covered with 9 mm thick closed cell nitrile rubber foam), Cordless remote & other fasteners etc.		
a	2.0 (1-Ph) TR (For Banking Hall)	3	Nos
b	1.5 (1-Ph) TR (For Banking Hall & Branch Manager)	3	Nos
c	1.0 (1-Ph) TR (For Cash Officer & ATM)	3	Nos
2	Supply of Voltage Stabilizers for the above Airconditioner as per the following ratings.		
a	5 kVA	3	Nos.
b	4 kVA	3	Nos.
c	3 kVA	3	Nos.
3	Installation, Testing & Commissioning of the following Air Conditioners along with the necessary accessories completely as per standards		
a	2.0 (1-Ph) TR (For Banking Hall)	3	Nos
b	1.5 (1-Ph) TR (For Banking Hall & Branch Manager)	3	Nos
c	1.0 (1-Ph) TR (For Cash Officer & ATM)	3	Nos
4	Supply & fixing of Support structure for outdoor units made of M S Metallic Structures coated with non rustic paint as per the site conditions with necessary hardware and fasteners for the following AC units.		
a	2.0 (1-Ph) TR (For Banking Hall)	3	Nos
b	1.5 (1-Ph) TR (For Banking Hall & Branch Manager)	3	Nos
c	1.0 (1-Ph) TR (For Cash Officer & ATM)	3	Nos
5	Supply, installation, testing and commissioning of Refrigerant Piping (Liquid & Suction Soft Drawn Copper refrigerant piping) covered with Class-1, 9mm thk closed cell nitrile rubber foam wrapped with 0.5mm thick PVC Tape for above Airconditioners for interconnecting the indoor unit and OD Unit, to be suspended from the ceiling (where ever necessary) with proper supports, clamps and a piece of PVC pipe within the clamp to place the copper pipe.	24	Rmt
6	Supply and installation of Electrical & Control Cables of suitable size (Only one length will be will be considered even for multiple lines).	27	Rmt

7	Supply & fixing of Flexible PVC conduit of 0.5 mm thick and suitable dia for the refrigerant piping running in Out door areas to wrap over the nitrile foam gasket of the Copper pipe exposed to weather.	30	Rmt
B OTHER WORKS :			
8	Supply, installation, testing and commissioning of following size UPVC Drain pipe covered with nitrile rubber foam and PVC tape wrapped on it (for the length within the premises & not required in Out door area), with 'U' trap at the end.		
a	25mm dia, 2 mm thk	27	Rmt
b	20mm dia, 2 mm thk	21	Rmt
9	Supply and fixing of 40-45 mm PVC casing and capping of non perforated type and White colour finish including laying of refrigerant pipes and drain pipes with all other accessories as per the instructions of Banks Engineer.	12	Rmt
GRAND TOTAL (A+B+C):			

Note:

1. GST as applicable shall be paid extra.
2. All materials shall be selected by the SBI officials or Engineer-in-charge before execution.
3. All the quantities are approx and executed as per site requirement.
4. The Bank reserves the right to select any of the brands indicated in the "List of Approved Brands" in case of delay in delivery of ordered 'make of item'.
5. The contractor cannot claim anything extra if the Bank changes the make but with approved make.
6. Bidder shall visit/ inspect the site before quote.

	0
	0
	0
	0
	0.00

ution.

oved Makes”

in the list of